

BOQ FOR FURNISHING Works for Part Re-modelling of Guwahati Regional Office (2nd Floor) & Shifting of Conference & other Rooms on Upper Floor (4th Floor)

SR.NO	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
A	PARTITIONS				
	NOTES				
i	The rate shall be include of frame work above false ceiling level. Measurement should be taken up to false ceiling level and visible portion only.				
ii	Basic rate of Laminate shall be considered as Rs 35/SFT				
iii	Basic rate of veneer shall be considered as Rs 135/ sft				
iv	Basic rate of Solid Surfaces (CORIAN) 6mm thk shall be 1150/ sft, and for 12mm shall be 1800/ sft				
1	FULLY GLAZED PARTITION WITH TOUGHENED GLASS (INCLUDING FIXED GLAZING AT ENTRANCE)	S.FT	254		
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass with frosted film using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling. <u>Note- If Patch Fittings are used instead of U-Shaped Aluminium rails at bottom then necessary deduction @ Rs 80/ Sft as per the estimated rates / equation</u>				
	Rate Shall be inclusive of Frosted film/ itching as per design and as directed by the architect with Coloured vinyl LOGO on either sides of the door				
2	FULL HT SOLID PARTITION				
i	Providing and fixing in position full height solid partition 75 mm thk. as indicated in the drawing excluding the door. The partition shall be made of Aluminium Frame Work of hollow sections of specified sizes given below of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips with vertical & horizontal members at not more than 600 mm center to center all complete including necessary additional supports for fixing of patch fittings of door, bracing, runner etc. so that lateral movement is arrested as per instructions of EIC / Architect. The first horizontal member shall be fixed at ground level and thereafter at every 600mm. Framework shall be fixed with 8/9mm thick BWP grade ply of required width and size as per drawing including cost of making openings for switches, AC facias etc. The rate includes cost of polishing, adhesives like fevicol,silicon, nails, screws and labour charges etc. all as per instructions of EIC / Architect.. The ply finished Partition shall then be finished with or without 1.0 mm thick laminate / 4mm thk veneer/ 6mm thk lequered glass (back painted in white colour) of approved shade and make or equivalent on both the sides as per the description as below. Rate shall be inclusive of provision of pencil groove as directed by the Architect. Height of the partitions upto soffit of false ceiling / laminate finish top shall be considered for payment. Alternate, corner vertical members of the partition shall be fixed with				
a	FINISHED WITH BOTH SIDE LAMINATE	S.FT.	790		
b	FINISHED WITH ONE SIDE LAMINATE OTHER SIDE PLY	S.FT.	222		
c	FINISHED WITH ONE SIDE LAMINATE & OTHER SIDE VEENER 4.0 MM THK OF Green Ply/ Century/Duroply/ Durian. instead of 1.0mm thk laminate	S.FT.	610		
3	FULL HEIGHT PARTLY GLAZED PARTITION	S.FT.	78		
	Providing and fixing full height partly glazed partition in 50x50x2mm thk aluminium framing @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures.The framing shall be fixed with 8/9 mm thk. commercial grade plywood on both side and finished with 1mm Laminate of approved shade and make . Approved make 5/6 mm thick itched Float glass or clear glass fixed with frosted film with coloured vinyl logo as per design, to be fixed at an height as mentioned in the drawing or as directed by the architect . The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine				
4	SEMI HT. SEMI GLAZED PARTITION IN LAMINATE	S.FT.	512		
	Specification same as 4 above but of low ht as per the drawing. All external surface and edges to be finish with 1mm thk laminate of approved shade & make. Providing and Fixing inserted Soft board / White boards / frosted Glass maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / white boards / frosted Glass				
a	WITH BOTH SIDE LAMINATE				
5	GLAZED DIVIDER PARTITIONS OVER WORKSATATIONS	S.FT.	38		
	Providing and fixing glazed partition 450mm (Max Height) as per approved design of 12mm thk clear glass with frosted film as per approved pattern and design, mirror polished fixed with S S D Clips and grove made on Mullion Box as per design with a piegon hole at the centre as per design and as directed by the architect for Single Window Counter				
6	Full Ht Solid Partition in One side laminate & other side Aesbostos Sheet with Door (Having Fire Rating of 3Hours) (4mm both side) FOR KITCHEN AND UPS ROOM	SFT	240		
	Providing & fixing in position Full Height Solid Partition in Aluminium frame work in 2'x 2' grid (horizontally and vertically) comprising of 50mm x 50mm x 3mm thk Aluminium Section covered with with 6/8 mm thick Laminate one one side & 6/8mm thk Aesbostos Sheet on on the other side. The ply surface on the outer side should be finished with approved shade of laminate in approved pattern and style and the A.C board surface on the inner side should be finished with paint of				
B	PANELLING				
1	PANELLING ON WALLS/ COLUMNS - with or without frame				

BOQ FOR FURNISHING Works for Part Re-modelling of Guwahati Regional Office (2nd Floor) & Shifting of Conference & other Rooms on Upper Floor (4th Floor)

SR.NO	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Providing and fixing of wall panelling directly on the wall surface with or without any framework with 12mm thick BWP grade ply and then finished with 1.0 mm thick. laminate of equivalent make frosty white / 4 mm thk veneer of approved shade. If the framework is required it shall be of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make as internal frame structure placed horizontally & vertically in 550 mm x 550 mm or 600mm x 600mm center to center or as directed by the Architect . All woodwork & laminate shall be finished with two or more coats of Melamine or PU polish over one coat of sealer; all complete as per the instructions of Architect. The rate shall be inclusive of provision of groove with 1.0 mm thick. laminate along all 3 sides of the groove in the panelling of size 12mm x 12mm x 18 mm ht. and as directed by the				
a.	WITH LAMINATE	S.FT.	348		
b	Same as above but Finished with 4.0mm Thk Veneer of Green Ply/ Century/Duroply/ Durian, instead of 1.0mm thk laminate	S.FT.	312		
2	PANNELLING WITH 6MM THK LECQUERED GLASS OF APPROVED SHADE	S.FT.	64		
	Providing and fixing of paneling with or without frame so as to receive a plain and even surface in exact plumb line , covered with 9mm thick commercial ply and finished with 6mm thick TEMPERED LECQUERED GLASS of approved shade and make as per the design . Rate shall be inclusive of 100 mm high skirting of silver metal laminate as and where required and as per the direction of the				
3	PANNELLING ON WALLS WITH PVC BAFFLE IN WOOD FINISH	S.FT.	192		
	Providing and fixing panelling on walls with wood finished PVC /WPC Baffle including preparation of base by panelling with 12mm thk plywood in plumb line so as to fix the baffle. The size of each section in baffle should be 15mm x 50mm and having a gaping of 25-38 mm in between. Rate shall be inclusive of all framing, sections, screws etc all complete as required to fix the PVC panel to the				
4	PANELLING ON WALL/COLUMNS WITH 4MM THK ACP IN TIMBER SERIES	SFT	642		
	Providing and fixing panelling on wall with 3mm thick Aluminium Composite Panel (Timber Series) for cladding at walls/ partitions/ columns at places as directed by the EIC/ Architect, of ALU Decor / Aluco Bond / Alo Bond or approved equivalent make for Internal wall / column / partition cladding in combination with other colours , including all necessary frame work and complete weather sealing. The composite panel should consist of 2.5mm thermoplastic core of LDPE sandwiched between 2 skins of 0.25mm thick aluminium sheet (alloy designation 310S) making a total panel thickness of 3mm. The surface will be furnished with Lumiflon based flourcarbon coating on top sides and service coating on reverse side. Coatings shall conform to specifications of specifications of ECCA / AAMA and conforming to the mechanical properties of panel as per detailed technical specifications. the system shall be fixed using GI brackets and stainless steel bolts and nuts complete with spring washers and cap nuts and all other necessary accessories. The bracket support shall be designed as per manufactures specification and shall withstand a wind pressure of 150 kg / sqm. all hardware shall corrosion resistant frame out of anodised aluminium member. Rate shall be inclusive all hardware				
C	DOORS				
1	GLAZED DOOR IN PATCH FITTINGS	S.FT.	70		
	ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS)				
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film , Coloured Vnyl LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)				
	DOORS - WITH OZONE / HAFFLE / YALE / GODREJ MAKE FITTINGS				
2	DOORS ON WOODEN PARTITION WALLS				
i	PARTLY GLAZED/ SOLID FLUSH DOOR (with or Without door frame) /WICKED DOOR, FINISHED ON BOTH SIDES WITH LAMINATE				
	Providing and fixing in position 35mm thick solid core flush door shutters conforming to IS 2202 with/ without(as per design) 6mm thick plain Clear Glass(vision panel) finished with frosting film of approved make as per design and pattern. The shutter is to be finished with 1.0mm thk laminate of approved shade and make on both the sides. All edges should be finished with Second Class Teak Wood lipping (minimum thickness 12 mm) with three or more coats of melamine polish. The glass shall be fixed with the flush door shutter by using suitable beading from both sides made out of second class teak wood. Rate shall include the cost of all approved quality hardwares required like nails, screws, handles, lock, heavy duty hinges, door stoppers etc. in case of veneer partition, the rate shall be inclusive of melamine polish of 2-3 coats or further as per the satisfaction of the architect/ engineer incharge, so as to achieve a glossy finish without any marks on the surface. Item to be completed in all respects as per drawings & instructions from EIC /Architect.				
a.	WITH DOOR CLOSER & MORTICE LOCK	NOS	8		
b	WITHOUT DOOR CLOSER & WITH MORTICE LOCK	NOS	1		
c	IN NORMAL HINGES AND WITH ALDROP/ LATCH	NOS	1		
d	RE-MODELLING OF EXISTING DOOR- The Scope of work shall involve re-modelling the existing door by covering the same with 4/6mm ply and then finishing with Laminate of approved shade in approved pattern. It shall also include finishing with all hardware fittings like Handle, Mortice Lock, Door Closer, Door Stopper etc. all complete wherever required	NOS	3		
D	CARPENTRY WORKS				
1	LOW HT RUNNING STORAGE(1'-3"DX2'-6"HT) (BACK CADENZA)				

BOQ FOR FURNISHING Works for Part Re-modelling of Guwahati Regional Office (2nd Floor) & Shifting of Conference & other Rooms on Upper Floor (4th Floor)

SR.NO	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate/ veener on all the edges. All external surfaces shall be finished with 1.0mm thk laminate/ 4.0mm thk veener of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make) locks, 3" long brushed finish handle, tower bolts and any other misc hardware				
a.	IN LAMINATE FINISH	S.F.T	84		
2	OVERHEAD STORAGE				
	Providing and fixing over-head storages which consist of 18mm thk. BWP. ply shutter with box type higes of approved make & Steam beach lipping with approved laminate/ veener on all the edges. The shutter should be made of 18mm thk. BWP. Ply top, sides, rear and bottom. All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish)/ 4.0mm thk veener of approved				
	Division of the shutters shall be made equally according to the length of the storage. The edges of the shutters shall be provided with steam beach lipping. One Ply shelf of 18mm thick BWP.ply removable type supported on side steam beach wood battens on both sides (divided equally) shall be provided. All inner surfaces shall be finished with laminate/ veener including the shutters.. Rate shall be inclusive of all necessary approved fittings like box type hinges, locks, tower bolts, 100mm SS Brush				
a.	IN LAMINATE FINISH	S.F.T	88		
3	SHUTTERS WITH FRAME FOR EXISTING STORAGE SPACE	S.F.T	144		
	Providing and fixing 18mm thk. Com ply shutters with same ply frame. Division of shutters shall be made equally according to the length. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate of approved colour and shade on outer side and inside finised with 2 coats of enamel paint of app colour and shade. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch,150 mm long SS Brush Finish handle, tower bolts, locks, Aluminium powder coated air vent grills and necessary hardware fittings complete, etc.,				
4	SIDE / CORNER TABLES				
	Providing and fixing corner / centre table of below mentioned sizes made with 19 mm BWR Ply legs finished in 1 MM laminate. Item includes 10mm bevelled brown glass fixed in 25 MM SS spacers on top				
a.	CORNER TABLES(1'-6" x 1'-6" x 1'-6"HT.)	NOS.			
b.	CENTER TABLES (1'-6" X 2'-6" X 1'-6"HT)	NOS.			
5	PIN-UP BOARDS	S.F.T	58		
	Providing and fixing pinup boards. It consist 12mm thick soft boards of good density to be mounted over 12mm thick BWP. ply. The soft board will be covered with a plain fabric (appox Rs.250 /Rmts. of Dark Blue Colour) from front and edges. Suitable steam beach moulding 25mm x 25mm size to be fixed on all four sides and will be finished in melamine polish. Note- If Steam beach T.W moulding are not provided around the soft board then the rate of this item shall be reduced to Rs 50.00/ sft as per the estimated rate and actual rate shall be calculated based on contractor rate at the time.				
	Note : Only soft bords provided on other than semi ht partitions shall be measured in this item .				
6	BOXING FOR ROLLING SHUTTER				
a.	WITH LAMINATE FINISH	S.FT	32		
	Providing & fixing ¾" BWR ply boxing for the rolling shutters. Necessary wooden framing shall be provided. The boxing shall be finished on all exposed sides by 1mm laminate and internally with enamel paint				
	Note : rate shall include all necessary hardware fittings, etc.				
7	TRAP DOOR FOR ROLLING SHUTTERS WITH LAMINATE	S.FT	6		
	Providing and fixing trap doors consisting of 1/2" thk. BWP. ply shutters with a clear opening of 4.5" opening for smooth operation of shutters and rest is closed with mirror screws (for opening for servicing). The shutters shall be finished with approved 1mm laminate, frame of 2" x 1 ½" wood sections shall be provided for proper support and strength. Rate shall be inclusive of necessary fittings				
8	FALSE CEILING IN PLY FINISHED WITH LAMINATE	S.FT.	66		
	Providing and fixing 12mm ply with necessary support from ceiling of 2"x2" Sal wood members provided at 2'-0" c/c and finished withLAMINATE of approved shade, with necessary primer etc. as per the approved design. (Painting will be measured separately)				
E	FALSE CEILING AND POP WORKS				
1	GYPSON FALSE CEILING	S.FT.	1400		
(a)	Providing and fixing Gypsum false ceiling comprising of the following: Framework: GI channel framework in 24 to 26 guage. The perimeter channel will be GI channel having one flange of 20mm and the other 30mm and web 27mm along the perimeter of the ceiling. It shall be screw fixed to brick wall / partition with the help of rawl plug of dimension 38mmx12mm dia fixed into the soffit at 610mm centres. The intermediate channels of size 45mmx0.9mm thick with flanges of size 15mm each shall be suspended from ceiling using angle of size 25mmx10mmx0.55mm spaced not more than 1220mm c/c which are fixed to soffit with GI 27mmx37mmx25mmx1.6mm cleat and steel expansion fasteners. Ceiling section of 0.55mm thickness having curled web of 80mm and flanges of 26mm are fixed to intermediate channel with the help of connecting clip of 2.64mm dia perpendicular to intermediate channel at 457mm centre to centre.				

BOQ FOR FURNISHING Works for Part Re-modelling of Guwahati Regional Office (2nd Floor) & Shifting of Conference & other Rooms on Upper Floor (4th Floor)

SR.NO	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Ceiling Board: Gypsum board false ceiling of India Gypsum make - Plain Gypboard: Milky white colour of 12.5mm thickness shall be fixed to the ceiling section using 3.5x25mm corrosion resistant self-tapping zinc plated dry wall screw at 230mm centres				
	No additional load like light fittings etc. shall be directly put on the ceiling frame. Separate suspension system shall be adopted for the same.				
	NOTE: The rate shall be inclusive of provision for core lighting, small moulding, verticals in two levels, 18.75mm x 12.5mm grooves on the edges, cutouts for cove lights and AC grills.				
	Note Only the plan area will be measured for payment. No Extra payment will be made for Grooves, Cutouts, Mouldings etc.)				
2	2' X 2' ACOUSTICAL FALSE CEILING- Armstrong -DUNE MAX MICROLOOK or approved equivalent make. SILHOUETTE series	S.FT.	1088		
	Providing & fixing in position Acoustical Ceiling tiles of Armstrong -DUNE MAX MICROLOOK or approved equivalent make, SILHOUETTE series , in true horizontal level suspended on inter locking Grid system using hot dipped galvanized steel section, entire surface prefinished in baked polyester paint, rotary stitched double-web construction main Beam tee of size 42x15mm - 6mm reveal at every 600mm c/c maximum and double rotary stitched cross tee of size 42x15mm - 6mm reveal at every 600mm. c/c and Shadow moulding of size 19mm X 7mm X 7mm X 14mm fixed to periphery of the wall. The tiles and grid system to be used as follows:				
	TILE SIZE: 600mm X 600mm X 15mm				
	EDGE : DUNE MICROLOOK				
	FRAME WORK & INSTALLATION - silhouette section				
	Frame work to consist of:				
	Main Runner spaced at 600 mm center, fixed to the roof at every 1200mm c/c by using 2.0 mm thick pre-straightened GI wire. First and last hanger should not be at a distance more than 450mm from the adjacent wall.				
	600mm x 600mm module to be formed by fixing 600mm Cross Tee between center of Main Runner.				
	Shadow moulding to be secured to wall at 450mm centers. Installation to be done as per approved Manufacturer's specification.				
3	WPC Baffle CEILING	S.FT.	540		
	Providing and fixing panelling on ceiling with wood finished PVC /WPC Baffle including preparation of base by suspending with 12/19 mm thk plywood with necessary supports & framings from the slab in plumb line so as to fix the baffle. The size of each section in baffle should be 15mm x 50mm and having a gaping of 25-38 mm in between. Rate shall be inclusive of all framing, sections, screws etc all complete as required to fix the PVC panel to the desired wall surface. Note if Gypsum is used as Backing Material instead of Plywood of 12/19mm thk then no Payment for Gypsum shall be paid				
	FALSE CEILING IN PLY FINISHED WITH 4.0MM THK VEENER	S.FT.	88		
	Providing and fixing boxing in false ceiling with 12mm ply with necessary support from ceiling of 2"x2" Sal wood members provided at 2'-0" c/c and finished with 4.0mm Thk Veener of Green Ply/ Century/Duroply/ Durian, instead of 1.0mm thk laminate of approved shade, with P.U. Polish as per the satisfaction of the Architect/ Bank				
4	WALL PUTTY ONLY IN HALL AND CUSTOMER AREAS	S.FT.	1500		
	Providing and applying Wall Putty on walls and columns (average 12mm thk). The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the window and door frames. <u>If the average thickness is found to 8mm~6mm or less, then Wall Putty will be considered as putti finish - at the rate of - 50% the quoted rate (Make: ...)</u>				
5	POP PUNNING FOR GYPSUM CEILING	S.FT.	1480		
	Providing and applying POP Punning on Gypsum Ceiling (average 8mm thk). The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the windows and door frames. If the average thickness is found to be 4mm or less than POP will be considered as a putti finish and the rate shall be 50% of the quoted rate				
F	PAINTING WORKS				
1	PLASTIC EMULSION ON GYPSUM CEILING	S.FT.	1480		
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & finish shall be provided				
2	LUSTRE PAINT ON WALLS	S.FT.	1500		
	Providing & applying Luster Paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided				
3	ENAMEL PAINT IN EXISTING ROLLING SHUTTER, COLLAPSABLE GATE, GRILLS & OTHER M.S WORKS	S.FT.	600		
	Providing & applying 1 st quality oil paint of approved make, quality & shade. The rate shall include scrapping, levelling & preparing the surface with primer quote.				
4	TEXTURED PAINT	S.FT.	156		
	Providing and applying Texture paints of Asian Royle Play/ Ikos/SKK brands on wall in required coats, including preparation of base etc. all complete(Base Rate Rs 80 sq ft)				
5	DISTEMPER PAINTS FOR WALLS (TOILETS, STORE, UPS AND STRONG ROOM)	S.FT.	2000		
	Providing and applying Distemper paint on walls, columns & ceilings. The rates shall include scrapping, levelling & preparing the surface. Primer coat +(MINIMUM) 3 coats to get evenly spread quality finish(roller Finish) of approved make, quality and finish shall be provided.Note- Rates shall also include - filling up the cracks in the wall & ceilings, making good surface .				
G	MISC. ITEMS				
1	ROLLER BLINDS, VERTICAL BLINDS, FILM etc.				
i	VERTICAL BLINDS	S.FT.	42		
	Supplying and Fixing VERTICAL BLINDS Vista/Mac/Parytex make. Blinds made using 100% polyester with acrylic polymer coating, of the shade and colour as approved by the Arcitect/ Bank ffficial(only for external windows. In case of front facia necessary approval need to be obtained)				
ii	ROLLER BLINDS FOR CONFERENCE ROOM	S.FT.	102		

BOQ FOR FURNISHING Works for Part Re-modelling of Guwahati Regional Office (2nd Floor) & Shifting of Conference & other Rooms on Upper Floor (4th Floor)

SR.NO	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	Supplying and Fixing Roller Blinds of Vista/Mac/Parytex make. Blinds made using 100% polyester with acrylic polymer coating, of the shade and colour as approved by the Arcitect/ Bank ffcial(only for external windows. In case of front facia necessary approval need to be obtained)				
2	COLOURED ACRYLIC SHEET LOGO FO THE BANK, BACK LIT Supplying, fabricating and installation of Canara Bank's Logo of 2 NOS of Triangle (Blue and Yellow Colour) made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings . This Coloured Acrylic sheet box logo should be fixed with strip light fitted from inside , as per the direction of the architect.				
i	OVERALL SIZE 750MM X 750MM	NOS	1		
ii	OVERALL ZIZE 450MM X 450 MM	NOS	4		
3	NOTICE BOARD with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer	SFT.	12		
4	WALL PAPER (In partition at Conference Room & other areas) Providing fixing and pasting Wall paper as per design & details. The item includes making POP base to get a uniform smooth surface. (base Price Rs. 100/ sqft.without taxes) The fixed area of wall paper shall be considered for payment and not the area of procured material	SFT	188		
5	DRY PLANTER BOX WITH POT & PLANTS Providing and fixing dry Planters Boxes of avg. size 350mm x 350mm x 300- 450mm(H); The Planter Box shall be made out of 2 nos 18 mm thk. sandwiched plywood - sides finished in both inner and outer surfaces with 1.0mm thk laminate of approved shade and all exposed side edges of Ply/ board shall be covered with teak wood beading finished with matching Deco paint to give it similar finish. Rates shall be inclusive of 12-14" dia PVC Flower pot with artificial/ natural plants as per architect's	NOS	10		
6	10MM GLASS SHELVES- 250-300MM WIDE Providing and fixing 10mm thk Clear Glass Shelves, 250-300MM WIDE in mirror polished edges as per design. The Glass selves should be fixed with the help of Stainless Steel F Type Glass Shelf Bracket Square 12 Inches, with screws to walls / partitions/ panneling, at an interval of 24-30" as per design and as directed by the architect	RFT	22		
H	LOOSE FURNITURE				
	TABLES				
1	RECEPTION TABLE - 1'-8" WIDE TABLE OF OVERALL SIZE 4'-0" x 4'-0" WITH FRONT LEDGE IN 12MM THK BENDABLE ACRYLIC SOLID SURFACE (CORIAN) (NON-WHITE COLOUR) AS PER DESIGN Providing and making a table of over all size of top as mentioned above and as per design given. It shall consist of 18mm thk. BWP.Ply top , sides and front and finished with 1.0 mm thk laminate of approved shade and make . All inner surfaces shall be finished with 0.80 mm thk laminate of white colour. It shall also consist of a set of 3 drawer unit with central locking system on the right side of the table and a side cadenza with drawers on top and shutters below as per the detailed drawing, on the left side. The drawer unit and side cadenza should be finished with 1.0 mm thk laminate of approved shade and make on all outer surfaces and all inner surfaces should be finished with 0.80 mm thk laminate of white colour. The front modesty panel shuould be finished 18 mm BWP. ply with laminate (as approved colour / shade) with Metallic laminate. A 19mm thk Ply wood boxing at a slope ranging from 150mm to 300mm should be taken from the bottom of the fron apron of the table as per design and sahl be continued as cutomer ledge horizontantly at a height of 300 feet from the table level . This boxing and ledge should be finished with 12 mm thk Corian of Merino Hanex Solid Surface of approved shade and colour. <u>NOTE- Colour of Corian should be other than white, as selected and approved by the Architect and if white colour is found to be used at site then necessary deductions.</u>	NOS	1		
2	V.C ROOM TABLE IN CORIAN TOP OF OVERALL SIZE - 11'-0" X 3'-6" OR AS PER DESIGN AS MENTIONED IN THE DRAWING Providing and making a table of over all size of top as mentioned above. It shall consist of 18mm thk. BWP. Ply top as per design finished with 12 mm thk Corian of Merino Hanex Solid Surface of approved shade and colour, supported on 6-8 nos numbers of mullion boxes, as per design of size 18" x 10" made of 18mm thk. BWP finished with 1mm thk laminate of approved shade and Ply inter connected with boxing 10" x 6" (as approved by the architect) on top(below table top) and at bottom (on floor level), finished in laminate of approved shade. Table top to be finished with 12 mm thk Corian of Merino make- Hanex Solid Surface of approved shade and colour and other external surfaces with 1.0 mm thk laminate of approved shade.This supporting boxes shall be then covered with apron on all sides as per design with 19 mm thk plywood finished with approved shade of laminate. Additional legs/ supports in 19 mm thk BWP Ply and finished with approved shade of laminate to be provided at distance as mentioned in the detailed drawings and as per the direction	NOS	1		
3	CONFERENCE TABLE IN CORIAN TOP OF OVERALL SIZE - 37'-6" X 5'-0" OR AS PER DESIGN AS MENTIONED IN THE DRAWING Providing and making a table of over all size of top as mentioned above. It shall consist of 18mm thk. Comm. Ply top as per design finished with 6mm thk Corian of Merino Hanex Solid Surface of approved shade and colour, supported on three boxes of size 24" x 6" made of 18mm thk. Comm finished with 1mm thk laminate of approved shade and Ply inter connected with boxing 4" x 6" (as approved by the architect), finished in laminate of approved shade. Table top to be finished with 6 mm thk Corian of Merino make- Hanex Solid Surface of approved shade and colour and other external surfaces with	NOS	1		

BOQ FOR FURNISHING Works for Part Re-modelling of Guwahati Regional Office (2nd Floor) & Shifting of Conference & other Rooms on Upper Floor (4th Floor)

SR.NO	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
3	BACK OFFICE RUNNING COUNTER (2'-0" WIDE)	R.FT.	68		
	Supply and fixing of running counter 2' wide with top made up of 19mm thk ply with laminate of 1mm thk on top and wooden beading/ moulding all round melamine polished. The table to include an keyboard tray, wire manager for every 4 ft length. The works to include all hardware fittings fixtures etc along with proper supporting verticals. All exposed edges to have wooden lipping				
4	Pedestal	NOS	17		
	Providing stand alone drawer pedestals on castors with two pencil drawers of 100mm deep & a file shutter of 450mm. Drawers made of 12mm ply finished with veneer outside & wood lipping, mounted on drawer slides. To include all hardware like castors, brass hinges, ballcatches, fully extendable drawer slides, locks, handles etc., of approved make. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Cost to include Borer/antitermite treatment for wood/plywood. The lock to be of single control type.				
5	Providing and fixing for CPU trolley of Ebbco or Equivalent make	NOS	17		
6	D.M'S TABLE IN LAMINATE FINISH- Overall size : 5'-6" x 2'- 6"	NOS	1		
	Supply and fixing of table with top made up of 19mm thk ply finished with laminate of 1.0mm thk on top as approved by the architect and wooden beading/ moulding all round melamine polished. The table to include two pencil drawers of 100mm deep & a file shutter of 450mm, a wire manager, a keyboard tray and 250mm wide CPU trolley. The works to include all hardware like castors, brass hinges, ballcatches, fully extendable drawer slides, locks, handles etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and detail of the table shall be as per Architects design. All the visible external surface to be with 1.0mm thk laminate of approved shade and make. Rates shall also be inclusive of 12 mm thk clear glass with bevelled edges on all sides to be placed on the table top.				
7	SECTION HEAD'S Table - Overall size : 5'-0" x 2' 6" IN LAMINATE FINISH	NOS	6		
	Supply and fixing of table with top made up of 19mm thk ply finished with laminate of 1.0mm thk on top as approved by the architect and wooden beading/ moulding all round melamine polished. The table to include two pencil drawers of 100mm deep & a file shutter of 450mm, a wire manager, a keyboard tray and 250mm wide CPU trolley. The works to include all hardware like castors, brass hinges, ballcatches, fully extendable drawer slides, locks, handles etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and detail of the table shall be as per Architects design. All the visible external surface to be with 1.0mm thk laminate of approved shade and make. Rates shall also be inclusive of 12 mm thk clear glass with bevelled edges on all sides to be placed on the table top.				
8	SIDE CADENZA- OVERALL SIZE 3'-0"-3'-6" X 1'-3" X 2'-6"				
	Providing and laying side cadenza of above sizes and as mentioned in the drawing. It shall consist of 3/4" thk plywood top, side and bases and 1/4" thk back. The edges on th top shall be provided with suitable (as per architect's design) wooden moulding with melamine finish. A pair of 3/4" wood shutters will be provided which will slide on 1" x 1" wooden battens above skirting. 1" x 3/8" deep vertical depression shall be made on each shutters to act as handle as shown in the drawing. All external surfaces should be finished in 1.0mm laminate / veneer of approved shade and make. A 3/4" thk fixed ply wood shelf on battens shall be provided at 16" intervals from the base. Rates shall be inclusive of necessary approved fittings like sliding rollers, locks, tower bolts and any other misc.				
a	IN LAMINATE FINISH -OVERALL SIZE 3'-0"-3'-6" X 1'-6" X 2'-6"	NOS	7		
9	FULL HT. STORAGE IN PANTRY	SFT	56		
	Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk. comm. ply top, sides, back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type hinges of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages (as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate				
	18mm thk. Comm. Ply shelves removable type supported on side steam beach wood battens on both sides at 16" interval (approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles, tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding				
10	WOODEN FLOORING IN CONFERENCE ROOM	SFT	800		
	Providing and fixing Real Wood Floors of Shade- OAK NATURE/ OAK CAPPUCCINO of Mikasa ATMOS/EICHE From Greenlam Industries Ltd, Thickness: 10mm and plank dimensions size 1200mm X 125 mm X 10mm as per design and as directed by the architect, with veneer thickness upto 0.60mm and core material being High Density Fibre Board in brushed/ matt finish, having a 10 years warranty on the use. The product should comply to EN14354. The Board should be constructed in 3 layers in order to minimise expansion and contraction with in the floor boards and the direction of the fibres within each layers should be oriented in such a manner that each layer is aligned at an angle of 90 degree with the other. It should fulfill the classification of Class G as per the fire classification. The Quoted Rate Shall be inclusive of 4"-6" High Skirting with the same material on all sides in Walls & Partitions without any extra cost. For Payment only the Floor Area Shall be Measured				

BOQ FOR FURNISHING Works for Part Re-modelling of Guwahati Regional Office (2nd Floor) & Shifting of Conference & other Rooms on Upper Floor (4th Floor)

SR.NO	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	<u>Note- Contractor Has to submit the Hard Copy of Certifying 10years Warranty from Greenlam Industries to the Circle Office alongwith the Final Bill and a Copy of the same to the Architect alongwith his Final Bill otherwise the Bill for this item shall not be considered</u>				
11	VINYL FLOORING IN DISCUSSION ROOM Providing and fixing 3.2 mm thck Solid Vinyl Tile of ARMSTRONG make with wear layer thickness of 0.5 mm with size 305mmx610 mm ; having chemical resistance no more than slight change in surface dulling, attack or staining; Heat resistance ΔE <8; Light resistance ΔE <8. Rate shall be inclusive of fixing in desired location with adhesive	SFT	188		
12	DISMANTELLING OF ALL FURNITURE & FIXTURES OF EXISTING OFFICE PARTS WHERE REMODELLING IS PROPOSED , INCLUDING SHIFTING OF EXISTING COUNTERS/ TABLES AND PROVIDING TEMPORARY ARRANGEMENTS FOR SMOOTH OPERATIONS Dismantelling of all Counters, Work Stations, Tables, Storages, partitions, False Ceilings, doors, ,etc all complete as related to carpentry works whichwould be replaced with new furniture, partition, ceilings, doors etc all complete as per the approved layout plan. The Scope of Work shall include buying back all the above discribed materials and clearing the same from the branch premises. Scope shall include Shifting Old counters and tables with all other accessories, from the area of the branch to be surrendered ; shifting the same to suitable positions temporarily till the furnishing of the branch, so as to have a smooth functioning of the branch .	JOB	1		
13	BUY BACK				
	GRAND TOTAL				