

**BOQ FOR ONSITE ATM AT PROPOSED NEW JONAI BRANCH**

S.No	Details of the BOQ	Qty	Unit	Rate	Amount
<b>CARPENTRY WORKS</b>					
1a	Outside Panelling at entrance and walls made of 2" x 2" Aluminum box section with 4mm ISO Aluminum Composite Panel in wooden texture of Alu Décor/ Alstone / Reynobond or equivalent make.	142	SFT		
b	Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consist of aluminium sections 50mm x 40mm (wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 1/4" thk plywood finished in approved shade of laminate of thickness 1.0mm. Wooden moulding, lipping etc as directed by the architect shall be provided wherever required. The panelling should be done in such a way that it can house the sliding folding partition when fully opened and remain in flush with the panelling	242	SFT		
2	Dust bin - PVC Type				
3	Shutter Boxing – Providing and fixing shutter boxing with 4.0MM thk external grade ACP in wooden texture of Alu Décor/ Alstone / Reynobond or equivalent make and fixed to a framework made of 38x 25mm aluminium box sections as per detail. Cost to include all necessary framework, support and fixing details, etc.. Complete. <b>Note the mode of measurement would be the multiplication of the length and the height of the boxing</b>	36	sft		
4	<b>MODULAR FALSE CEILING - ARMSTRONG METAL MODULAR CEILING / equivalent make</b> Providing and fixing Armstrong Metal Modular false ceiling of size 24"x24" at levels as shown in the drwg. from FFL. Rate shall be inclusive of providing the total system with installation etc.. The contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site	72	sft		
<b>5 MAIN ENTRANCE &amp; WINDOWS</b>					
a	<b>MAIN DOOR</b> -Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)	21	SFT		
b	<b>FIXED GLAZING</b> - Providing and fixing full height fully glazed toughened glass partition with 12mm thick toughened glass using S.S Patch fitting of DORMA or equivalent make at the top and grouting at the bottom with <b>U - Shaped Aluminium rails</b> and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.Rates shall be inclusive of frosted film/ glass itching with bank's Logo in approved patter, style and shade.	38	SFT		
<b>6 MISCELLANEOUS ITEMS</b>					
a	Writing ledge Wooden Ledge 1'-6" X 8" X 1'-6" with glass top and wooden slots for keeping slips.	1	Nos		
b	Soft board 3'X2' - Providing and fixing soft board incl of 6mm ply base backing and 12mm thk. crock sheet which is wrapped all around with fabric in Approved Shade. The edge trims to be finished in 19mmx 6mm lipping patti with melamine finish. The rate should i	1	Nos		
c	Fire Extinguisher 1kg ABC From Minimax / Safex	1	Nos		
<b>TOTAL OF CARPENTRY WORKS</b>					
<b>A ELECTRICAL WORKS</b>					
<b>Note- All wires including Main Line, UPS Line, Cat-6 points should be drawn from the branch and no extra payment for the same shall be entertained in any ways and hence the contractor is advice to read the drawing or visit the site in advance before quoting the rates for the electrical works and the quoted rates shall be inclusive of all as mentioned above</b>					
7	LED panel light- 36 W 2' x 2' PL ( Back Lit Armstrong), Century Magic Light make with all accessories in complete.	1	Nos		
8	LED Down lights - RDL Series , 8W , Outer size (116x 36) mm of Century Magic Light make with all accessories in complete.( Including 2 nos in shutter boxing)	5	Nos		
9	Light point wiring with earth using 1.5 sq mm PVC copper Multistrand flexible wire all pulled through concealed PVC conduit with circuit wires	1	LS		
10	4 nos. 6 Amp one way switch with 4 module concealed backbox and plate for lighting (Anchor / Roma / Crabtree). This includes all the Switches for the light provided inside the Atm on Lumpsum basis and no payment per point wise will be entertained in this regards	1	Nos		
11	Power point wiring with earth using 2.5 sq mm PVC copper Multistrand flexible wire all pulled through concealed PVC conduit inclusive of 5/15 A switch, socket, back box, plate ( 2 Nos AC , 3 Nos UPS Pt for ATM machine, UPS i/p & o/p point ,Telephone and router,extra 1 nos.)	1	LS		
12	Fascia point Light point wiring with earth using 2.5 sq mm PVC copper Multistrand flexible wire all pulled through concealed PVC conduit with circuit wires	1	LS		
13	Data Point using cat - 5 cables of systemax make data cable pulled through PVC conduits and concealed along with end termination with RJ-45 I/O socket AT&T compatible with back box and plate and 5' long patch chord with both ends crimped.	2	Nos		
14	Extra For Cat-6 Cable above 10Metre length	50	Mtr		
15	63 A Main Switch including necessary wiring all complete	1	Nos		
<b>B TOTAL OF ELECTRICAL WORKS</b>					
<b>GRAND TOTAL (A + B)</b>					