

CANARA BANK					
CIRCE OFFICE DELHI					
SCHEDULE FOR CIVIL WORKS AT CANARA BANK MCB AT MORNA SECTOR-18 NOIDA					
SN	DESCRIPTION OF ITEM	QTY.	Unit	RATE (Rs.)	AMOUNT (Rs.)
A	CIVIL WORK				
I	Dismantling Work				
i)	Dismantling brick/ concrete flooring & disposal of malba from site, including dismantling door and window frames, i/c hold fasts, stacking at site, repairs of damaged walls with cement mortar/ plaster, stacking useful bricks/ bats, etc. complete in all respects. Rates include supporting RCC slab with scaffolding, ballies etc, if required, during making door opening or removing wall; dismantling sanitary/ plumbing fixtures & stacking the same.	1.50	cum.		
ii)	Dismantling & removing of existing vitrified flooring, ceramic flooring & ceramic wall tile & False ceiling etc developing even surafce to layout new flooring as per Architect's instruction, cleaning and clearing the debris to muncipal dumping grounds.	95.00	Sq.Mt.		
iii)	Dismantling and removing doors and ventilator wherever required in a manner which facilitates easy fixing of new doors and windows without undue expense. the rate shall include removal of debris from site.	1.00	NOS.		
2	BRICK WORK				
	Providing & laying brick wall with brick class designated 75 in cement mortar 1:4 (1 cement: 4 coarse sand), including all types of leads/ lift, scaffolding, pads, racking joints, curing, cutting concrete floor before starting work, complete in all respect. In case of half brick wall, MS reinforcement as per CPWD specifications to be provided, i.e. 2 nos. 6mm dia TOR steel bars will be provided at every third course, for which no extra payment will be made.	1.00	cum.		
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size), including the cost of centering and shuttering, curing etc, complete - All work up to plinth level.	1.00	cum.		
4	Providing & laying Cement plaster 1:4 (1cement: 4 fine sand) on brick walls, shelves, ceiling etc, including all types of leads/ lift, scaffolding, pads, racking joints, curing, etc. complete.				
i)	12 to 15mm thick Cement plaster 1:4	32.00	Sq.Mt.		
	Please Note: The Contractor should ensure that all stages (a to c) of PMM works to be passed by the consultant.				
5	PAINTING				
i)	Applying three or more coats of Acrylic Emulsion Paint (ASIAN/ NEROLAC) of approved shade including making of ground, rubbing, filling of putty base preparation with BIRLA/ JK Putty, applying a coat of cement primer, complete. In case where the surface has been earlier white/colour washed, the old white/colour wash shall be entirely removed and surface broomed/scrapped down before preparing the surface foe applying paint as described above. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	120.00	Sq.Mt.		
ii)	Applying 2 or more coats of enamel paint (NEROLAC/ ASIAN) on wooden/ steel doors & windows to give even & uniform surface.	70.00	Sq.Mt.		
iii)	Applying three or more coats of Exterior emulsion paint (ASIAN/ NEROLAC) of approved shade including making of ground, rubbing and scrapping old surface with sand paper/ steel wire brush, filling of putty for base preparation, applying coat of cement primer, etc. complete in all respect.	70.00	Sq.Mt.		
6	VITRIFIED FLOOR TILES				
	Providing and fixing VITRIFIED Tiles of approved make, shade and pattern as shown in the drwng. / as aproved by Bank/ Architect. In CM 1:4 in proper line and level with out spacers for maintaining the grid lines. Rate shall be inclusive of providing and laying necessary PCC and Cement Mortar for a thickness of 3" and joint filling compound of the same shade of the tiles and including pop covering on the new flooring for the protection of tiles with base covering plastic.				
	NOTE: Recessed floor for 3M floor mat (of size 4' x 2' x 12mm) should be made at the entrance.				
i)	32" x32" Vitrified tiles.	95.00	Sq.Mt.		

7	Laying Black/ Coffee Brown Granite on steps (risers & tread)/ skirting/ shelves/ wash basin counters in cement mortar 1:3 (1 cement: 3 coarse sand), including grouting joints with neat cement mixed with pigment to match colour of granite, complete. Rates should include making edge moulding, making opening in granite for wash basin/ waste etc as per directions.	10.00	Sq.Mt.		
34	ROLLING SHUTTER	5.00	Sq.Mt.		
	Providing & fixing M. S. Rolling shutters (18/22 gauge sheets) for the facade openings (middle 1/3rd grill). Rate shall include all necessary locking arrangements including centre lock. 2 coats of anti rust paint to be provided for the shutters.				
35	M.S.COLLAPSIBLE GATE	5.00	Sq.Mt.		
	Providing and Fixing MS Collapsible Gate Single shutter made out of vertical double channels 12mmx8mm x 3mm at maximum 125 mm apart when fully stretched as specified, braced with flat iron diagonals 12 mm x 5 mm as specified in the item. The top and bottom rails shall be of M.S. section 25mm x 25mm x 6mm with 25 mm dia rollers in every fourth double channels.				
	Where collapsible gate is to be fixed within the opening but is fixed along the outer surface of opening; the M.S. section at top shall be replaced by M.S. flat 40mm x 10mm. The necessary fittings such as bolts, nuts, locking arrangements, stoppers, handles, etc. shall be provided. The gates shall open and close smoothly and easily. T-iron rails shall be fixed to the lintel and floor with masonry nails embedded in cement concrete of lintel and floors at suitable spacing. The bottom runner shall be embedded with floor and proper groove formed and the floor shall be made good to match the rest of the flooring. At the sides, the end double channels shall be fixed with T-iron rails and also by holdfasts 200mm x 40mm x 4 mm bolted at one end to the end double channels and in the masonry in cement concrete 1:2:4 (nominal mix) blocks of size 115 mm x 75 mm x 230 mm, 3 nos. each side. The side masonry shall be made good to match the rest of the masonry finish. Two coats of anti rusting paint to be provided to the gate.				
36	Supplying and fixing of 4 / 5 mm thick plain / Bazri type glass in the existing windows by applying glass putty i/c removing of old damaged glasses carefully and throwing the malba outside etc as reqd.	25.00	Sq.Mt.		
37	Misc labour for cleaning , making minor repairs, throwing of additional malba (not included in scope of works) cleaning of back portions. Misc dismantalling including the cost of throwing malba etc complete as reqd.	1.00	Job		
TOTAL					
TOTAL FOR CIVIL WORKS (EXCLUDING GST)					
A	Discount If any (Only on Excluding GST amount only)				
Net Amount (After Discount if any - Excluding GST) (Discount if any shall be given on Amount in Sub part (A -Excluding GST) Not on sub part (C)).					
GST as extra as applicable (For CIVIL works) - By Bank					
B	Buyback Amount for Old/Unused Items (Credit to Bank) (EXCLUDING GST)				
	The work includes giving credit to Bank towards the existing toilet, fittings, shutter, grill etc after carefully dismantalling and thereafter disposal of the same from the Branch site. No additional amount shall be paid for dismantalling, transportation, etc. works.				
GST as extra as applicable (For Buy back) - By Vendor					
C	GRAND TOTAL {Electrical Work Amount less Buyback Amount} [A - B] (EXCLUDING GST)				
GST as extra as applicable					

PLACE:
DATE:

SEAL AND SIGNATURE OF THE
CONTRACTOR WITH ADDRESS