

NOTICE OF INVITATION TO TENDER FURNISHING WORKS AT NEW DIPHUPAR BRANCH

Sealed Tender are invited from empanelled Interior Furnishing Contractors for the Furnishing Works to be carried out at our CANARA BANK DIPHUPAR (NEW BRANCH), NAGALAND, RO DIBRUGARH as per the details below:

1.	Time for Completion	:	20 days from the date of the work order.
2.	Submission of tenders	:	Nature of the document: SINGLE BID CONCEPT. This Tender document comprises of the following: a. Notice Inviting Tenders b. General Rules and Conditions c. List of Makes d. Drawings & Layouts of the Branch e. BOQ of the Works Duly filled documents in their prescribed form should be placed in one sealed envelope. The Name of Work & Tenderer must be written on the envelopes in a legible manner
3.	Date of Issue	:	09/10/2024
4.	Last Date & Time of Submission	:	21/10/2024 up to 03:00 P.M. To, The Assistant General Manager, Premises & Estate Section, Canara Bank, Circle Office, Guwahati.
5.	Date & Time of Opening	:	Will be opened on 21 21/10/2024 on or after 03:30 P.M. or any subsequent date as intimated by the bank.

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reasons whatsoever.

Signature of the Contractor (with Seal)

GENERAL RULES, INSTRUCTIONS AND CONDITIONS

1. Sealed OFFERS are invited for the work of:

“FURNISHING WORKS AT DIPHUPAR (NEW BRANCH), NAGALAND OF RO DIBRUGARH”

2. Offer shall be on prescribed form only, can be obtained from the above office from Senior Manager, Premises & Estate Section as detailed in Notice Inviting offer and are not eligible to be transferred.
3. The offers are called from Banks panel contractors and it is a part of the condition that **the terms and conditions detailed in the IBA’s construction works manual will be applicable and binding on the contractor**. It is open for the entire contractor to refer the manual, which is available at our section.
4. The works are to be carried out under the supervision of Bank’s Technical Officer. The works shall be carried out strictly according to the specification as specified in the tender and working drawings. Any ambiguity in the specifications / drawings shall be brought to the notice of the Bank & the decision of the Bank in such matters will be final & the same is binding on the contractor.
5. **Time period:** The total time allowed for carrying out of the work shall not exceed the period specified in the Notice Inviting Tenders i.e. **20 days**.
6. The offerers should quote in figures as well as in words the rate, and amount tendered by them. The rates quoted shall be all inclusive rates for the item of work described, including materials, labour, tools, carriage & transport, lift charges, supervision, overheads & profits, mobilizing and other charges whatsoever including any anticipated or un-anticipated difficulties, any formality with the building society etc. complete for proper execution of the work as per specifications and no claim whatsoever for any extra payment shall be maintainable.
7. Canvassing in connection with tenders is strictly prohibited and the tenders submitted by the offerers who resort to canvassing will be liable for rejection.
8. Offerer shall quote the rates which shall be inclusive of all the incurred cost for materials and services or installation at the site as per the work contract and the Employer will not entertain any claim whatsoever in respect of the same, and nothing extra shall be paid/reimbursed for the same subsequently.
9. Goods and Service Tax as applicable will be paid as per the applicable government norms at the time of realization of bills. Offerers must quote the rates / total amount exclusive of GST and GST amount shall be mentioned (with %age) separately on the last page of the financial bid.
10. The Bank reserves the right to call for bills or orders placed to the Dealers/ Companies/ Distributors for procurement of material by the Offerer.

Signature of the Contractor (with Seal)

11. The Employer does not bind itself to accept the lowest or any tender and reserves to itself the right of accepting the whole or any part of the offer and offerer shall be bound to perform the same at the rate quoted.
12. **The rate shall hold good for any upward or down ward variation in quantities and no claim on this account will be admissible.**
13. Offerers are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their offers as to the nature of the site and dimensions, the means of access to the site, and obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their offer.
14. The offerer shall note that the work is to be carried out in a running branch premises and hence, contractor should use extra manpower for utilizing the available time. The necessary permission to carry out the works with statutory authorities in night times is within the scope of the contractor and bank will not pay any additional charges.
15. **Payment Terms:** The interim payment shall be based on the progress of the works after getting the certification from the architects. The bills for interim payment shall be on a format similar to the tender or as prescribed by the bank along with the measurements of the executed work. While considering interim payment the value of materials at site shall not be considered. The number of interim payments allowed is **1(one)**. The interim payment amount payable is subject to deduction of retention money @ 10 % (Ten) and other statutory taxes.
16. The final bill for the works shall be submitted within one month from the date of completion of works, failing which the Bank reserves its right to treat the bill for the last interim payment itself as the final bill for the work and the contractor has no right to claim any amount against the work.
17. **RETENTION MONEY:** An amount equal to 10 % of the value of the work executed shall be withheld as security deposit with the bank and the same shall be released without any interest after the defect liability period, subject to clause below.
18. **DEFECT LIABILITY PERIOD:** The DLP is **12 months** from the date of completion of works as certified by the Engineer-in-charge. The works shall be guaranteed for a period of one year from the date of completion of work. Any defect arising during this period due to bad workmanship, quality of materials and others shall be rectified at no extra cost of bank, failing which the bank shall have liberty to engage other agency and recover the cost from the contractor.
19. The contractors shall make his own arrangement for the storage of the materials, without causing inconvenience to the normal working of the office and the security of the material stored shall be at the sole responsibility of the contractors/agency.

Signature of the Contractor (with Seal)

20. The contractors can make use of the available facilities at site like, electricity; water etc, with the prior approval of the Bank.
21. Any damage caused to the equipment, furniture, fixtures, decor of the office etc shall be rectified by the contractor at their own cost or the cost of the damages, as decided by the Bank, will be recovered from the contractor.
22. **Contractor shall note that no additional work is to be carried out without the written order from the Bank.**
23. All makes/brands of materials to be used in the works shall be as per the list of approved makes enclosed to the tender offer. Any make of material not listed shall be got approved by bank before us in works. Bank reserves the right to insist on the makes of materials given in the list and the decision of the bank in choosing the make shall be final and binding on the contractor.
24. **LIQUIDATED DAMAGES:** Time is the essence of the contract. If the contractor fails to maintain the required progress in terms of the contract or to complete the work and clear the site on or before the contract or approved extended date of completion, he shall, without prejudice to any other right or remedy of the Employer on account of such breach, pay as agreed compensation the amount calculated at 1 percent per week or such smaller amount as may be fixed by the bank on the contract value of the work for every week of delay or part thereof.
- The Employer shall have the right to adjust, / set-off their claim, if any against any sum payable to the contractor under this or any other contract with the Bank anywhere in India/outside India.
25. **Arbitration:** In the event of any disputes, the parties have agreed to settle the same amicably between them, failing which the same will be referred to an independent Arbitrator as may be mutually agreed between the bank and contractor as per the Indian Arbitration Act.
26. **Note:** Any discount offered in percentage by the contractors should be clearly mentioned in figures and as well as word. The offerer should arrive at the discounted amount and the same should be deducted from the quoted rate and Grand total should be arrived at. Any tenderer not adhering this condition, will be liable for rejection.

I/We have read the offer document, its terms & conditions including clauses contained in IBA's construction works manual, aware of the scope of work, site conditions, specifications and quoted accordingly.

Place :

Date :

Signature of the Contractor (with Seal)

LIST OF PREFERRED MAKE / BRAND ALL WORKS

Sr.No.	LIST OF NOMINATED MATERIALS & SUPPLIERS	SUGGESTED MAKE LIST
1	INTERIOR WORKS	
	BWP Plywood (IS : 710)	Century / Green / Sylvan / Austin
	Laminate	Green lam / Century mica / Sunmica / Aica
	Acrylic sheet	ICI, GE or equivalent ISI make
	Marine grade plywood	Century / Green / Sylvan / Austin
	Adhesive	Fevicol/Araldite/Anchor or equivalent
	Solid Surfaces (Corian)	Merino Hennex / LG/ Dulux/ Hyundai
	Marine grade Block Board	Century / Green / Sylvan / Austin
	Flush Door / BWP Block board (IS : 1659)	Century / Green / Sylvan / Austin
	Polish	Asian / Dulux or equivalent
	Latex	MM Foam or equivalent ISI make
	High density foam	U Foam or equivalent ISI make
	Locks	Godrej / Hafele /Hettich / Kich / Doorset / Yale
	Storage Hardware	Godrej/ Haffle / Hettich / Ebco or equivalent
	Screws / Nails & other accessories	GKW/Nettleford or equivalent
	Plain/Toughened glass	Saint- Gobain, Indo Asahi , Modi or equivalent
	Hardware for general staff areas	Dorma / Euro/ Ozone / Enox / Ebco /Hamco or equivalent
	Hardware for main Glass doors (patch fittings)	Dorma / Euro/ Ozone / Enox / Ebco /Hamco or equivalent
	Door Closers (general use)	Godrej / Archi / Sterling (DC 2000)
	Floor springs (general use)	Godrej / Archi / Sterling (FS 3000)
	Floor springs for main glass doors	Dorma / Euro/ Ozone / Enox / Ebco /Hamco or equivalent
	Aluminum Sections for Partitions	Jindal / Tata steel or equivalent
	False Ceilings: Gypsum	India Gypsum / Saint Gobin / USG Boral
	False Ceilings: Grid (As Approved)	Armstrong
	False Ceilings: Grid (Metal Ceiling)	Armstrong
	GI Sections	India Gypsum / Saint Gobin / Jindal or equivalent
	Acoustical False Ceilings: Mineral fiber board	Armstrong, Hunter Douglas / Peritex or equivalent
	POP Punning	Gyprock / India Gypsum / Birla
	Paint	Asian / Nerolac / Dulex / Berger or equivalent
	Exterior Paint	Asian / Nerolac / Dulex / Berger or equivalent
	ACP (Exterior / Interior)	Alstone / Alu Decor /Alucobond
	Silicon	G E / Dow corning / Wacer
	Rolling / Vertical Blind	Vista / Peritex / Winfab / MAC or equivalent
	Frosted Film	Garware or equivalent

Signature of the Contractor (with Seal)

	Aluminum Skirting - 50mm	Jindal or equivalent
	Water Proofing	Pidilite or equivalent
	HardWood	Salwood / Teakwood/kapoor
	Glass	Saint Gobain / equivalent
2	ELECTRICAL	
	Light Fittings	Philips / Wipro / Havells / Crompton G.
	MCCB, MCB , RCCB, DB, ICTPN TP, HRC Fuse, change over switch, switch fuse Unit	L&T, ABB, Legrand, Havells, Schneider
	FRLS insulated Elec. Wire/ cable armoured, unarmoured, Sheathed,unSheathed, flexible LT cable, Multi core, single core cable, flat cable	Finolex/Polycab/Havells/RR kabel/KEI
	PVC conduit(HEAVY DUTY ONLY)	CAP/Finolex/Polycab
	PVC insulated copper conductor Wires	Finolex/ Polycab/RR Cable
	Distribution Box	Legrand/ Schneider/ Havells /Siemens
	MCB & MCCB	Legrand/ Schneider/ Havells /Siemens/L&T
	Light Fixture & Lamps	Philips/ Wipro / Havells / Crompton G.
	HT cable	Polycab/Havells
	Modular Switches	ABB/ Legrand/ MK/ANCHOR/ Havells /ROMA
	DLP Trunking	Legrand/Schneider or equivalent
	Power cable	CCI/ Skytone/ Universal/ LAPP/ Torrent
	End Termination	Raychem/ Mahindra/ELMEX
	PANEL	Crompton/L&T/C&S
	Fan	Crompton/Havells/Bajaj/Usha
	Raceway & Alu. Trunking	Tata/Jindal/Zenith
	Casing Caping	Finolex/Cap or equivalent
	Weather proof socket outlet with MCB	ABB/MDS/LEXIC/Neptune/Elcon- Clipsil, Siemens, Schneider (Merlin Gerin)
	Miniature Circuit Breaker	ABB/MDS/LEXIC/ Clipsil/Siemens/ Havells
	Earth Leakage Circuit Breaker	MDS/LEXIS/Siemens/ Havells
	MCB Distribution Boards in sheet steel housing (double door)	ABB/MDS/LEXIC/Siemens/ Havells
	Telephone Cable	Skytone/ Delton/ NICCO/Polycab/Finolex
	Switch, TV & Telephone socket & boxes (Modular Type)	CPL/Legrand/ABB/Anchor
3	Miscellaneous Items	
	Lightning Protection Unit	Erico/ Pheonix/ INDELEC
	Relays	L&T/ABB/Siemens/BCH
	Contractors	L&T/ GE Power/BCH/ Siemens/ABB

Signature of the Contractor (with Seal)

	Changeover switch	C&S/Havells/ L&T/HPL
	KWH, PF, Frequency meter	BHEL/ AE/Havells/ L&T/ALSTOM
	Push Buttons	L&T/ Siemens
	Timers	L&T/ Legrand/ Schneider/Siemens/GE
	Timer Switch	L&T/ Legrand/ Schneider/Siemens/GE
4	Networking	
	Switches	Brocade/Cisco/DigiLink/3Com/Nortel/Foundry/D-Link
	Patch Panel,Patch cord and I/o	Digi-Link / Tyco(AMP) /Schneider/D-Link
	Cable	Digilink/Clipser/National/Polycab/Lapp/Finolex
	Racks	ComRack / HCL / ValRack / APW President

CONTRACTOR

NOTE: The contractor shall use only above mentioned material to be approved by the Consultant. All other materials shall confirm to the specifications laid down. The tenderers shall take this into account while tendering rates / prices.

Signature of the Contractor (with Seal)

**BOQ FOR INTERIOR FURNISHING WORKS FOR CANARA BANK
PROPOSED NEW BRANCH AT DIPHUPAR, NAGALAND**

PART A: INTERIOR FURNISHING WORKS FOR BRANCH					
SL	DESCRIPTION OF WORKS	UNI T	QNTY	RAT E	AMOUNT
	CARPENTARY IN LAMINATE				
	GENERAL NOTES FOR CARPENTRY WORKS				
	1. All Plwood and Block board to be used in Furnishing works should strictly be of Century / Green / Sylvan / Austin ply only				
	2. All Plywood/ Block Board used to be of BWP (IS : 710) grade but of above make only				
	3. All laminates should strictly be 1.0mm thk of Green lam / Century mica / Sunmica / Aica make				
A	TABLE , DESKS , DRAWERS AND STORAGES				
	ALL TABLES / WORK STATIONS SHOULD HAVE KEYBOARD TRAY, CPU TROLLEY(METAL), FOOT REST AND RATES SHOULD BE QUOTED ACCORDINGLY WITHOUT ANY EXTRA CLAIM				
i	Front Office/ Clerical Counter:	RFT	11.00		
	Providing and fixing in position Front Office Counter 3'-0" wide including 6" ledge on Customer's Side as per drawing comprising of the following complete in all respects:-				
	i) Working top made with 18/19mm thick commercial BWP Plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1¼"x1" Teak Wood moulding finished with melamine polish/ with PVC Moulding of matching shade. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine finish.				
	ii) Vertical facia (Apron) made with 18/19mm thick commercial BWP Plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.				
	iv) Glazed partition above working top to be provided with 12mm thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.				
	v) vertical supports made with 18 mm thick BWP Plywood finished with 1.0mm thk laminate of approved shade and make.				
	vi) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.				
	vii) Footrest made with T.W. member of size 4"x1 ½ " finished with french polish.				

Signature of the Contractor (with Seal)

	viii) Drawer units- It shall also consist of a stand alone drawer pedestal on castors or Fixed with the table as per Architect's direction & site conditions, with two pencil drawers of 100mm deep & a file shutter of 450mm. All sides of the drawer box and the Drawers shall be made of 18/19mm thk commercial ply finished with 1.0mm thk laminte of approved shade and make on the outer serfaces and all inner surfaces shll be finished with mellamine polish/ paint of approved shade and make. The drawers shall be fixed with EBCO/ Godrej make telescopic drawer channel/ slides and the lock for this pedestal to be of single control type. Each drawers will be provided with 4"/5" C-Type handles (Stainless Steel finish) of design as per approval of the Project Consultant / Bank.				
	Each drawer. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.				
	The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Necessary beadings with melamine polish for fixing the glass are to be provided				
	The front apron of the table should be fixed with 1'-3" x 1'-3" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design, FOR EVERY WORK STATIONS				
ii	Cash Counter (Including partitions except Rear Door):	NO	1.00		
	Providing and fixing in position Cash Counter all complete except rear dooras per drawing comprising of the following :	S			
	i)Working top made with 18/19 mm thk commercial BWP Plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1¼"X1" Teak Wood moulding finished with melamine polish/ PVC edge beading of maching shade. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine polish.				
	ii)Vertical facia (Apron) made with 18mm thick BWP Plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.				
	iii)Vertical drop box (horizontal band) of size 12" ht x 10" thickness(hollow inside) shall be provided suspended from the ceiling lvl on the facia above the working top made with 18mm thick BWP Plywood finished with 1mm thick laminate with provision for concealed light,				

Signature of the Contractor (with Seal)

<p>iv) 1'-0" height solid partition over working top and fixed with a ledge(transaction top) of 12" wide @3'-6" from finished floor lvl and finished with laminate. The ledge should be such that it is 8" projecting outside the counter and 4" inside the counter</p>				
<p>v) A gap of 4" should be left above the transaction top (all along the width of the teller counter)</p>				
<p>vi) Glazed partition above the transaction top (in facia) and also above 4" clear gap shall be provided with 12 mm thick glass (itched) till 6'-6" height from the FFL in parts as per drawing. The edges of cut out and the top edge of glass are to be mirror polished and to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing.</p>				
<p>vii) Full Ht Partly Glazed Partition (till 6'-6" high) shall be provided with 8/10mm thick itched glass on all sides as per design and back till 6'-6" lvl from ground level) to provided as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. . The exposed edges shall be finished in mirror polish.</p>				
<p>viii) Boxing (12"x 10") made with 18mm thick BWP Plywood as per drawing with horizontal (Boxing) extension at the top all finished with approved shade of laminate shall be provided for the counter</p>				
<p>ix) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.</p>				
<p>x) Footrest made with T.W. member of size 4"x1 1/2 " finished with french polish.</p>				
<p>xi) Drawer units- It shall also consist of a stand alone drawer pedestal on castors or Fixed with the table as per Architect's direction & site conditions, with two pencil drawers of 100mm deep & a file shutter of 450mm. All sides of the drawer box and the Drawers shall be made of 18/19mm thk commercial ply finished with 1.0mm thk laminte of approved shade and make on the outer serfaces and all inner surfaces shll be finished with mellamine polish/ paint of approved shade and make. The drawers shall be fixed with EBCO/ Godrej make telescopic drawer channel/ slides and the lock for this pedestal to be of single control type. Each drawers will be provided with 4"/5" C-Type handles (Stainless Steel finish) of design as per approval of the Project Consultant / Bank.</p>				
<p>xii) Boxing as per drawing made with 12mm thick BWP Plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.</p>				

Signature of the Contractor (with Seal)

	The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the Vertical drop and also in the 12"x10" boxing as shown in the drawing. Necessary beadings with matching melamine polish for fixing the glass are to be provided as per drawing/ as directed.				
	The front apron of the table should be fixed with 1'-6" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
v	Manager's Table of size 6'-0"(L) x 3'-0"(W) x 2'-6"(H) with 8mm thk clear Glass (all edges mirror polished) on Top	NO S	1.00		
	Providing and making Manager Table in laminate finish of size 6'-0" X 3'-0". It shall consist of 3/4" thk BWP Plywood top as per design(double edge on outer edge with 1 1/2" THK HALF ROUND MOULDING ON THE EDGES/ PVC Bead in Matching shade supported on 3/4" thk BWP Plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate.The table should have metal keyboard tray,wire manager,and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement. The front apron of the table should be fixed with 1'-6" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
vi	Officer's Table of size 5'-0"(L) x 2'-6"(W) x 2'-6"(H)	NO S	1.00		
	Providing and making Officer's Table in laminate finish of size 5'-0" X 2'-6". It shall consist of 3/4" thk BWP Plywood top as per design(double edge on outer edge with 1 1/2" THK HALF ROUND MOULDING ON THE EDGES/ PVC edge Bead in matching shade supported on 3/4" thk BWP Plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate.The table should have metal keyboard tray,wire manager,and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement. The front apron of the table should be fixed with 1'-6" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
vii	MAY I HELP YOU- TABLE	NO S	1.00		

Signature of the Contractor (with Seal)

	Providing and laying a Plain Table for Security Gurd with a Pencil Drawers for over all size of top as mentioned above. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make. The front apron of the table should be fixed with 1'-6" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
viii	Side Cadenza of size 1'-6"(W) x 3'-6"(L) x 2'-6" (H) (FOR MANAGER)	NO S	1.00		
	Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit (C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk BWP Plywood for top, base and sides and base 1/4" thk marine BWP Plywood, 3/4" thk BWP Plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
ix	Side Cadenza of size 1'-6"(W) x 3'-0"(L) x 2'-6" (H) (FOR OFFICERS)	NO S	1.00		
	Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit (C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk BWP Plywood for top, base and sides and base 1/4" thk marine BWP Plywood, 3/4" thk BWP Plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from				

Signature of the Contractor (with Seal)

	the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
x	LOW HT RUNNING STORAGE(1'-6"DX2'-6"HT) (BACK CADENZA)	SFT	92.00		
	Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk BWP Plywood for top, base and sides and base 1/4" thk marine BWP Plywood, 3/4" thk BWP Plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make . Note- The Height of the running stoarge should be 2'-6" and should comprise of a 6" high drawe and shutters below. No shelves should be provided inside the shutters				
xi	OVER HEAD STORAGE IN PANTRY	SFT	14.00		
	Providng and fixing over-head storages which consists of 3/4" thk BWP Plywood shutter with self closing hinges of haffle make(full ovel open) & t.w lipping matching with approved laminate on all the edges. They shall consist of 3/4" thk BWP Plywood top , sides and bottom and 1/4" thk marine BWP Plywood back. A 3/4" thk ply wood palmet shall be provided below the storage to house the tube light. All the external surfaces shall be finished with 1.0mm thk laminate of approved shade. Divisions of shutter shall be made equally in accordance to the length of the storage. All internal surfaces shall be finished with french polish including the shutter. Rate shall be inclusive of all necessary hardware fittings of approved make like- hinges, locks, towerbolts, handles etc.Note- the pelmet for tubelights will not be considered as seperate item on in the measurement				
xii	FULL HT. STORAGE	SFT	220.00		

Signature of the Contractor (with Seal)

	Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk.comm. ply top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type hinges of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages (as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. 18mm thk. Comm. Ply shelves removable type supported on side steam beach wood battens on both sides at 16" interval (approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.				
xiii	SHUTTER BELOW PANTRY COUNTERS	SFT	14.00		
	Providing and fixing 19mm thk.WPC Board shutters with WPC frame, skirting gap as shown in the drawing shall be maintained. Division of shutters shall be made equally according to the length of the counter. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate (suede finish) of approved shade from outside, and edges of shutters with PVC lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
xiv	BACK OFFICE RUNNING COUNTER (1'-6" - 2'-0" WIDE)	RFT	4.00		
	Providing and laying a Plain running counter either free standing or wall mounted with only Pencil Drawers at every 3'-0" length for over all size of top as mentioned bellow. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with half round moulding on the edges) supported on 3/4" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with melamine shall be provided to the edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make. 1no. Pencil drawer unit as shown in the drg shall be provided. Drawer shall consist of 1/2" thk. Comm. Ply sides, back and 1/4" thk. Comm. Ply base. Facia of drawers shall be of 3/4" thk. Comm. Ply finished in 1.0 mm. Thk. Laminate and with a wooden moulding on top/bottom edge for handle. Each drawer shall slide on a pair of hafele make telescopic drawer sliders.				
B	PANELLING				

Signature of the Contractor (with Seal)

1	PANELLING ON WALLS/ COLUMNS IN LAMINATE FINISH				
	Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consists of aluminium sections 50mm x 38mm(wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 18/19mm thk commercial grade BWP Plywood and finished with 1.0mm thk laminate or left naked as per the direction of the EIC/architect. Wooden moulding, lipping etc as directed by the architect shall be provided wherever required.				
a	In 12 mm BWP Plywood finish in laminate for sealing of ventilator & window near cash counter	SFT	56		
b	In Laminate Finish over Ply	SFT	510		
2	PANNELLING WITH LECQUERED GLASS OF APPROVED SHADE	SFT	80.00		
	Providing and fixing of paneling with or without frame so as to receive a plain and even surface in exact plumb line , covered with 9mm thick commecial ply and finished with 8/9mm thick TEMPERED LECQUERED GLASS of approved shade and make as per the design . Rate shall be inclusive of 100 mm high skirting of siver metal laminate as and where required and as per the direction of the Consultant Architect/ Engineer.				
3	PANNELLING ON WALL (EITHER SIDES OF LECQUERED GLASS) WITH WPC PANNELS OF SIZE 2950MM (LENGTH)X 195MM (WIDTH) X 27MM(HEIGHT)	SFT	32.00		
	Providing and fixing panelling on wall & ceilings with WPC (Wood Polymer Composite) Fluted Panels of size 2950MM (LENGTH)X 195MM (WIDTH) X 27MM(HEIGHT) of LEBEN/ Alutuff / Murrato or other approved make of approved shade in approved pattern as directed by the architect. Rates shall be inclusive of all hardware fittings sna fixtures as required to fix the same on the wall and ceilings including corner beading and fastners.				
C	PARTITIONS				
	(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca/ rcc ceiling/slab but the area of partition payable will be below the false ceiling only).				
1	Full Height Solid Partition B/S Laminate	SFT	222.00		
	Providing & fixing in position solid Full Height Partition in frame work in 2'x 2' grid (horizontally and vertically) comprising of 2"x 2" T.W. Section with 8 mm thick BWP Plywood on both sides finished with 1 mm thick laminates of approved make and colour as shown in drawing. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
2	FULL HEIGHT PARTLY GLAZED PARTITION	SFT	94.00		

Signature of the Contractor (with Seal)

	Providing and fixing full ht. partly glazed partition at places as mentioned in the drawing and as directed by the Architect/ EIC. The partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures.The framing shall be fixed with 8/9 mm thk. commercial grade BWP Plywood on both side and finished with 1mm Laminate of approved shade and make . Approved make 5/6 mm thick itched Float glass or clear glass fixed with frosted film as per design, to be fixed at an height as mentioned in the drawing or as directed by the architect . The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine Polish.				
5	FULLY GLAZED PARTITION WITH TOUGHENED GLASS(In Manager cabin Front , Self Service Area & Front Glazing)	SFT	96.00		
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.Rate shall be inclusive of frosted film and bank logo to be fixed over the glass surface as per deign and as directed by the architect				
6	Semi height Semi Glazed/ Solid Partition	SFT	24.00		
	Providing and fixing in position Semi Height Semi Glazed/ solid Partition work as shown in the drawing in frame work at 2' x 2 ' grid (horizontally and vertically) with 6mm BWP Plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings.Item to include 8 mm thick glass with itching as per design and 2"x 2" T.W. member for glass sides to take 8 mm thick glass with etching and frosting. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
7	FULL HEIGHT SOLID PARTITION FINISHED WITH ONE SIDE LAMINATE OVER PLY AND OTHER SIDE WITH A.C BOARD FINISHED WITH POP & PAINT INCLUDING DOOR (Having Fire Rating of 3Hours for UPS Room)	SFT	172.00		

Signature of the Contractor (with Seal)

	Providing & fixing in position Partition in Aluminium frame work in 2'x 2' grid (horizontally and vertically) comprising of 50mm x 50mm x 1.8mm thk Aluminium Section covered with with 8/10 mm thick Aesbestos Sheet and finished with POP and paint on one side and the other sides to be finished with 8/9mm thk BWP Plywood and finished with approved shade of laminate. It shall also consist of a Flush door of required size and fixed with aesbestos Sheet on one side and laminate on other sides with the same specifications as mentioned in the above line. Rates shall be inclusive of all hardware fittings and fixtures such as - hinges, handles, locks, door closer, door stopper etc. all complete				
D	DOORS				
a	SOLID DOORS- IN LAMINATE FINISH (BOTH SIDE LAMINATE)				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall consist of 3 nos 2" x1" C.P teak wood styles and 3 nos 3" x 1" C.P teak wood bottom, middle and top rails. The wooden framing will be covered with 1/4" thk BWP Plywood on both sides. A door frame of size 3"x1 1/2" t.w section finished with mellamine polish shall be provided. Rates shall be inclusive of approved locking system(Godrejmake- Ultra mortise dead lock), door stopper, a pair of handles, tower bolts etc and misc. hardware items of approved make				
i	3'-0"X7'-0"-IN LAMINATE FINISH (WITH 1 1/2X4" WOODEN FRAME)	NO S	3.00		
b	PARTLY GLAZED DOOR				
	Specification same as above except for 8mm thk Modi Guard clear float glass shall be provided at 4'-0" from floor lvl The door shall be finished in 1.0 mm thk laminate on both sides				
I	PARTLY GLAZED DOORS / DOORS WITH VISION PANEL	NO S	1.00		
II	AT ENTRANCE TO CASH COUNTER PASSAGE	NO S			
III	2'-6" X 7'-0" TELLER COUNTER & SW COUNTER DOOR WITH NIGHT LATCH	NO S	1.00		
IV	4'-0" high Wicked Door as per design	NO S	1.00		
c	ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS)- AT ENTRANCE & BM'S CABIN	SFT	56.00		
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to acCommercial gradeodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film /				

Signature of the Contractor (with Seal)

	LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)				
E	FALSE CEILING AND POP WORKS				
1	GYPSON BOARD CEILING	SFT	400		
	Providing and fixing 1/2" thk Gypsum India Board false ceiling at levels as shown in the drg. From the FFL. Rate shall be inclusive of all Gypsum India Components contained G.I perimeter channels of size 0.55 thk having one flange of 20mm and another flange of 30mm and a web of 27mm along the perimeter of the ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws at 610mm centres. The suspending G.I intermediate channels of size 45mm, 0.9mm thk with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angles of width 25mm x 10mm x 0.55mm thk fixed to soffit with G.I cleat and steel expansion fastner at every 610mm c/c. Ceiling sections of 0.55mm thk having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in directions perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment. The board are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & jointing paper tape. Rate shall be inclusive of any vertical ceiling part, cutouts for spot and tube lights, a.c grills, fire and security system cutouts. All Sections should adhere to the manufacturer's guidelines .				
	Note- Rates shall be inclusive of The drop/band of 6"-12" between the gypsum(at lower level) and Armstrong(at heigher level). No extra can be claimed for the same. Amount will be paid as per the measurement of the horizontal surfaces of Gypsum and Armstrong and nothing will be paid for vertical surface / band/ drop as it is all inclusive. Rate				
2	MODULAR FALSE CEILING- ARMSTRONG make	SFT	380.00		
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm grid sections) false ceiling of size 24" X24" AT LEVELS AS SHOWN IN THE DRG. FROM THE FFL. Rates shall be inclusive of providing the total system with installation etc. The contractor has to mantain all ceiling tiles in good order and replace the defective tiles (at his own cost) before the handing over				

Signature of the Contractor (with Seal)

	of the site.				
F	PAINTING				
1	LUSTRE PAINT WITH POP PUNNING ON GYPSUM FALSE CEILING	SFT	430.00		
	Providing & applying Luster Paint on walls, columns & ceilings over pop punning. The rate shall include scrapping, levelling & preparing the surface. with pop , jointing compound and Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.				
2	DISTEMPER PAINTS FOR WALLS (TOILETS, STORE, UPS AND STRONG ROOM)	SFT	2000.00		
	Providing and applying Distemper paint on walls , columns & ceilings. The rates shall include scrapping, levelling & preparing the surface. Primer coat +(MINIMUM) 3 coats to get evenly spread quality finish(roller Finish) of approved make, quality and finish shall be provided.Note- Rates shall also include - filling up the cracks in the wall & ceilings, making good surface .				
3	WALL PUTTY/ POP PUNNING (ON BANKING HALL WALLS AND GYPSUM CEILING ONLY)	SFT	500		
	Providing and applying POP Punning on walls and columns (average 6mm thk). The rate shall include scrapping, levelling and preparing the surface. The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the windows and door frames. If the average thickness is found to be 4mm or less than POP will be considered as a putti finish and the rate shall be 50% of the quoted rate				
	If Wall Putty is provided on RCC ceiling/ Slab and other area than banking hall, then the same shall not be payable				
4	PLASTIC EMULSION PAINT (ON BANKING HALL WALLS ONLY)	SFT	600		
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided.				
	If Plastic emulsion paint is done on all non-banking areas like store room, toilets, Strong room, Pantry, UPS Room etc, then the same shall not be considered and payment for plain distemper paint shall be considered				
G	MISC. ITEMS				
1	VERTICAL BLINDS	SFT	156.00		

Signature of the Contractor (with Seal)

	Supplying and Fixing VERTICAL BLINDS Vista/Mac/Parytex make. Blinds made using 100% polyester with acrylic polymer coating, of the shade and colour as approved by the Arcitect/ Bank ffficial(only for external windows. In case of front facia necessary approval need to be obtained)				
2	PIN UP BOARD IN BRANCH	SFT	24.00		
	Providing and fixing Pin-Up board of sizes as mentioned in the drawing in 1/2" thk soft board of good density to be mounted over 12mm thk ply and fixed to partition/ walls or at places as directed by the architect. The soft board shall be covered with valver cloth of approved shade and make (BASIC RATE RS. 200 /R.MTS.) .				
3	SHUTTER BOXING	SFT	52.00		
	Providing and Fixing Shutter Boxing with 19mm thk Marine Ply and Finished with Approved Shade of laminate> The boxing of shutter should be made opennable type for periodic maintainance. <u>Note the mode of measurement would be the multiplication of the length and the height of the boxing</u>				
4	NOTICE BOARD	SFT	12.00		
	Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
5	SIDE/CORNER/CENTRE TABLE				
	Providing and making corner/ side/ centre table of below mentioned sizes as per drawing. Table top shall consist of 12mm thk glass with champhered edge with approved quality of itching. The base shall be made up of CP TEAK WOOD frame/ 3/4" BWP Plywood or as directed by the architect. All exposed faces shall be finished with natural polish(if wood frames are used) or with 1.0mm thk laminate of approved shade for ply. All inner surfaces should be finished with natural french polish				
a	CORNER TABLE(1'-6" X 1'-6 X 1'-6HT)	NO S	1.00		
b	CENTRE TABLE(1'-6" X 2'-6 X 1'-6HT)	NO S	2.00		
6	WRITING LEDGE	RFT	4.00		
	Providing and fixing Wall Mounted Writing Ledge Of Size 4'-0" x 1'-3" x 1"(H), made out of 19mm thk BWP Plywood of approved make and finished with 1mm Thk approved				

Signature of the Contractor (with Seal)

	shade of laminate. This ledge should have 4 nos of Pockets made along 4' length with the Supporting wall as base with 3" clear space to house withdraws/deposit etc slips. All inner surfaces of the Ledge should also be laminated. A 12mm thk Clear Glass, Mirror polished on all sides of size 4'-0" x 1'-3" shall be fixed with 4 nos 1-1/2" dia and 4" High S. S Studs should be fixed on the Top portion of the ledge.				
7	COMPLAIN BOX & SUGGESTION BOX	NO S	1.00		
	Supplying and erecting free-standing complain box of overall size 300 mm long x 200 mm deep x 450 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete with hardware fittings and fixtures of approved make and quality. Top and all exposed surfaces of block board are to be finished with 1.00 mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.				
8	CHEQUE DROP BOX	NO S	1.00		
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.P teak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including all free edges are to be finished with 1 mm thick laminate sheet of combination shade. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer. Rate to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved design and quality.				
9	10MM GLASS SHELVES- 250-300MM WIDE	RFT	24		
	Providing and fixing 10mm thk Clear Glass Shelves, 250-300MM WIDE in mirror polished edges as per design. The Glass shelves should be fixed with the help of Stainless Steel F Type Glass Shelf Bracket Square 12 Inches, with screws to walls / partitions/ panneling, at an interval of 24-30" as per design and as directed by the architect				
10	DRY PLANTER BOX WITH POT & PLANTS (WITH FLOWER POT)	NO S	8		

Signature of the Contractor (with Seal)

	Providing and fixing dry Planters Boxes of avg. size 350mm x 350mm x 300- 450mm(H); The Planter Box shall be made out of 2 nos 18/19 mm thk. sandwiched WPC Board on sides and bottom and finished with 1.0 mm thk laminate of approved shade in approved style and pattern. All exposed side edges of shall be covered with WPC beading finished with similar finish. Rates shall be inclusive of 12-14" dia PVC Flower pot with indoor quality natural plants as per architect's / Bank Officials choice.				
11	COLOURED ACRYLIC SHEET LOGO FO THE BANK, BACK LIT (450 X 450)	NO S	1.00		
	Supplying , fabricating and installation of Canara Bank's Logo of 2 Nos of Triangle (Blue and Yellow Colour) made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings . This Coloured Acrylic sheet box logo should be fixed with strip light fitted from inside , as per the direction of the architect.				
	(A) TOTAL OF INTERIOR FURNISHING WORKS AT BRANCH				
PART B: INTERIOR FURNISHING WORKS FOR ATM					
S.No	Details of the BOQ	Qty	Unit	Rate	Amount
	CARPENTRY WORKS				
1	Panelling on Out side & Inside with ACP- Providing and fixing panelling on walls/ columns with or without aluminium framing as per the directions of the architect. It shall then be covered with 3/4.0mm thk A.C.P of pure white colour on all sides . The Brack drop of the wall on which the ATM machines will be placed shall be finished with 2 full height blue bands (in Canara Bank Blue shade) 1'-6" - 2'-0"of ACP on either sides in combination with the white colour ACP Alu Décor/ Alstone / Reynobond or equivalent make	256	SFT		
2	Dust bin - PVC Type				
3	Shutter Boxing - Providing and fixing shutter boxing with 3/4.0MM thk external grade ACP in white colour of Alu Décor/ Alstone / Reynobond or equivalent make and fixed to a framework made of 38x 25mm aluminium box sections as per detail. Cost to include all necessary framework, support and fixing details, etc.. Complete. Note the mode of measurement would be the multiplication of the length and the height of the boxing	48	sft		
4	MODULAR FALSE CEILING - ARMSTRONG METAL MODULAR CEILING / equivalent make				

Signature of the Contractor (with Seal)

	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm grid sections) false ceiling of size 24" X24" AT LEVELS AS SHOWN IN THE DRG. FROM THE FFL. Rates shall be inclusive of providing the total system with installation etc. The contractor has to maintain all ceiling tiles in good order and replace the defective tiles (at his own cost) before the handing over of the site.	98	sft		
5	MAIN ENTRANCE & WINDOWS				
a	MAIN DOOR -Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)	21	SFT		
b	FIXED GLAZING - Providing and fixing full height fully glazed toughened glass partition with 12mm thick toughened glass using S.S Patch fitting of DORMA or equivalent make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.Rates shall be inclusive of frosted film/ glass itching with bank's Logo in approved patter, style and shade.	66	SFT		
6	MISCELLANEOUS ITEMS				
a	Writing ledge Wooden Ledge 1'-6" X 8" X 1'-6" with glass top and wooden slots for keeping slips.	1	Nos		
b	Soft board 3'X2' - Providing and fixing soft board incl of 6mm ply base backing and 12mm thk. crock sheet which is wrapped all around with fabric in Approved Shade. The edge trims to be finished in 19mmx 6mm lipping patti with melamine finish. The rate should i	1	Nos		
c	Fire Extinguisher 1kg ABC From Minimax / Safex	1	Nos		
	(B) TOTAL OF INTERIOR FURNISHING WORKS AT ATM				
	GRAND TOTAL (A + B)				

Signature of the Contractor (with Seal)