

ESTIMATES FOR INTERIORS WORK FOR CANARA BANK AT RAH GUNTUR					
Sr.No.	Description	Unit	Qty	Rate	Amount
<b>INTERIOR FURNITURE WORK FOR BRANCH</b>					
1	<b>GYPSON BOARD FALSE CEILING</b>				
	Providing & fixing as per design with suspended false ceiling consisting of 12mm.thk.Gyp. board suspended on G.I. framework to consists of G.I. perimeter channels 0.55 mm thk. x 20mm .x 30mm. along perimeter of false ceiling; screw fixed to wall/partition with nylon sleeves & screws @ 600mm. dc. Suspending GI. Intermediate channels of size 0.9mm thk.x45mmx15mm. from the soffit at max. distance 1220mm. dc with ceiling angle 0.55mm. thk.x2n5mm.x10mm. Fixed to soffit using proprietary supplied GI. Cleats & steel expansion fasteners. Ceiling section 0.55mm thk. xweb size 51.5mm & flanges 26mm. Each & 10.5 mm. lips fixed perpendicular to intermediate channel at 457mm. c/c Gyp board is screw fixed to ceiling section with 25mm. drywall screws at 230mm. c/c. boards to be finished with proprietary supplied jointing tape & jointing compound & sand papered to achieve a smooth finish etc.complete or as directed by the Architec/Bank. Gyp ceiling where necessary as normal specification Rate should include all types of cut-outs, grooves ,moulding & plain troughs for tube lights / Down Lighter as directed by the designer. Note: Where RCC Slab is old and concrete is weal, the G.I.suspended channel shall be fixed with epoxy chemical and necessary load test to be	Sft.	640.00		
2	<b>ARMSTRONG FALSE CEILING</b>				
	Providing and fixing of Armstrong make Mineral fibre Ceiling Boards in true horizontal level suspended on inter locking Grid system made of Hot Dip Galvanized steel sections powder coated XL -15 mm as per manufacturers specification including making opening for electrical and air conditioning fitting complete as directed. The tiles and grid system FRAMEWORK XL-15 mm Main Runner of 3000mm spaced at 1200mm centre fixed to soffit by approved hangers at 1200mm distance. First and last hanger should not be at a distance more than 450mm from the adjacent wall.XL-15 mm 1200mm cross Tee to be interlocked between Main Runner at 600mm centre to form 1200x600mm module 600mmx600mm module to be formed by fixing XL-15mm 600mm Cross Tee between centre of 1200mm Cross Tees.19X19 mm Wall Angle to be secured to wall at 450mm centers Suspension to be done by using 2mm pre-straightened GI wire using anchor fasteners. Make - Armstrong - ANS Micro & Supra fine XL frame work. Note: Where RCC Slab is old and concrete is weal, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be	Sft.	720.00		
3	<b>FULL HT SOLID PARTITION</b>				
a	Full Height Solid Partitions : Providing and Fixing of Full height partitions all made with Alumimium section Framework of 2" x 1" x 1.5mm Thikness with 2'0"x 2'0" c/c vertically and horizontally. Frame to be covered with 8 mm plywood of (Century/Archid/Greenply) from both sides. 1mm thick laminate of (Century/heritage/Archid/Greenply) to be covered from both the sides of the partition. Frame should be properly fixed to the Floor, Vertical members should be firmly to the Slab and side wall available. Laminate should be considered up to two or three colour combination. All as per the design suggested at site and instructions of Architects.(Frame work above false ceiling done for fixidity shall not be measured but contractor may factor it while quoting their rate as measurements up to false ceiling level only be taken). Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISI.	Sft.	110.00		
	Re-lamination of the existing partition for the Manager cabin Full Height Solid Partitions using 6 mm thk ply and 1mm thk laminate of the approved material	sft	120.00		
b	Providing & fixing Aerocon panel 3"/75 mm thk cladding for the saferoom as per design with 14 x 25x 08/1mm thk. square G.I.sections at 20" - 22" c/c mark the floor and then cut the floor channels as per the required lenght.mark the ceiling and fix the ceiling channels with self expansion screws. install the panel by placing the 600mm side of the panel parallel to the floor. keep the groove side of panel towards wall end and slowly put the panel into the floor channels with heavy duty screw drivers without damaging anything complete in all respect.	sft	690.00		
4	<b>SEMI GLAZED PARTITION WITH DOOR - BRANCH MANAGER CABIN &amp; DISCUSSION ROOM</b>				
	Full Ht. Partitions : Same as Item no 3 but 8mm toughened Glass ( upto 7' ht with support from the ceiling) with Etching design or One way vision film approved design should be provided with 35mm x 12mm Steam beach Molding duly melamine polished. The glass will be starting from 1'-0" ht from ffl for Manager cabin. but the glass for discussion room will be starting from 3'-0" ht from ffl for Manager cabin.All as per the design and instructions of Architects. Plywood wherever mentioned BWR GRADE IS 303.AS GIVE IN THE ITEM NO (FOR MANAGER AND CASH) For cash Rate include with Side Partition Also.	Sft.	470.00		

ESTIMATES FOR INTERIORS WORK FOR CANARA BANK AT RAH GUNTUR					
Sr.No.	Description	Unit	Qty	Rate	Amount
5	<b>PARTLY GLAZED LOW HT PARTITION</b> Low Ht /Half Ht Solid Partitions: Same as Item no 3 but Low ht or Half height as per design. Edges of the partition to be covered with 3"x1.5" Steam beach wood duly male mine polished moulding. All as per the design and instructions of the design in charge.ply wood wherever mentioned BWR GRADE IS 303,(AT WORK STATION AND BETWEEN TABLES)	Sft	390.00		
6	<b>Re Lamination of the existing Branch Manager Table ( 5'-0" to 6'-0" x 3'-0") with side unit</b> Relamination of the existing Manager Tables ( with side unit) with 6mm ply and new laminates ( bank brand) . top surface shall be laminated with 1.5mm thick rubber wood laminate.12mm thk plain glass on table top as per shape with cutting for wire manager. The internal surface shall be painted with to coats of enamel paint (VANILLACREAM, CODE -3229) of Asian paints, over a coat of primer. The cost should include necessary change of hardware Moulding handles & Godrej make drawer locks with common key for cash drawers, footrest etc. complete as per design. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x 3/4" inner side) and polishing done etc. complete as shown in drawing. for the section incharges and DM.All as per the design and instructions Bank. The rate should includes all material , labours and conveyance cost.	No.	1.00		
7	<b>Officer/Clerk counter</b> Providing & fixing officers/clerk running counter without side unit of 4'-6" length , 2'-6" height and 2'-6" width , Counter to be made up of 18mm. thk. Plywood framework <b>with 12mm. thk. Clear glass on top</b> and small drawer above it on other side of Key Board drawer. Each unit shall be provided with a sliding key board tray 2'-3" of wide with sliders, cupboard below the drawer with locking arrangements aluminum handle, brass hinges etc the front back & top surface shall be laminated with 1.5mm thick rubber wood laminate.12mm thk plain glass on table top as per shape with cutting for wire manager.The internal surface shall be painted with to coats of enamel paint (VANILLACREAM, CODE -3229) of Asian paints, over a coat of primer. Provision for c.p.u stand 1'-0" x2'-0" & footrest of size 75mmx 38mm shall be made at the bottom. Wire manager shall be provided at the corner of the counter top. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x 3/4" inner side) and polishing done etc. complete as shown in drawing.	Nos.	16.00		
7b	Providing and fixing <b>OFFICER/MANAGER TABLE with SIDE UNIT of 4'-6"to 5'-0" X2'-6"</b> , table made out of 18 mm BWR grade ply board (approved make )structure with edges fixed with teak wooden lipping ,having officer table top 2'-6" from the ground level & 2'-6" clear top width, a unit of drawer in 18mm thk BWR plywood. it will have a side unit of size 1'-6" x 3'-0". Each unit shall be provided with a sliding key board tray 2'-3" of wide with sliders, cupboard below the drawer with locking arrangements aluminum handle, brass hinges etc the front back & top surface shall be laminated with 1.5mm thick rubber wood laminate.12mm thk plain glass on table top as per shape with cutting for wire manager. The internal surface shall be painted with to coats of enamel paint (VANILLACREAM, CODE -3229) of Asian paints, over a coat of primer. Provision for CPU stand 1'-0" x2'-0"(if required) & footrest of size 75mmx 38mm shall be made at the bottom. Wire manager shall be provided at the corner of the counter top. All exposed edges of the block shall be provided with teak wooden beading (3"x1"front side and 1"x 3/4" inner side) and polishing done etc. complete as shown in drawing.	Nos.	2.00		
8	<b>GLASS WORK</b> -Providing and fixing 12mm thick clear Toughened Glass in front of public counters, cash counters & elsewhere held together with SS clamps & SS studs as per approved sample including providing and fixing etching fim of 3M Make as per design, steam beach beadings (18x18mm), steam beach moulding (62 x 31mm) along with polish & melamine spray finish etc. complete instructions given by the architect.	Rft	82.00		
9	<b>DISCUSSION TABLE</b> Providing and Fixing <b>ROUND TABLE</b> in the discussion room of with 1MM thk laminate size of 4' dia Counter made up of 19mm BWR ply board finished with 1.0 mm thk laminate. With necessary support. as same as item no 8	rft	14.00		
10	<b>Storage Units</b> Providing & fixing storage units made up 18 mm. thk. plywood framework, 6 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminate ed surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design. LOW HEIGHT STORAGE	Sft	32.00		

ESTIMATES FOR INTERIORS WORK FOR CANARA BANK AT RAH GUNTUR					
Sr.No.	Description	Unit	Qty	Rate	Amount
10b	Providing & fixing storage units made up 18 mm. thk. plywood framework, 6 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminate ed surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design. FULL HEIGHT STORAGE . (7' to 8' as per the site requirement)	Sft	290.00		
12	<b>Main Entrance Door with Partition</b>				
	Providing & fixing main door & partition made up of 12 mm thk. Clear toughened glass shall be fixed in.Ozon / Enox make patch fitting with necessary hardware.With application of sealant from all sides. Edge polish for all exposed sides of glass. Complete as per design Door size 7'0" x 3'0" - Providing & fixing main door made up of 12 mm thk. Clear toughen glass shall be fixed in.Ozon / Enox make patch fitting with necessary hardware like floor spring, 12" S.S. finished decorative handle pair,& locking arrangement. Edge polish for all exposed sides of glass. Complete as per design for	Sft	90.00		
14	<b>PILLER /WALL PANELLING</b>				
	Fabricating and fixing column paneling to consist of Alumimium section Framework of 2" x 1" x 1.5MM Thickness at spacing not exceeding 600mm bothways (horizontal and vertical). Paneling framework to be secured to wall surface/column surface.Paneling framework to be clad on one side with 8mm thick commercial ply finished with 1.0mm thk laminate including skirting of 100mm high & 12mm x 12mm groove at skirting level. Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISI.(THIS ITEM IS AS PER SITE CONDITION AND AS PER THE REQUIRMENT ) for branch.	Sft	250.00		
15	<b>SHUTTER BOXING - ACP PANELLING</b>				
	OUT OF SHUTTER BOX Supply installation and fixing of Acp cladding with side pillars and front at the entrance to be cladded with standard approved bank colour and acp to be done one aluminum frames to be made as per the standard specifications and design given by the Architect.	Sft	70.00		
16	<b>SOLID DOORS:</b>				
	Solid Doors : providing and fixing of solid door and Door Frame should of best quality non-teak wood of 4.5"x2.5" section without Glass. Instead of glass, matching laminate on plywood to be used for maintaining uniform appearance. Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISI. rate includes with laminate panel, nails adhesive , hardware ,labour ,transportation,lifting, etc for LUNCH,UPS,RECORD and PASSAGE	Nos	3.00		
17	<b>ROLLER BLINDS:-</b> Providing and fixing Roller blinds of 100mm of vista Lavour of approved shade/Zebra And pattern as suggested by the bank. The rate shall include necessary scotch gurd treatment on both sides. The overlapping should be uniform and adequate.Necessary oparative arrangements,frames to be provided. The work to be completed as per specification and approval of the architect.MAKE(vista) at banking hall and cabins windows.	Sft	50.00		
18	<b>SOFT BOARD:-</b> Providing and fixing soft board with necessary framework with 12mm plywood on top 12 jolly board to be fixed finished with fabric @Rs120 , with necessary mouldings duly polished along the periferi.	No.	1.00		
19	Providing and fixing of cupboard (7'-0" x 4'-0") /storage in the branch entrance with 12mm Thick BWP ply with 1.0mm thick laminate on the other side to be of bison / fire proof board for enclosing name panel board and stabilzers for Acs as per the site condition and instuctions given by the bank.	Sft	36.00		

<b>ESTIMATES FOR INTERIORS WORK FOR CANARA BANK AT RAH GUNTUR</b>					
<b>Sr.No.</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
20	<b>CIVIL WORKS</b>				
	Dismantling of the wall for the door and brick works in the wall by removing the door. All works includes plastering and painting complete.	LS	1.00		
21	<b>PAINTING OF THE BANKING HALL</b>				
	Providing & applying Luster Paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.	Sft	620.00		
22	Dismantling existing Interior items, and Temporary table arrangement etc... Complete job for smooth functioning of regular branch operations until the completion of new furnishing works	LS	1.00		
	<b>TOTAL AMOUNT FOR BRANCH INTERIOR WORK</b>				-
	<b>TOTAL AMOUNT</b>				
	<b>DISCOUNT</b>				
	<b>GRAND TOTAL AFTER DISCOUNT</b>				