

CANARA BANK
BOQ FOR FURNISHING WORKS OF DBU AT RAJIV GANDHI UNIVERSITY, DOIMUKH, ARUNACHAL PRADESH

S.No	Details of the BOQ	Unit	Qty	Rate	Amount
	FURNISHING WORKS				
1	Outside wall/ Column Panelling with ACP - Providing and fixing panelling on wall/ column with 3/4.0mm thk ACP in Pure White Colour. Framing shall consist of Aluminium framing 50 mm x 25 mm @ 600mm C/C. Both ways horizontally and vertically on the wall / with Aluminium Sections of 2"x1" as directed by Bank / Architect. This framing shall be finished with 3/4 mm thick "Aluminium Composite Panel". The rate shall inclusive of necessary fixtures and fittings, sealant etc. complete.	SFT	102		
2	Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consists of aluminium sections 50mm x 40mm(wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 1/4" thk plywood finished in approved shade of laminate of thickness 1.0mm. Wooden moulding, lipping etc as directed by the architect shall be provided wherever required. The panelling should be done in such a way that it can house the sliding folding partition when fully opened and remain in flush with the panelling	SFT	296		
3	Providing and fixing , with 4 Nos 5/6mm thk Solid Acrylic sheet having 18mm wide strips @ 25mm spacing in banks Brand colour as directed by the Architect/ EIC, on existing partition/ panelling with company approved adhesive/ Silicon in desired pattern	RFT	17		
4	FULL HEIGHT SOLID PARTITION FINISHED WITH ONE SIDE LAMINATE OVER PLY AND OTHER SIDE WITH A.C BOARD FINISHED WITH POP & PAINT INCLUDING DOOR (Having Fire Rating of 3Hours for UPS Room)- Providing & fixing in position Partition in Aluminium frame work in 2'x 2' grid (horizontally and vertically) comprising of 50mm x 50mm x 1.8mm thk Aluminium Section covered with with 8/10 mm thick Aesbostos Sheet and finished with POP and paint on one side and the other sides to be finished with 8/9mm thk Plywood and finished with approved shade of laminate. It shall also consist of a Flush door of required size and fixed with aesbostos Sheet on one side and 1.0mm thk Glossy laminate on other sides with the same specifications as mentioned in the above line. Rates shall be inclusive of all hardware fittings and fixtures such as - hinges, handles, locks, door closer, door stopper etc. all complete	SFT	84		
5	Semi height Semi Glazed Partition - Providing and fixing in position Semi Height Semi Glazed Partition in between machines at Self Service Area in approved shape as per the approved design and as directed by the architect/ EIC, in frame work at 2' x 2' grid (horizontally and vertically) with 6mm plywood on both sides finished with 1 mm thick glossy laminates of approved shade and colour as shown in drawings.Item to include 8 mm thick glass with itching as per design and as directed by the Architect/ EIC. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.	SFT	38		
6	Dust bin - S.S perforated/ Solid Dust Bin with (pedal operated) opennable Lid/ Cover , overall dia 300/400mm and height 600mm	Nos	2		
7	Shutter Boxing – Providing and fixing shutter boxing with 3.0/4.0 MM thk external grade ACP in pure white colour of Alu Décor/ Alstone/ Reynobond or equivalent make and fixed to a framework made of 50 mm x 25mm aluminium box sections as per detail. Cost to include all necessary framework, support and fixing details, etc.. Complete. Note the mode of measurement would be the multiplication of the length and the height of the boxing	sft	54		
8	PLYWOOD BOXING ABOVE ATM, PASSBOOK PRINTER/ ACCOUNT OPENNING ETC MACHINE- Frabricating & Erecting 18/19mm thk Plywood boxing at a desired height as per design above machines at Self Service Area as per design and as directed by the architect. It shall be finished with 1.0mm thk Glossy laminate of approved shade and make in approved pattern and as directed by the architect/ EIC. Necessary groove for fixing of continious light should be made on the bottom surface of the box as per the approved design and as directed.	SFT	32		
9	GYPSUM BOARD CEILING WITH POP AND LUSTURE PAINT - Providing and fixing 1/2" thk Gypsum India Board false ceiling at levels as shown in the drg. From the FFL. Rate shall be inclusive of all Gypsum India Components contained G.I perimeter channels of size 0.55 thk having one flange of 20mm and another flange of 30mm and a web of 27mm along the perimeter of the ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws at 610mm centres. The suspending G.I intermediate channels of size 45mm, 0.9mm thk with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angles of width 25mm x 10mm x 0.55mm thk fixed to soffit with G.I cleat and steel expansion fastner at every 610mm c/c. Ceiling sections of 0.55mm thk having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in directions perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment. The board are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & jointing paper tape. Rate shall be inclusive of any vertical ceiling part, cutouts for spot and tube lights, a.c grills, fire and security system cutouts. All Sections should adhere to the manufacturer's guidelines .Rate shall be inclusive of required numbers of POP to obtain a smooth surface and then finally finishing with approved shade of lusture paint	Sft	90		
10	MODULAR FALSE CEILING - ARMSTRONG METAL MODULAR CEILING / equivalent make				
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm grid sections) false ceiling of size 24" X24" AT LEVELS AS SHOWN IN THE DRG. FROM THE FFL. Rates shall be inclusive of providing the total system with installation etc. The contractor has to maintain all ceiling tiles in good order and replace the defective tiles (at his own cost) before the handing over of the site.	sft	80		
11	MAIN ENTRANCE & WINDOWS				
	MAIN DOOR -Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, srews, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)	SFT	21		

CANARA BANK
BOQ FOR FURNISHING WORKS OF DBU AT RAJIV GANDHI UNIVERSITY, DOIMUKH, ARUNACHAL PRADESH

S.No	Details of the BOQ	Unit	Qty	Rate	Amount
	FURNISHING WORKS				
12	FIXED GLAZING - Providing and fixing full height fully glazed toughened glass partition with 12mm thick toughened glass using S.S Patch fitting of DORMA or equivalent make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling. Rates shall be inclusive of frosted film/ glass itching with bank's Logo in approved patter, style and shade.	SFT	32		
13	MISCELLANEOUS ITEMS				
	Writing ledge made with 18/19mm thk plywood , cantilevered from wall/ partition and finished on top , sides and bottom (Below top) with 1.0mm thk glossy laminate of approved shade and make	RFT	5		
14	Soft board 3'X2' - Providing and fixing soft board incl of 6mm ply base backing and 12mm thk. crock sheet which is wrapped all around with fabric in Approved Shade. The edge trims to be finished in 19mmx 6mm lipping patti with melamine finish. The rate should i	Nos	1		
15	Fire Extinguisher 1kg ABC From Minimax / Safex	Nos	1		
16	WOODEN FLOORING (ILVT) AT RD'S CABIN, CONFERENCE ROOM & VC WOOM - Providing and fixing 8/10mm thk Laminate Wooden Flooring (LWF) with minimum 10 years company's warranty of Merino / Mikasa (Greenlam) / Square Foot/ VOX etc make as per design and as directed by the architect, with veneer thickness upto 0.60mm and core material being High Density Fibre Board in brushed/ matt finish, having a 10 years warranty on the use. The product should comply to EN14354. The Board should be constructed in 3 layers in order to minimise expansion and contraction with in the floor boards and the direction of the fibres within each layers should be oriented in such a manner that each layer is aligned at an angle of 90 degree with the other. It should fulfill the classification of Class G as per the fire classification. The Quoted Rate Shall be inclusive of 4"-6" High Skirting with the same material on all sides in Walls & Partitions without any extra cost. For Payment only the Floor Area Shall be Measured	SFT	140		
17	DRY PLANTER BOX WITH POT & PLANTS (WITH FLOWER POT) - Providing and fixing dry Planters Boxes of avg. size 350mm x 350mm x 300- 450mm(H); The Planter Box shall be made out of 2 nos 18/19 mm thk. sandwiched WPC Board on sides and bottom and finished with 1.0 mm thk laminate of approved shade in approved style and pattern. All exposed side edges of shall be covered with WPC beading finished with similar finish. Rates shall be inclusive of 12-14" dia PVC Flower pot with indoor quality natural plants as per architect's / Bank Officials choice.	Nos	2		
18	COLOURED BRANDING STICKER - Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyster film with required coloured frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.)	SFT	18		
19	FROSTING FILM - Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyster film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.)	SFT	28		
20	8" HIGH CNC CUT ACRYLIC SHEET LETTER - Supplying and Fixing in desired position 8" HIGH CNC CUT Black ACRYLIC SHEET LETTER using 10mm thick acrylic sheet in approved design and font	Nos	12		
21	Sealing of Existing windows with 9/10 mm thk A C Board from inside the premises after properly closing the window and then finally finishing the same with pop and paint in required number of coats so as to have an neat surface	SFT	60		
	TOTAL OF FURNISHING WORKS				