

BOQ FOR INTERIOR FURNISHING WORKS FOR CANARA BANK DBU AT MAHENDRAGARH

| A SCHEDULE - 'A' (FURNISHING WORK) | | | | | |
|------------------------------------|---|--------|--------|------|--------|
| S.NO. | DESCRIPTION | UNIT | QTY. | RATE | AMOUNT |
| 1 | FALSE CEILING (GYPSUM BAORD) | | | | |
| | Providing and fixing Gypsum false ceiling as per drawing including of providing and fixing G.I. Frame work shall comprise of G.I. perimeter channel (MF-6A) of size 0.50mm thick having one flange of 19.12 mm and another flange shall be of size 29.12 mm and a web of 26.12 mm along with perimeter of ceiling, screw fixed to the beam to the required curvature with nylon sleeves and screws at not exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to soffit with G.I. cleats and steel expansion fasteners as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5mm board and all necessary perimeter channels etc. The joints to be properly mended with paper tapes and gypsum compound all complete. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be completed as per specification , approval of the bank. No Drop or design(if any)will be considered as extra measurement it will be considered flat ceiling. (Only plan area to be measured for payment) .No extra payment will be made for the cutting of light points , stain glass,cove lighting etc. The measurement will be taken in one level , rate should include the drops also, no extra amount will be paid for the | Sq.Ft. | 205.00 | | |
| 2 | FALSE CEILING (ARMSTRONG CEILINGS – FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL) | | | | |
| | Providing and fixing false ceiling system manufactured by M/s. Armstrong World Industries using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. and wall angle of size 19 x 19 mm., having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 600mm c/c. in both directions using 2.0 mm. thick pre-straightened GI wire laying FINE FISSURED MICROLOOK WITH SILHOUETTE GRID(BLACK REVEAL) ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.55, Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/mOK, Humidity Resistance of 99% , having Fire Performance CLASS O / CLASS 1 (BS 476), surface having 3 coats of white paint with Fine Fissured, back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete.(Branch & ATM) | Sq.Ft. | 130.00 | | |
| 3 | FULL HEIGHT SOLID PARTITION | Sq.Ft. | 180.00 | | |
| | Full ht. Solid Partition including flush door & strong room partition up to 7' only :- Providing and fixing solid partition , the framing shall made out of aluminium hollow section of 65mm x 37mm size 1.0mm thick of JINDAL / INDAL as internal frame structure placed horizontally & vertically at max distance of 2'-0" x 2'-0" center to center. On one side Fixing 3 mm thick ACP to be in 2' wide panels or distributed equally. Panels to be fixed to the frame with 3M or equi-valent adhesive. Joints to be finished with Silicon based sealant.finished with silicon on one side & other side finished with 12mm thick Plywood finished with 1.0mm thick laminate on top of approved shade with groove pattern as per instructions of Architect. The rate shall include the cost of providing skirting of 100mm wide lined with 1mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1mm thk laminate complete. Laminate Should be considered up to two or three color combination. The edge beadings with steam beach wood should be finished with melamine polish if required, frame work above false ceiling done shall not be measured but contractor may factor it while quoting these rates as measurment up to false ceiling lvl.. The rate inclusive of providing & fixing of required flush door of 37mm thick approx. with 1.0mm th.laminate both side with steem beech wood chowkhat of size 75mm x 65mm approx and Item includes Heavy-duty SS ball bearing butt hinges 100 x 5.5 mm (4 Nos. per shutter) with screws etc.The shade of laminate finish to be got approved from Bank. . All as per the design and instructions Bank Note :- For the purpose of payment partition shall be measured including the area of door/door frames up to false ceiling height. Framework shall be regidly secured to floor, bottom of slab & exisitng walls at 2'-0" c/c with dash fasteners. | | | | |
| 4 | PANELING | | | | |
| a | WALL / COLUMN PANELING (Full Ht. - till soffit of false ceiling) (IN ATM Room / Walls in Manager Cabin / Walls in Cash cabin / Independent pillars in branch hall / Side wall adjacent to Officer Table ONLY) | Sq.Ft. | 450.00 | | |

BOQ FOR INTERIOR FURNISHING WORKS FOR CANARA BANK DBU AT MAHENDRAGARH

| A | SCHEDULE - 'A' (FURNISHING WORK) | | | | |
|-----------|--|--------|--------|------|--------|
| S.NO. | DESCRIPTION | UNIT | QTY. | RATE | AMOUNT |
| | <p>Providing and fixing in position wall panelling in 600 X 600 mm grid (horizontally and vertically) comprising of 25 mm X 50 mm heavy duty GI Box Sections (1.6 mm) with 8 mm thick ply finished with 1 mm thick laminate finish of approved shade and make. The soffits of the doors / windows shall also be covered with paneling as well. Item shall include 100mm high skirting on bottom of the finished floor in Canara Bank Blue shade and a top band of 100mm high from the soffit/ceiling/visible top height of the paneling in Canara Bank Yellow shade. Remaining area shall be finished with 1.0mm thk white laminate of approved make.</p> <p>Note - No paneling shall be provided behind the storage / cabinets / tables sides or any other surface which is not visible (no payment for same shall be entertained by the bank). Entire paneling shall be provided only on visible surfaces as per approved layout or as directed by the Bank. Also, no paneling shall be provided on the columns embedded in walls. The paneling should be provided on independent pillars in the branch hall only that too till soffit of false ceiling.</p> | | | | |
| | Note:- In case of wall not being true to plumb extra shims of aluminium section shall be provided. Nothing extra shall be payable in this regard. | | | | |
| | <p>Note:</p> <p>a) In case of false ceiling, area of panelling payable will be below the false ceiling only.</p> <p>b) Measurement of height shall be taken from finished floor only, in case of varying heights on either side of panelling, average height shall be considered.</p> <p>c) Openings/ door/ glass shall not be measured for payment.</p> | | | | |
| | | | | | |
| b | ACP SHUTTER BOXING & EXTERNAL SURFACE PANELING | | | | |
| | <p>Providing and fixing Aluminum Composite panels in all colours of approved brand for wall cladding at all heights and elevations including necessary aluminum composite panel consist of 3mm thermoplastic core of anti oxidant LDPE sandwiched between two skin of 0.5 mm thick alloy sheet making a total sheet thickness of 4 mm. The surface shall be finished with PDVF base coating on the top side and service coating on the reverse side shall be with a polymer paint. Coating shall confirm to ECCA of AAMA. The system shall design to withstand wind pressure of 200 Kg/Sqm and shall be fixed to the masonry/RCC walls with necessary clamps, bracket and anchor fasteners. All Clamps and brackets shall be hot dip galvanized minimum 80 micron thick and confirmed to IS : 4759 - 1996. The extruded aluminum sections shall be anodized in approved colour with anodic coating minimum 20 microns. Extruded section shall be of 6063 T5 or T6 alloy confirming to ASTM B 221. (items include cost of aluminum frame, ACP Panels, Cramps 110mm size, weather sealant, gasket, foam, fixtures, scaffolding, all machineries and any other fastening strips, nuts, bolts, rivets, washers, etc. complete).Item shall include to provide EPDM gaskets (Make:OSAKA/Satya or equivalent), open cell polyethylene backer rods, weather sealant etc. The weather sealant shall be Dow Corning 991 or equivalent and the width of the gap filled with sealant shall be as specified</p> | Sq.Ft. | 150.00 | | |
| | | | | | |
| 5 | TOUGHENED GLASS PARTITION | Sq.Ft. | 150 | | |
| | <p>Providing and fixing 12mm thk toughned glass partition with all sides polish, using dorma make patch fittings, the dimension of the glass as per dwg., includes necessary one way vision frosted films to be fixed on the glass, the joints between the glass to be filled with necessary silicone of approved make. (BACIS COST OF ITEM RS. 600/- SQ.FT.)</p> | | | | |
| 6 | TOUGHENED GLASS DOORS | Sq.Ft. | 25 | | |
| | <p>providing and fixing 12mm thk toughned glass door with all sides polish for cabins including dorms make patch fittings includes the bottom patch to be with automatic door closer, a handle and a lock necessary frosted film to be fixed as per design on cabins. (BACIS COST OF ITEM RS. 800/- SQ.FT.)</p> | | | | |
| | | | | | |
| 7 | Glass divider: | | | | |
| | <p>Providing and fixing of 12 mm thick toughened frosted glass divider between machines with necessary fittings and hardware as per drawing</p> | Sq.Ft. | 60 | | |
| | | | | | |
| 8 | <p>Supplying and fixing of Dorma/GEZE Dline / Hardwyn/Godrej or approved equivalent Door Closed for wooden door for Branch manager, Banking ahll, Chief Cashier.</p> | Nos | 1 | | |
| 9 | <p>Supplying and fixing of mortice door lock of hardwyn make HML-480 Lock Body 304 Stainless Stell. (in BM Cabin , Store room . Cash cabin shall be Godrej Night latch.(atm 1 No.)</p> | Nos | 1 | | |
| 10 | <p>Supplying and fixing of door stopper SS Grade 304, HESSF-2C hardwyn make.</p> | Nos | 1 | | |
| | | | | | |
| 11 | STORAGE CABINETS / CREDENZAS | Sq.Ft. | 40 | | |
| | <p>Providing & placing in position box type storage cabinets / Credenzas 18" deep & height as given below made out of 19mm approved board with 1mm laminate with shade as per bank's approved scheme. The top of the low height storages / credenzas shall be finished with 1.0mm thk Canara Bank Blue laminate. The sides, partition, top, shelves & bottom shall be made out of 19mm thk. approved board and back made out of 6mm thk. approved ply. Item shall have one 6" high drawers on top made out of 19mm thick approved ply / board complete with handles, locks etc of approved makes. The shutters made out of 19mm commercial ply wood finished with 1.0mm thk laminates of approved scheme on the outer surface shall cover the remaining space available below the drawers. All inner surface shall be finished with 0.8mm thick white laminate with matching edge tapes for all exposed edges. A 100mm high top band shall be provided on top front face of the storage cabinets / credenzas finished with 1mm thk canara bank yellow laminate & 100mm high skirting finished with canara bank blue laminate shall be provided as per approved make.</p> | | | | |

BOQ FOR INTERIOR FURNISHING WORKS FOR CANARA BANK DBU AT MAHENDRAGARH

| A | SCHEDULE - 'A' (FURNISHING WORK) | | | | |
|-------|--|--------------|---------|------|--------|
| S.NO. | DESCRIPTION | UNIT | QTY. | RATE | AMOUNT |
| | The drawer must be finished with 1.0mm thk laminate of shade as per Bank's scheme on outer surface and 0.8mm thick white laminate on the inner surfaces. The drawers shall be supported with SS telescopic sliding channels of approved make with smooth push-pull mechanism along with SS handles and individual locks. The shutters below the drawer shall be supported with soft close clip-on SS Hinges of approved make of required number depending upon the size of the shutter. Each shutter shall be supplied with necessary accessories and hardware such as individual locks, SS handles, magnetic ball catchers, SS tower bolts, individual locks etc. of approved makes screwed and fixed rigidly. Horizontal shelves & vertical planks made out of 19mm thick commercial board shall be provided inside the shutters in such a manner to create optimum number of storage chambers each of equal storage space depending upon the size of the cabinets / credenzas. These partiotions shall be finished with 1mm thick white laminate on all faces and exposed side (thickness) edges of the partition members shall be finished with teakwood lipping and 2 coats of melamine polish. <u>Note.-</u> For the purpose of contractors bill payment, only front elevation area shall be measured | | | | |
| A | Full Ht. Storage (8'-6" High) (FOR space in record room) Same as Sr. No.3 but without drawers & with shutters fitted with SS butt hinges, vertical and horizontal shelves of appropriate size to utilize the entire space available as per layout for creating optimum space inside storage chambers at different heights. | 35.00 | Sq. Ft. | | |
| B | Box Framing as per above specification above machine as per instruction given by Architect. | 60.00 | Sq. Ft. | | |
| 13 | PIN UP / NOTICE BOARD | | | | |
| | Providing and fixing soft board with necessary framework with 12mm BWR PLY board on top 12 jolly board to be fixed finished with fabric @Rs80 , with necessary mouldings duly polished along the periferi. All as per the design and instructions Bank. | Sq.Ft. | 12 | | |
| 14 | PAINTING PLASTIC PAINT | Sq.Ft. | 800 | | |
| | Applying 2 Coat putty with primer and Providing and applying Plastic emulsion paint (asian) of approved make and shade on walls including scrapping off, preparing the base & applying 3 or more coats of approved make, color and shade to give an even and smooth surface on new work including necessary scaffolding, coat of cement primer etc. all complete as per direction of Bank. (only banking hall.) | | | | |
| 15 | ENAMEL PAINT | Sq.Ft. | 300.00 | | |
| | Providing & applying 1 st quality oil paint of approved make, quality & shade. The rate shall include scrapping, levelling & preparing the surface with primer quote. | | | | |
| 16 | ACRYLIC SOLID STRIP ON PANELLING SURFACE | | | | |
| | Providing and fixing of 5mm thk solid acrylic sheet, providing 18mm wide strips @ 25mm spacing, in Bank's Brand Colours as instructed using adhesive & rubbing & polishing top surafce so that there will be no joint visible as required by Architect. The sheet need to place in a manner that there will be no joinry on top of the surface of acrylic sheet. The sheet need to be applied on top surface of panelling surface & wherever Architect give instruction to apply it. For measurement purpose only front surface is measured for payment, no thickness or moulding will be counted. | Sq.Ft. | 15.00 | | |
| 17 | ACRYLIC SOLID CUT LETTER ON PANELLING SURFACE | No of Letter | 12.00 | | |
| | Providing and fixing Cut letter branding using 10mm thick acrylic sheet, providing 12mm wide letter having height of 150mm in Bank's Brand Colours as instructed using adhesive & rubbing & polishing top surafce so that there will be no joint visible as required by Architect. The sheet need to place in a manner that there will be no joinry on top of the surface of acrylic sheet. The sheet need to be applied on top surface of panelling surface & wherever Architect give instruction to apply it. For measurement purpose only number of letter is counted for payment, no thickness or moulding will be counted. | | | | |
| | GRAND TOTAL FOR FURNISHING (A) | | | | |
| | * GST EXTRA AS APPLICABLE | | | | |