

CANARA BANK, CIRCLE OFFICE DELHI					
SCHEDULE OF QUANTITIES FOR RENOVATION OF FURNISHING WORK AT CANARA BANK , MSME NEHRU PLACE BRANCH, NEW DELHI .					
S.No	Particulars	Quantity	Unit	Rate	Amount
1	LAMINATED PARTITION				
	FULL HEIGHT GLAZED PARTITION				
	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be finished with 12 mm thk. MDF board on both side and finished with 1.00 mm thk. texture/ ultra gloss matte Laminate in all direction/ combination and having 1.00 mm wide skirting in SS Satin brush metal laminate of make Archidlam/Green or approved equivalent including grooves as / Architect. Item include 65 x 65 mm teakwood member for door frame and additional framework and teakwood beading required for providing glazing. All exposed teakwood surface, grooves and the like to be finished in melamine polish of matching laminate colour including all necessary fitting and SS hardware of make dorma. The rate to include provision of extra frame work as necessary for skirting and making cut- outs for electrical switches, switch boxes, conduiting, door / glazing as per drawings. The edge beadings with steam beach wood should be finished with melamine.				
	8mm approved make clear float glass shall be provided above 2' 6" from ff.lvl. or as advised by architect/ bank with necessary steam beach moulding finished with melamine. The rate shall include necessary etching film / LOGO.	240.00	SQ.FT.		
2	FULL HEIGHT PARTITION (SOLID PARTITION)				
	Providing and fixing partition framing shall consist of Heavy duty (14 guage) Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be finished with 12 mm thk. MDF board on both side and finished with 1.00 mm thk. texture/ ultra gloss matte . The shade of laminate finish to be got approved from Bank / Architect. The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine.	420.00	SQ.FT.		
3	FULL HEIGHT SOLID PARTITION WITH BISON BOARD ON BOTH SIDE PAINT				
	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be finished with 12 mm thk. BISON BOARD on both side and finished with Enamel paint of make Archidlam/Green or approved equivalent including grooves as / Architect. including all necessary fitting and SS hardware of make dorma. The rate to include provision of extra frame work as necessary for skirting and making cut- outs for electrical switches, switch boxes, conduiting, door / glazing as per drawings.	180.00	SQ.FT.		
4	LOW HEIGHT PARTITION				

	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The framing shall be finished with 12 mm thk. MDF board on both side and finished with 1.00 mm thk. texture/Ultra gloss matte Laminate finished with melamine polish. The shade of laminate and polishing finish to be got approved from Bank / Architect. The 1.00 mm wide skirting in SS Satin brush metal laminate of make Archidlam/ Green or approved equivalent including grooves as / Architect. Rate shall be inclusive of necessary hardware items, etc. Complete. The rate to include for provision of extra frame work as necessary for skirting and making cut out for electrical switches, switch boxes, conducting, receiving A.C. etc. as per drawing .				
	A 70mm x 15mm steam beach moulding with champhered edge is to be provided on all external edges & finished in melamine as per details. Providing and Fixing inserted Soft board / White boards / Glass maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / Glass.	340.00	SQ.FT.		
5	WALL PANELLING OVER COLUMN & WALL				
a)	Providing & Fixing of the wall panelling , made of Heavy Duty Aluminium section 50x50mm @ 600 mm c/c both ways horizontally and vertically on the wall providing over 12 mm thick MDF board with 1.00 mm thick Ultra / High Gloss laminated of approved quality laminate and shade shall be fixed on faces of panelling as per design with groove, skirting shall be 100 mm high finished with 1.00mm laminate. Wooden moulding ,lipping etc.as directed by the bank.	2100.00	SQ.FT.		
b)	Same as above but panelling to be finished with Laquered glass 12mm thick wall adhesive of approved brand and manufacture all complete as per the direction of architect / engineer - in - charge.	64.00	SQ.FT.		
6	Providing and Fixing notice board /display board,made of 50x25mm .Meerandi wood frame with 6mm thick comm.ply /particle board with 12mm thick board covered approved fabric, with 40x25 mm teak wood moulding all around finished with melamine polish.	150.00	SQ.FT.		
7	CUP BOARD (Low Height)				
	Providing & Fixing low ht. cabinet of height of cupboard shall be 750mm to 900mm with 19mm th. Comm. Board , Ultra / High Gloss matte 1.00mm thick laminate to be fixed all exposed surface (side, top, & front). The rate includes necessary hardware such as hinges, godrej lock brass handle, beading to be polished , all the inner surface shall be laminated finished .	310.00	SQ.FT.		
8	FULLY GLAZED PARTITION - WITH TOUGHENED GLASS				
	USING DORMA MAKE FITTINGS				
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using PT Standard fittings like PT90/ PT92 of DORMA make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.	220.00	SQ.FT.		

9	GLASS DOOR WITH FLAMELESS ON PATCH FITTING				
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cilinder - US 10, Handle - TG 9300 EQ - S 25mm dia X 300mm length)	72.00	SQ.FT.		
10	FALSE CEILING (Armstrong Grid)				
	P/F in position 600x 600x15 mm prima fine fissured tegular in 24 mm eposed tee white with trulok suspension systems with nrc value of 55 (acoustic performance) false ceiling of approved quality over M/S Armstrong world industries (india) Ltd trulok suspension systems of required weight as per architects app at reguired spacing, finishing of all joints neatly to proper line & level including providing of additional framework for electricals fixtures.including giving trap doors where ever required. Diffusers,cutouts for fire sprinklers etc. as per the specifications approved by architects Including necessary scaffolding supports,suspenders etc.	1200.00	SQ.FT.		
11	FALSE CEILING (GYPSUM BOARD)				
	Providing & fixing false ceiling as per design consist of G.I.frame , which includes perimeter channels along with the parameter of ceiling , with intermediate channel of size 45 mmx0.9 mm thick with two flange of 15 mm each @ 1220 mm c/c with ceiling angle of size 25x10x.5mm fixed to bottom of ceiling with G.I. cleat and steel expansion fastener, ceiling section of 0.55mm thick with knurled web of 51.5 mm and two flangesof 26 mm each with lips of 10.5 mm are then fixed to the intermediate channel with connecting clips and direction perpendicular to the intermediate channel at 457mmc/c ,12.5mm thick Gypsum board shall be fixed with screw with filling and finishing the tapered edge with jionting compound.				
	paper tape and painted with two or more coats of plastic emulsion paint over a cot of primer. The item includes P/F perimeter channel of size 20x27x30mm and 0.55 mm thick for light fittings, AC grills, diffusers and cutouts i/c cutting of opening for light fixtures,A.C. etc.with 40x40mm wooden moulding all around the walls / pillars.All complete as per design .(The finished surface area shall be measured.)	1000	SQ.FT.		
12	TABLE (Laminated top)				
	Providing Table in position with writing top , sides and front apron all be made of 19mm thick comm. Board with teak wood lipping on exposed ends of comm. Board .The front apron and sides shall be finished with 1.00mm thick laminate of approved shade with Ultra / High Gloss matte . The writing top shall be provided with 1.00 mm thick laminate of approved shade(as per the sample). The exposed edges of the top shall be rounded on both the edges with teak/rubber wood moulding as per design .The skirting shall be 100 mm high with 1.00 mm thick laminate.				

	There shall be a CPU shelf of size 600 mm x 300mm made of 19 mm commercial block board fixed at height of 150 mm inside the counter with airound teakwood lipping. There shall be wood foot rest made of hollock wood.				
	There shall be key board tray made of 19 mm commercial block board with teak wood lipping and ebco make sliding fitting.				
	There shall be a drawer unit with alround boxing made of 19 mm commercial block board with vertical support of the counter as one sidde. All made of 19 mm commercial block board. The drawer bottom and rear sidde of the unit shall be covered by 6 mm commercial plywood. The front face of the draw shall be covered by 1 mm laminate of approved shade and make. Each draw shall have multipurpose lock (godrej) and SS handle.				
	All the inner surrfaces of table , drawer unit and shelves shall be laminated finished .				
	a) 1800 mm x900mm x 750 mm high, with drawer unit consists of three drawer, mounted on sliding channel (ebco make) (MANAGER TABLE)				
	6'-0" X 3'-0"	1	nos.		
	5'-0" X 2'-6"	11	nos.		
13	SIDE STORAGE UNITS				
	Providing & Fixing storage unit with sides, top , bottom, shutter and shelves all be made of 19mm thick comm. Board of approved quality and make .The shelves shall be spaced at 450 mm c/c .There shall be swing shutter. The rear side shall be made of 6 mm thick comm. ply with laminate finish. The top, sides, shutter and back finished with Ultra / High Gloss matte 1.00 mm thick laminate (in two shades) of approved quality and shade as per design with groove .The exposed edges of the board shall have teak wood lipping .There shall be skirting 100 mm high made of 1 mm thick laminate. All the inner surface of drawer and storage shall be laminated finished.				
	The rate includes necessary hardware such as piano hinges, tower bolts, brass dead lock, magnetic catchers, 4" long SS handle of approved design.				
	a) The size of the storage unit shall be 3'-6" x2'-6' x 1'-6" (deep) with 1.00 thick laminate on top.	10	nos.		
14	CENTRE/SIDE TABLE				
	Providing in position table made of 50x50mm teak wood frame with 40x25 mm cross tie members on all four sides at top and bottom finised with melamine of approved colour and shade at top with 12 mm thick beveled edge tinted glass top.	2	nos.		
	a) 600 mm x 600 mm x 400 mm				
15	Providing & Fixing 12 mm clear float glass on top of Manager tables . The exposed edges shall be grinded and polished.	30.00	SQ.FT.		
16	Poviding & Fixing door closer	11.00	Nos.		
17	Poviding & Fixing Handle Mortize lock	6.00	Nos.		
18	Diluting and injecting chemical emulsion for POST - CONSTRUCTION anti - termite (including the cost of chemical emulsion) along the complete suface area of the wall, floor & ceiling using chemical emulsion @7.5 litres/sq.m. of the vetical surface of the substructure complete with chlopyriphos/ Lindane E.C.20% with 1% concentration.	800.00	SQ.FT.		

[illegible]