

TENDER BOQ FOR FURNISHING WORKS FOR CANARA BANK, FIRST FLOOR (UPPER HALL), KARNAL CIRCLE OFFICE, SECTOR-12, KARNAL

A	FURNISHING WORKS				
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount
1	FALSE CEILING (Including ATM Ceiling)				
a.	Providing and fixing GYPSUM BOARD FALSE CEILING in levels as per the detailed drawing - made up of G.I frames as specified by Gypsum India/Saint -Gobain Gyproc and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel of size 20X27X30 mm and 0.55 mm thick for light fittings, AC Grills, diffusers, suspenders etc. shall be standard sections supplied by Gypsum India/ Saint Gobain. Spacing of intermediate channels shall be at 1200 mm c/c and ceiling section at 457 mm c/c. The work includes taping and jointing, applying primer, two or more coats of plastic emulsion paint of approved shade ICI/ ASHIAN PAINTS make, making cut-out for light fixtures /fittings, etc. The Final coat shall be done with FOAM ROLLER and no brush marks should be visible. Providing of perimeter channels / beading etc. as per drawing complete in all respects.(All measurement in sqft only and finished surface area shall be measured)	1780	sqft		
	b. GRID FALSE CEILING(24" x 24")				
	24"x24" Grid False Ceiling Providing and fixing in the true horizontal level false ceiling system of Armstrong world industries. The suspension system shall be the Armstrong Trulock Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color black or white revealed Silhouette main runners and cross tees to have mitered ends with birds mouth notches to provide mitered cruciform junctions. Main runners to be spaced at 12mm c/c fixed by using 2mm pre straightened GI Wire.Main tee, rotary stitched of size 15mm x44mmx3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mmx44mm x1200mm at every 600 mm c/c maximum and 600 mm c/c cross tee of size 15 mm x 44 mm x 600 mm at every 1200mm c/c maximum and 19mmx19mmx3000 wall angle. All as per the design and instructions Architects (make- Armstrong & thickness of tile- 16 mm)	695	sqft		
	c. Providing & Fixing of Ceiling tiles shall be of high acoustic performance of Decosonic CNBM make and micro edge glass fiber in size 600x600x15 mm of color white/Black. It comprises a high-density glass wool panel covered with painted glass wool tissue for decorative ceiling effect and glass wool tissue on the backside and having sealed edges. It shall have a noise reduction co-efficient of greater than 0.90, light reflection of over 85%, density of 100kg/m3, humidity resistance. To lay the field panel of size 600x1200mm, flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre. Thus a grid system of 600mm X 1200mm is formed. Installation shall not begin until all wet work is completed and dry. Building shall be properly enclosed and under standard occupancy conditions (temperature of 20-40°C and not more than 70% relative humidity) before installation begins (make-Armstrong & thickness of tile- 16 mm)	25	sqft		
2	PARTITIONS WITH WOODEN PRESERVATIVE				
	Low height Partition Providing & fixing of LOW HEIGHT PARTITION (HT. 4'-6") made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of approved make on both faces finished with 1mm thick laminate of approved shade. Till the height of 3'-3" and 1'-3"(10mm thk.) toughened glass on (side & front) top complete with teak beading, The PU polishing teak sections of approved shade as per drawing and fixing of soft board covering with similer fabric. Complete in all respects to the complete satisfaction of the Architect.	0	sqft		
	Full height Partition (Both Side Laminate) Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 10 mm MDF BOARD of approved make on both faces finished with 1mm thick laminate of approved Make and shade. minimum 8 mm thick toughened glass of approved make with etching/taping as required) on the glazed portion. The work includes PU polishing on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. Including doors but excluding cost of door closers, mortise locks.	220	sqft		
	Full height Partition (One Side Veener & Other Side Laminate) Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 9 mm plywood of approved make on both faces consisting of one side 4 mm thick Veneer of approved make & on one side finished with 1mm thick laminate of approved make and shade. The work includes spirit polishing on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. (Basic rate of Veneer-350/- per ft) Including doors but excluding cost of door closers, mortise locks.	145	sqft		

TENDER BOQ FOR FURNISHING WORKS FOR CANARA BANK, FIRST FLOOR (UPPER HALL), KARNAL CIRCLE OFFICE, SECTOR-12, KARNAL

A	FURNISHING WORKS				
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount
d	Full height Partition (Both Side Veneer) Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 9 mm plywood of approved make on both faces finished with 4 mm thick Veneer of approved make and shade. The work includes spirit polishing on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. (Basic rate of Veneer- 350/- per ft.) <i>Including doors but excluding cost of door closers, mortise locks.</i>	700	sqft		
e	Full height Partition with acoustic Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 9 mm plywood of approved make on both faces consisting of 2" mm thk. Polyester fibre acoustic panel finished with 4 mm thick Veneer of approved make and shade. The work includes spirit polishing on woodwork and teak beading etc. Complete in all respects to the complete satisfaction of the Architect. (Basic rate of Veneer- 350/- per ft.) <i>Including doors but excluding cost of door closers, mortise locks.</i>	0	sqft		
f	Providing & Fixing 50mm Glasswool in between the soild partition complete as directed by the Engineer-in Charge	1110	sqft		
g	Sliding folding full height Partition Providing & fixing of FULL HEIGHT PARTITION up to ceiling level partly glazed, made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways 9 mm plywood of approved make on both faces consisting of 2" mm thk. Polyester fibre acoustic panel finished with 4 mm thick Veneer of approved make and shade. The work includes spirit polishing on woodwork and teak beading etc. (Basic rate of Veneer-350/- per ft.) Including doors but all sliding and folding fittings and fixtures with locking system etc. Complete in all respects to the complete satisfaction of the Architect.	0	sqft		
h	SEMI GLAZED PATITION Providing & fixing of partly glazed (12mm toughened glass of approved make as per design), made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both <i>ways 10 mm MDF BOARD of Approved Make on both faces finished with 1mm thick laminate of approved make & shade</i> The work includes providing PU polishing of shade on woodwork and steam beach beading etc. Including doors but excluding cost of door closers mortise locks. Complete in all respects to the complete <i>satisfaction of the Architect./Engineer.</i>	0	sqft		
i	Providing and fixing of fallowing items/ accessories completeed in all including				
i	Mortise locks with handles.(Make Godrej)	12.00	no.		
ii	Hydraulic Door closer.(Make Godrej/ Universal)	12.00	no.		
ii	Floor springs.for Glass door.(Make Godrej/ Universal)	7.00	no.		
3	GLASS DOORS				
A	Providing and fixing of (3'-0"/ 3'-6" X8'-0")12mm toughened glass door with18" long SS handles, floor spring (Ozone-FS- 9400) etc, locking arrangement of brass make at top of standard make(patch fitting), including fixing of Frosted strip vision film & bank logo as directed by the Bank/ Architects.	165	sqft		
B	FIXED GLAZING Providing and fixing external FIXED GLAZING comprising of 12 mm thick toughened glass of approved Make with top, bottom and vertical U Channel frames comprising of powder coated (shade as approved) 16 gauge Aluminium members of approved shade 1.5mm avg. thick top, bottom & vertical member with clip sections as per specifications and drawings to complete satisfaction of the Architect.	170	sqft		
C	BLOCK DOORS Providing and fixing solid core 38 mm solid core flush door finished with lippings in all side with necessary door hinges , cylindrical locks(golden, Godrej) , door clouser, door stoppers, etc with a frame work of T.W./Beech wood size 75mm x 62.5mm with necessary hold fast fixed to the wall/partition. 1 mm laminate to be fixed on both sides duly finished,edges to be finished with wooden lippings.A wooden moulding size 1.5"x2/8" to be provided all along the periferi of the frame work in the both sides . All the wooden area to be duly polished as per specification of the Architect. In case of Partly glazed door 8 mm thk etched toughened glass with granular blasting/sand blasting as per design of the Architect to be fixed with necessary mouldings.	0	sqft		
4	COUNTERS AND TABLES				

TENDER BOQ FOR FURNISHING WORKS FOR CANARA BANK, FIRST FLOOR (UPPER HALL), KARNAL CIRCLE OFFICE, SECTOR-12, KARNAL

A	FURNISHING WORKS				
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount
a	<p>Providing and fixing Tables with 10mm beveled toughened glass of approved make to be fitted on top obtain the total height of 2'-6" as per detailed drawing, made up of 19mm board of approved Make and finished with 1 mm thick laminate of approved make, and shade. Table(with one side drawer unit and another side drawer unit) shall be provided with drawers sliding on telescopic channels and one cabinet with proper locking arrangements and keyboard with telescopic channels . The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, PU polishing of steam beach/ white cedar beading etc. and The inner exposed surfaces to be finished with 0.8 mm thik laminate of approved shade. complete in all respects to the entire satisfaction of the Architect/Bank.</p>				
i	DGM Table size: 7'-0"x 3'-0 x 2'-6"	3.00	nos.		
ii	AGM Table size: 6'-0"x 3'-0 x 2'-6"	0.00	nos.		
c	<p>VC TABLE Providing and erecting in position VC TABLE of approx size 10'-0" X 4'-0" oval shaped (10 seater) as per layout to be made out of 19mm thk Commercial ply top with 60 X 60mm thk t.w.moulding all round the top to be finished with approved 4.0 mm thk veneer with approved polycoat polish, and to be erected on a framing of t.w 75 X 75 mm thk moulded frame including bracings at a regular interval of 900 mm centres finished with ply on both sides & 4.0mm thk veneer (Basic Price Rs 150/- per Sqft) with melamine polish. The exposed middle verticals (approns) shall be finished with approved 4.0 mm thk natural veneer with melamine polish. The table shall have 3 nos of cut outs for placing planters with internal surfaces to be finished with the same 4.0mm thk veneer with polycoat polish. The rate shall include the cost of planters & white pebbles filling the cut out area including 12mm thk toughened glass for the cut out area supported on t.w moulding with melamine polish on sides etc complete. The rate shall be inclusive of necessary cut outs & provisions for video/tele conferencing, wire managers, necessary hardware, cable cubby, cabling arrangements for video / tele conferencing, Poppup box and openings for speakers etc complete in all respects to the complete satisfaction of the Architect</p>	1.00	no.		
d	<p>GM TABLE WITH SIDE UNIT Providing & Fixing of GM table as per image/ design with overall size of table 2250 x 2100 x 750mm. GM table of size 2250x925x750mm Ht, in single unit,Top to be made out of double layer of 19mm thk. board + 3.5mm thk. Premium category Veneer on exposed surfaces. All other surfaces to be pasted with matching teak wood lipping, Drawers to be made out of 19mm thk.MDF board + 3.5mm thk. Premium category Veneer on exposed and horizontal surfaces. All other surfaces to be pasted with 1mm matching laminate/ teakwood lipping, Shutter to be made out of 19mm thk. board +3.5mm thk. Premium category Veneer on exposed surfaces. All other surfaces to be pasted with 1mm matching laminate/teak wood lipping,and in middle portion with leatherette for writing of size 1500x600 i/c titghtning with 6mm mdff board ,necessary moulding and lipping of teakwood etc. of approved make , finishing with melamine polish (matt finish) on all surfaces etc.,8mm toughened glass on top of table complete in all respect as per specification and direction of Engineer-in-charge (Premium category Veneer base price 300 Rs/ Sqft). Providing and placing in position 1200 lenght,450mm deep, 750mm height low height side cabinet of table made with 19mm commercial block board with 3.5mm thk. Premium category Veneer on exposed surface and rest area pasted with 1mm thick laminate as per drawing, drawers mounted on telescopic sliding channel, providing with 3mm oak wood lipping all round shutters fixed with auto closing hinges, the unit finished with melamine polishing all complete as per approved drawing and as per direction of Architect only.</p>	1.00	no.		
e	<p>Back Unit: (16'-6" x 2'-6") Providing & Fixing Back Unit having overall size as per design/ drawing with top made of 4 mm thick veneer& edges of the unit also with veneer and corian finish with toughned glass salves and door. Back Unit shall have understructure having verticals made of 18 mm thick plywood finished in veneer and the unit finished with melamine polishing all complete as per approved drawing and as per direction of Architect only.</p>	1.00	no.		
f	<p>RECEPTION TABLE WITH BACK UNIT Table top: Table top of 2'-6" wide to be formed out of of 19mm thick commercial ply clad with 6mm thick approved Corian, complete as per detail dwg. & Architect's instruction (size- 8'-6" x 2'-6" x 3'-6")</p>	1.00	no.		
	<p>Modesty panel: Modesty shall be formed out of 19mm thick commercial ply boxing finished in 6mm thk approved Veneer with PU polish Finish from outside and all inner surface should be finished with 0.8 mm tk laminate from inside. Provision for Cove lighting to be done as per dwg Complete as per detail dwg. & Architects instruction. Cost to include providing & fixing 6mm thk SS inlays as shown in the drawing.</p>				

TENDER BOQ FOR FURNISHING WORKS FOR CANARA BANK, FIRST FLOOR (UPPER HALL), KARNAL CIRCLE OFFICE, SECTOR-12, KARNAL

A	FURNISHING WORKS				
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount
	Back Unit : Providing and fixing of 9'-0" X 1'-6" X 2'-6" ht. made out of 19mm thk Commercial Ply finished with 4mm thk approved venner . Drawer unit to have 2 drawers and 1 shutter made out of 19mm thk commercial ply finished with approved 1mm thk laminate , mounted on approved drawer channel, central locking, approved handle. Complete as per the detailed dwg and instructions of the Architect.				
g	SIDE CREDENZAS				
	Providing and fixing SIDE CREDENZAS size 3'-0" to 4'-0" x 1'-3" x 2'-6" made of 19mm board of approved make finished with 1 mm thick laminate of approved Make and shade on top, back, sides and front having two drawers and cabinet below complete with all accessories like locks, handles, magnetic catcher etc. Teak wood beading on all exposed edges with PU polish. (Should not be attached with partitions)	3.00	no.		
h	WORK STATIONS TABLE Providing and fixing of COMPUTER work Stations as per layout plan and and 10mm beveled Toughened glass of approved make to be fitted on top obtain the total height of 2'-6" high working top (As per drawing) made up of 19mm board / ply of approved Make, finished with 1 mm thick laminate of approved Make, shade as approved as per the detailed drawing . The tables shall have as per approved shade and color. All exposed surfaces (such as counter front, sides, drawers and cupboard etc) must be finished with 1mm thick laminate of approved make. Table top shall be finished with 1mm thick laminate. The inner exposed surfaces to be painted over one coat of primer and enamel paint of approved shade. Each unit of table shall be provided with keyboard tray with telescopic channels. The work includes fixing of wire managers, locks, footrests, PU polishing the steam beach beading, lipping, exposed frame, etc. as per drawings, and The inner exposed surfaces shall be finished with 0.8mm thick laminate of approved shade. complete in all respects to the complete satisfaction of the Architect/Bank.				
i	Officers Table (5'-0"/5'-6" x 2'-6 x 2'-6")	0.00	nos		
ii	Officers Table/ staff tables (4'-0"/4'-6" x 2'-6" x 2'-6")	1.00	nos		
iii	Staff running counter	0.00	rft		
5	MISCELLANEOUS FURNITURE				
a	Providing & fixing STORAGE CABINETS independent units (movable) 12 feet long (maximum) 4'-6" ht and 1'-6" deep as per layout plan made up of 19mm board/ply of approved make and finished with 1mm thick laminate of approved make, shade and as per detailed drawing . one shelves made up of 19mm thick board, each drawer(with lock) & cabinet(with lock) 19mm thickness portion every place must be finished with proper liping/ margin teak wood finish. In side and back shall be finished with 0.8mm thick laminate of approved Make and color The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc as specified. complete in all respects.	0	rft		
b	Full height STORAGE CABINATES upto 8'-6" false ceiling height specification as per (a)	130	Sqft		
c	Half height STORAGE CABINATES upto 4'-0"/ 2'-6" height specification as per (a)	90	Sqft		
d	COLUMN / WALL PANNELING Providing and fixing of COLUMN PANNELING as per design, consisting of 10 mm thick MDF BOARD of approved Make fixed on wall with made of 2"x2" alluminium tublar section framework (16 gauge) 2'0" c/c both ways. The above shall be laminated with 1mm thick mica of approved Make, The work includes PU polishing of wood beading, complete in all respects as per detailed drawings to the complete satisfaction of the Architect.	270	sqft		
e	Providing & fixing in position wall panelling as design (Location : GM Cabin & DGM Cabin) consisting of 9 mm plywood of approved make finished with 4 mm thick Veneer of approved make and shade with aluminium hat furring channel 22-25 @ 500 mm. both direction. The item is to be completed in all respects as per design & approval of the architect.	460	sqft		
6	NOTICE BOARD				
	Providing and fixing soft board with glass White board necessary framework and 12mm bwp plywood on top 12MM jolly board to be fixed finished with fabric @Rs80 , with necessary mouldings duly polished along the periferi.The work to be completed as per approval and satisfaction of the Architect.	25.00	Sft		
7	CENTER TABLES (3'-0" X 2'-0" X 1'-6"HT) Providing and making center tables of above mentioned size as per drg. Table top shall consist of 12 mm. Thk.float glass with chamfered edge with approved quality etching. The base shall be made up of CP Teak wood frame as directed by the Architect. All exposed faces finished with natural PU polish (if wood frmes are used) or with 1.0mm Thk laminate for ply. All inner surfaces will be finished with natural french polish.	2.00	no.		

TENDER BOQ FOR FURNISHING WORKS FOR CANARA BANK, FIRST FLOOR (UPPER HALL), KARNAL CIRCLE OFFICE, SECTOR-12, KARNAL

A	FURNISHING WORKS							
S. No.	Description				Qty	Unit	Rate (Rs.)	Amount
8	ROLLER BLINDS Supplying & Fixing of Seclusion Blockout fabric made up of 100% Polyester with Acrylic coated of 0.32mm(PVC free) of thickness 0.50mm ±5% and weighing 270-295gsm with openness factor of 0% .Shrinkage % Warp5-6. GREENGUARD certified fabric.The Roller blind system consists of 38mm OD extruded out of Aluminium alloy 6063 T6 with silver anodized to provide an everlasting finish and luster, the rotary unit shall be 36mm in OD incorporating a clutch mechanism composed of low – flexing braided polyester cord with nylon core, Control Ball chain shall be composed of braided nylon cord (2mm dia) with high engineering grade plastic beads of 4.5mm diameter mounted co-axially on the cord with a pitch of 6.2mm (C-T-C) Bottom rail should be powder coated Aluminium flat bottom rail of 290 gm to finish it from the ends it should have rail end caps. The clutch will be at the tube. The return end cap bracket shall incorporate snap spring design to facilitate easy installation and removal for maintenance activities. The bracket shall be finished with a flush mounting cover on each side providing an aesthetic finish. It should handle up to 5 Kgs of material. The clutch should mount flush to the face of the bracket which minimize the light gap between the shade and the window frame. Material & Color shade will be as per sample approved by Architect. (Make- Graber/walltact/hunter Douglas)				230.00	Sft		
9	Providing and fixing at Wooden work for ceiling made by 6 mm thk marine grade ply (IS-710) to be finished in 4.0 mm thk. polished veneer of approved shade, fixed to suspended Gypsteel chanel of appoprete size to hold the ceiling ply. The item is to be completed in all respects as per design & approval of the architect. The rate to be included for making necessary cut outs for light fittings, ac unit or other equipments.				100.00	Sft		
10	Providing and fixing of wall paper of approve shade and pattarten of Marshall /Excell/ WK make to wall/partition as per instruction with adhesive including all labour and material. This is to be pasted over POP / Putty surface with primer finish (cost of primer to be included in the rate). The item is to be completed in all respects as per design & approval of the architect. (basic cost of wall paper : Rs. 50.00/ s.ft.) (Location : DGM rm & Conference rm)				100.00	Sft		
11	MDF JALI: Providing, fabricating & fixing of Jali work Partition made of 25 mm MDF finished in Mettalic Duco paint to be fixed to the floor and ceiling, complete as per the detailed dwg or the instructions. Cost also to include Design and Lazer Cutting on theMDF , and MS supports above False ceiling up to true ceiling . Mode of measurement : Length & height upto Height of the Jali Work Partition shall be measured for payment. Providing and fixing 50x50mm thick teak wood in frame @ 600mm c/c horizontally and vertically for paneling frame work with coat of anti-termite treatment including hardware and adhesive as required complete as directed. Complete as per the detailed design dwg and instructions				50.00	Sft		
12	Frosted Film -Providing & pasting frosted film (3M, Garware make) on glass work partition and glass door as required as directed by the consultant/Architect.				335.00	Sft		
13	i	Logo -Providing & pasting frosted film (3M, Garware make) coloured logo on entrance door as directed by the Consultant.		0.00	Sft			
	ii	S.S logo of Canara Bank in SS plate of 18 inch dia and Poster Frame - one set poster frame consisting 2 sheets of imporettd acrylic of 5 mm thickness front sheet with half inch moulding and edge polished;back sheet with polished edge and Alumunuum stud for fixing the frame on wall,One Pin Board for fixing Notices and other communication made of 24"x18" soft board,with hardwood and aluminium frame,covered with satin of appropriate colour.		0	no.			
14	Painting of walls with textured paint, double spary coat or eq. of approved shade & colour complete as per manufacturers specs .Finishing walls with textured exterior paint of required shadeNew work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/ 10 sqm- textured paint Finalize by architect only.				0	Sft		
15	Providing and fixing designer Wall Paneling with 3D engraving in 18mm thick acrylic solid surface sheet of approved make or as approved by Architect basic white/ coloured. Design & fixing arrangement as per direction of Engineer. The material should be CNC 3D cut to achieve the desired design. The CNC cut Acrylic solid surface sheet to be fixed in a box frame or on a frame or on a flat surface as per the drawing and design and as per the instructions of the Architect. The material used shall be very translucent and the light shall pass through the acrylic solid surface enhancing the design and the lights passing should be very visible. The cost shall include the framing and Boxing of wood / plywood and the frame should be of stainless steel or wood as per requirement of stability and weight carrying capacity and its requirement for support. The 3D shall be done as per the requirement of light translucency and reflection of lights required as per the design and instructions of Architect. The backlit ceiling shall have the light passing and shall have translucency. Acrylic solid surface shall have Antibacterial certificate and TUV (Austria) FR grade certified. All design and drawings will be finalized by architect complete all the work as per satisfaction only.				0	Sft		

TENDER BOQ FOR FURNISHING WORKS FOR CANARA BANK, FIRST FLOOR (UPPER HALL), KARNAL CIRCLE OFFICE, SECTOR-12, KARNAL

A	FURNISHING WORKS							
S. No.	Description				Qty	Unit	Rate (Rs.)	Amount
16	"Providing 15mm thick Mikasa Make Engineered Wooden Flooring with plank width of 185mm / 135mm and length of 1800mm / 2100mm and top layer up to 3mm Oak natural Veneer. Surface of Top layer is pre finished with several layer of UV hardened Acrylic lacquer. Strictly Free from Formaldehyde and solvents. Flooring plank shall be interlocked using Plank Loc locking system in a glue less floating manner. Engineered wood planks shall be a composition of 3 layer of Pine wood with direction of each layer oriented at right angle to the adjacent layer of natural strain in Lacquer and Non Beveled /Beveled in length and width as specified by the manufacturer-in-charge. Product should be MAKE IN INDIA, to maintain a consistent and long term supply of all required quantities. Manufacturing Plant / Product should have FSC certificate and adhere to stringent emission standards. Design and shades are finalized by Architect.				0	Sft		
	Solid Wood Skirting of Matching shade to Engineered wood floor color							
	Installation of Engineered wood flooring in Linear Pattern							
17	Providing and fixing 4.5" wide seamless panel on the existing wooden surface i/c cutting the same and fixing with the help of suitable adhesive / nailing etc in approved design and pattern etc complete as reqd.				70.00	Sft		
18	Providing and fixing of wooden rafter of approx size 7"x2" made out of wooden member and duly clad with 1 mm thick laminate i/c fixing the same on the existing ceiling / floor etc complete as reqd.				32.00	Rft		
19	Providing and fixing of indoor artificial plant to create decorative vertical garden in the existing surface by fixing of base frame and artificial plants in the approved pattern and design etc complete as reqd				50.00	Sft		
20	Supplying and fixing of 6' x 6'x 3' deep conical shaped inverted dome like structure , fabricated out of double layers of 9mm ply / 12 mm MDF duly fixed on the ceiling with the help of frame work made out of aluminium frame and G.I.section and duly laminated from inside in step formation with 12 mm wide grooves & finishing the same by filling of grooves in matching colours of paint / polish etc complete as reqd.				0.00	Sft		
21	Providing and fixing 18 mm thick, 150 mm wide pelmet of flat pressed 3 layer or graded wood particle board medium density grade I, IS : 3087 marked, including top cover of 6 mm commercial ply wood conforming to IS: 303 BWR grade, nickel plated M.S. pipe 20 mm dia (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. flat 10 cm long fixed to pelmet with hollock wood cleats of size 100 mm x 40 mm x 40 mm on both inner side of pelmet and rawl plugs 75 mm long etc. all complete. PELMETS with Laminate Finish				40.00	Rft		
22	PANELLING ON WALL IN LACQUERED GLASS-Providing and Fixing of wooden Panelling of wall on hall and column made of 2 MM thick Aluminium tube frame The sections are placed @ 600 x 600 MM C/C both ways and additionally at openings or ends as required. Sections are joined by Aluminium angle cleats and the frame is fixed to wall, floor & ceiling with suitable aluminium angles and fastened with steel screws. Frame size 25 x 50 MM with 9 MM thick BWR Ply with 6mm thk colour lacquered glass in approved colour, design, shape and size, including Anti Termite Treatment. Complete in all respect and satisfaction of Architect/Engg.				50.00	Sft		
23	PANELLING ON WALL/PARTITION IN ACOUSTICAL PANELS-Providing & fixing Acoustical Panelling channelled Wood works spaced at perforated panels of width 128mm, thickness of 16mm and length 2440mm or as required on site & approved by EIC, made of a high density particle board substrate with a laminated facing as per the approved shade/species & finish and melamine balancing layer on the reverse side. The boards shall have a special perforation pattern where the visible surface has a ("Helmholtz" fluted perforation of 2mm width and 14mm of visible panel/4mm width and 28mm visible panel) each. The panels shall provide a minimum sag resistance of RH90 and a fire rating class of 1 as per Part 7 of BS 476. The edges of the panels shall be "tongue-and-grooved" to receive special clips for installation. The back of the perforated panel shall have sound absorbing non-woven acoustical fleece. The panels shall be mounted on special aluminium spines using clips provided by Armstrong or equivalent and approved.				50.00	Sft		
24	Providing & Fixing Panelling as same as above, having top layer as duco paint of approved make, quality & shade as per the architects direction on wooden or metal surfaces. The rate shall include scrapping, levelling & preparing the surface, primer coat, chock putty, all surface development as per satisfaction of Architect.				250.00	Sft		
25	WOODEN FLOORING - Providing and fixing of 8-9mm thick Laminated wooden flooring with a surface abrasion resistance of class AC4, with 0.2mm thick wear layer on top of a High Density Fibre substrate core of plank having uniline locking arrangement with an made of Armstrong natural colour foam, with accessories like Skirting, end profile, door profile, transition profile, reducer etc. Complete. Make-ARMSTRONG/ AMBIENCE PLUS/ PERGO/vista. Length and breadth of superficial areas of the finished work shall be measured for payment. Make - Carbolink, / Apex / Junkers / Parquet.				800.00	Sft		

TENDER BOQ FOR FURNISHING WORKS FOR CANARA BANK, FIRST FLOOR (UPPER HALL), KARNAL CIRCLE OFFICE, SECTOR-12, KARNAL

A	FURNISHING WORKS				
S. No.	Description	Qty	Unit	Rate (Rs.)	Amount
26	Providing and fixing of nylon carpet tiles of tufted textured loop in required design, colour, shades and made with 100% nylon BCF solution dyed, total pile height 6.5 mm +/- 0.3 mm, pile weight 700 gms/m ² +/- 5%, gauge 1/10"/1/8" ,backing with PVC Glass lined and size of tile 60.9x60.9 cm. fixing of tile with synthesis adhesive as per manufacturer guidelines etc. complete all as per the direction of Engineer-in-charge.	250.00	Sft		
27	SUN FILMS - Supplying and fixing Suncontrol window film for glazing in different locations and at different heights, to be fixed as per any of the approved type including removing old faded sun film by scrapping and thoroughly cleaning the glass surface with the help of suitable cleaning solution etc. and providing and installing of Sun Control film from inside, Complete job. Rates quoted shall be all inclusive for complete work. Nothing extra will be paid for scaffolding, breakage during execution of the work or for any other item necessary to complete the work satisfactorily. Measurement will be for the finished surface excluding Aluminium frames. Make - 3M / Avery.	450.00	Sft		
28	MISC ITEMS				
a	P&F High Quality PVC/Acrylic/Texture Laminate as per design given by Architect.	50.00	Sft		
b	P&F G-Profile as per Architect	50.00	Rft		
c	P&F SS Patti Gold 1.5"	90.00	Rft		
d	P&F T Patti Gold 3/4"	90.00	Rft		
e	P&F SS Patti Gold 3/4"	90.00	Rft		
f	P&F SS Patti Gold 3/4"	90.00	Rft		
	GST extra as applicable	Total			