# CANARA BANK INVITATION TO TENDER

# **ONLY FOR EMPANEL CONTRACTORS FOR**

# **ELECTRICAL WORKS (CATEGORY A , B,C ONLY)**

# <u>OF</u>

# **CIRCLE OFFICE GUWAHATI**

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

### **INSTRUCTION TO BIDERS AND**

### GENERAL CONDITIONS OF CONTRACT

### FOR

### **ELECTRICAL WORKS**

AT

### CANARA BANK – TELIAMURA BRANCH

TENDER NO.: 29/24-25/SP

NAME OF THE CONTRACTOR:

## **NOTICE INVITING THE TENDER**

Τo,

M/s .....

Sealed tenders on item rate basis are invited from panel Contractors for **Electrical Works at TELIAMURA BRANCH.** Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Guwahati during working hours from **23-10-2024** till **30-10-2024**.

Earnest Money Deposit	:	NIL
Period of completion	:	20 days
Last date, time and place for Submission of tender	•	On or before 3 pm, 30-10-2024 to The Asst. General Manager, Premises & Estate section Canara Bank, Circle Office Guwahati
Time and date of opening of tender	:	3.30 Pm on 30-10-2024

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

Asst. General Manager
Premises & Estate Section
Canara Bank, Circle Office
Guwahati

•••••

Date: 23-10-2024

### **GENERAL RULES & INSTRUCTIONS TO TENDERERS**

# Name of the work: Electrical Works to be carried out at TELIAMURA BRANCH Branch,

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

#### GST WILL BE PAID EXTRA.

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 20 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

#### TENDERS:

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

#### AGREEMENT

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

#### EARNEST MONEY AND SECURITY DEPOSIT:

There is NO Earnest Money Required to deposite/ submit along with the bids. Retention Money shall be deducted from the final bill at 3% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

#### CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together weather the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipments and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, Civil & furnishing wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

#### LIQUIDATED DAMAGES:

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.

#### TIME PERIOD FOR COMPLETION: 20 days from the date of award of work.

#### FINAL PAYMENTS

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The

acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

#### **ESCALATION:**

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroietc, unless specifically provided in these documents.

#### CONTRACTORS EMPLOYEES:

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

#### PAYMENTS:

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement, after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work. The contractor shall have to make his own arrangements for watch and ward of the work/building, till the

work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or

imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part there of if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

#### **ARBITRATION:**

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or branch of the contract[other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sour arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as a foresaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as a foresaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

The arbitrator shall be deemed to have entered on the reference the data he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

Date:

Signature of the Contractor With seal and address

#### LIST OF PREFFERED MAKE / BRAND ALL WORKS

Sr.No.	LIST OF NOMINATED MATERIALS & SUPPLIERS	SUGGESTED MAKE LIST
1	ELECTRICAL	
	Light Fittings	Philips / Wipro / Havells / Cromption G.
	MCCB, MCB , RCCB, DB, ICTPN TP, HRC Fuse, change over switch, switch fuse Unit	L&T, ABB, Legrand, Havells, Schneider
	FRLS insulated Elec. Wire/ cable armoured, unarmourd, Sheathed,unSheathed, flexible LT cable, Multi core, single core cable, flat cable	Finolex/Ploycab/Havells/RR kabel/KEI
	PVC conduit(HEAVY DUTY ONLY)	CAP/Finolex/Polycab
	PVC insulated copper conductor Wires	Finolex/ Polycab/RR Cable /Havells
	Distribution Box	Legrand/ Schneider/ Havells /Siemens
	MCB & MCCB	Legrand/ Schneider/ Havells /Siemens/L&T
	Light Fixture & Lamps	Philips/ Wipro / Havells / Cromption G.
	HT cable	Polycab/Havells
	Modular Switches	ABB/ Legrand/ MK/ANCHOR/ Havells /ROMA
	DLP Trunking	Legrand/Schneider or equivalent
	Power cable	CCI/ Skytone/ Universal/ LAPP/ Torrent
	End Termination	Raychem/ Mahindra/ELMEX
	PANEL	Crompton/L&T/C&S
	Fan	Crompton/Havells/Bajaj/Usha
	Raceway & Alu. Trunking	Tata/Jindal/Zenith
	Casing Caping	Finolex/Cap or equivalent
	Weather proof socket outlet with MCB	ABB/MDS/LEXIC/Neptune/Elcon- Clipsil, Siemens, Schneider (Merlin Gerin)
	Miniature Circuit Breaker	ABB/MDS/LEXIC/ Clipsil/Siemens/ Havells
	Earth Leakage Circuit Breaker	MDS/LEXIS/Siemens/ Havells
	MCB Distribution Boards in sheet steel housing (double door)	ABB/MDS/LEXIC/Siemens/ Havells
	Telephone Cable	Skytone/ Delton/ NICCO/Polycab/Finolex
	Switch, TV & Telephone socket & boxes (Modular Type)	CPL/Legrand/ABB/Anchor
3	Miscellaneous Items	
	Lightning Protection Unit	Erico/ Pheonix/ INDELEC
	Relays	L&T/ABB/Siemens/BCH
	Contractors	L&T/ GE Power/BCH/ Siemens/ABB
	Changeover switch	C&S/Havells/ L&T/HPL
	KWH, PF, Frequency meter	BHEL/ AE/Havells/ L&T/ALSTOM
	Push Buttons	L&T/ Siemens
	Timers	L&T/ Legrand/ Schneider/Siemens/GE
	Timer Switch	L&T/ Legrand/ Schneider/Siemens/GE
4	Networking	
	Switches	Brocade/Cisco/DigiLink/3Com/Nortel/Foundry/D-Link
	Patch Panel,Patch cord and I/o	Digi-Link / Tyco(AMP) /Schneider/D-Link
	Cable	Digilink/Clipser/National/Polycab/Lapp/Finolex
	Racks	ComRack / HCL / ValRack / APW President

**NOTE:** The contractor shall use only above mentioned material to be approved by the Consultant. All other materials shall confirm to the specifications laid down. The tenderers shall take this into account while tendering rates / prices.

		ELECTRICAL BOQ FOR CANARA BANK, TELIAMURA				
SI.No		Description of Item	UNIT	QTY	RATE	AMOUNT
1		Distribution System.				
		Supply, Installation, Testing and Commissioning of				
		Factory Manufactured Single/Three Phase & Neutral				
		Double Door Distribution board made out of 16 SWG				
		sheet steel enclosure, IP 43, with cutouts for operating				
		MCB/MCCB/RCCB etc. knobs & consisting of Phase,				
		Neutral & E arth Busbars with tapped holes, phase				
		barriers, & covers with removable plates on Top & bottom for Incoming & Outgoing Cables. D.B.'s shall be				
		flush mounting type for both single & three phase.				
		hush mounting type for both single & three phase.				
		63 A 4P MCCB, 25 KA in Sheet Steel Enclosure (Make L&T	No.	1		
	а	or equivalent)				
		63 A 4P on load changeover switch in Sheet Steel	No.	1		
	b	Enclosure (Make L&T or equivalent)				
	с	MAIN-DB	No	1		
		SITC of 4 way TPN Double Door Vertical MCB Distribution				
		Board with following MCCB/MCB/RCCB & cable end				
		boxes at Input & Output. (Make L&T or equivalent)				
		63A 4P MCCB 16 KA – 1 No.				
		16A / 20A / 25A / 32A SP MCB – 8 Nos.				
		40A SP MCB – 1 No.				
		40A 3P MCB – 1 No.				
	d	LIGHT D.B. :	No	1		
		SITC of 18 way SPN Double Door MCB Distribution Board				
		with following MCB/RCCB & cable end boxes at Input & Output. (Make L&T or equivalent)				
		Incomer: 40 A DP MCB - 1 No.				
		40 Amp DP R.C.C.B., 30 Milliamp sensitivity- 1 No.				
		Outgoing:				
		6 Amp S.P. Amp M.C.B 12 Nos				
	•	<b>DB-AC/POWER</b> :	No	1		
	е	SITC of 4 way TPN (8+12 WAY) Double Door MCB	NO			
		Distribution Board with following MCB/RCCB & cable end				
		boxes at Input & Output. (Make L&T or equivalent)				
		Incomer:				
		40 A 4P MCB - 1 No.				
		40 Amp 4P R.C.C.B., 30 Milliamp sensitivity- 1 No.				
		Outgoing:				
		16/20/25 Amp S.P. Amp M.C.B 12 Nos				
	f	U.P.S. (INPUT) D.B. :	No	1		

		SITC of 12 way SPN Double Door MCB Distribution Board with following MCB/RCCB & cable end boxes at Input & Output. (Make L&T or equivalent)			
		Incomer:			
		32 A DP MCB - 1 No.			
		40 Amp DP R.C.C.B., 30 Milliamp sensitivity- 1 No.			
		Outgoing:			
		110/16/20/25 Amp S.P. Amp M.C.B 8 Nos			
	g	U.P.S. D.B. :	No	1	
		SITC of 12 way SPN Double Door MCB Distribution Board with following MCB/RCCB & cable end boxes at Input & Output. (Make L&T or equivalent)			
		Incomer:			
		25 A DP MCB - 1 No.			
		25 Amp DP R.C.C.B., 100 Milliamp sensitivity- 1 No.			
		Outgoing:			
		10 Amp S.P. Amp M.C.B 8 Nos			
	h	DB-Inverter	No	1	
		SITC of 8 way SPN Double Door MCB Distribution Board with following MCB/RCCB & cable end boxes at Input & Output. (Make L&T or equivalent)			
		25A DP RCCB 30 mA sensitivity – 1 No.			
		10A SP MCB – 4 Nos.			
		Blank Plate - 2 Nos.			
	i	S.I.T.C of Modular 16 Amp. S.P. MCB with 16A socket outlet in Metallic box for Inverter input and output	No.	2	
	j	S.I.T.C of 32 Amp. D.P. MCB in Metallic box for input and output of UPS	No.	2	
2		Light Point/Raw Power Point/UPS Point/Fan Point wirings			

		Wiring with I.S.I. marked 1.1 KV grade 2 x 1.5 Sq.mm + 1 x 1.5 sqmm (Green for earth) multi-strand F.R.L.S. Copper P.V.C. wires in 19/25 mm Medium grade I.S.I. marked steel conduits to be laid on wall/above false ceiling/Through Modular Furniture slots etc complete with all conduit accessories like bends, tees, Junction boxes with necessary hardware etc. including re- surfacing of the floor/wall etc. wherever necessary with Resurfacing material for Lights, fans, exhaust fans, 6Amps socket outlets etc. Point wiring to include cost of wiring in PVC conduits, Installation, Testing, Commissioning and fixing of switch, sockets, boxes, plates & accessories and circuit wiring with 2x2.5 sqmm + 1x1.5 sqmm (green for earth) multi-strand F.R.L.S. Copper P.V.C. wires in 19/25 mm Medium grade I.S.I. marked steel conduits to be laid on wall/above false ceiling including all accessories complete.				
	а	Single Light points controlled by 6 Amp switch.	No	14		
	b	Two Light points controlled by one 6 Amp Switch.	No	11		
	с	Call Bell Buzzer (Ding Dong) controlled by 6 Amp Bell Push switch.	No	1		
	d	6 Amps 3/5 Pin combination type socket with switch mounted on switch-box.	No	7		
	е	Ceiling Fan, Points with 6 A Switch and regulator	No	2		
	f	Wall Fan & Exhaust Fan (in existing holes) Points with 6 A Switch and 6A socket	No	12		
3		Raw Power + UPS Power, Power Points & AC Points				
	а	Supply, Installation, Testing and Commissioning of Recessed 1 Nos. 6 Amp 5 Pin Sockets controlled by one 6 Amp switch complete with Flush surface plate for Raw Power On Work-Stns including wiring with 2x2.5 sqmm + 1x1.5 sqmm Cu (green for earth) multistrand conductors with all accessories as necessary complete.	No	5		
	b	Supply, Installation, Testing and Commissioning of Recessed 3 Nos. 6 Amp 5 Pin Sockets controlled by one 16 Amp switch complete with Flush surface plate for UPS Power On Work-Stns including wiring with 2x2.5 sqmm + 1x1.5 sqmm Cu (green for earth) multistrand conductors with all accessories as necessary complete.	No	6		
	С	Supply, Installation, Testing and Commissioning of 2 Nos of 6 Amp Sockets controlled by one 16 Amp switch and 1 No of 6/16 Amp Sockets controlled by one 16 Amp switch housed in a Modular PVC switch Box including wiring with 2x2.5 sqmm + 1x1.5 sqmm Cu (green for earth) multistrand conductors with all accessories as necessary complete.	No			

	d	Supply, Installation, Testing and Commissioning of power point with 16 Amp Switch and sockets housed in a Modular MS switch Box with Flush surface plate for Power Points including wiring with 2x4 sqmm + 1x2.5 sqmm Cu (green for earth) multistrand conductors in sreel conduits with all accessories as necessary complete.	No	4	
	e	Supply, Installation, Testing and Commissioning of point for 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.	No	1	
	f	Supply, Installation, Testing and Commissioning of point for 1.5/2.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required complete including wiring with 2x6 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.	No	2	
4		SUB-MAIN WIRING			
		Supply, Installation, Testing and Commissioning of with 1100 V grade PVC insulated multi stand FRLS copper conductor cable confirming IS 694 through 25 mm dia rigid steel conduit on wall with MS bar saddle , interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.			
	а	With 2 X 2.5 Sq.mm. + 1x2.5 sqmm (green for earth).	Mtr	30	
	b	With 2 X 4 Sq.mm. + 1 x 4 sqmm (green for earth).	Mtr	5	
	С	With 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth).	Mtr	25	
	d	With 4 X 10 Sq.mm. + 2 x 10 sqmm (green for earth).	Mtr	5	
	е	With 4 Core 25 sqmm Armoured Aluminum U.G. cable	Mtr	5	
	f	With 3½ Core 25 sqmm Armoured Aluminum U.G. cable	Mtr	30	
5		BRANCH POWER INDICATOR LAMPS			 

	а	Supply installation Testing and Commissioning of surface type Metal box made of sheet steel and thickness not less than 2mm and structural steel having light section completely dust tight and vermin proof and shall be painted with anti corrosive and anti condensation type two coats of primer and two coats of paint with front mounted pilot lamps for Main supply, Light DB, UPS DB & AC/Power DB.	Each	1	
	b	Supply, Installation, Testing and Commissioning of 2x1.5 sqmm 1100 V grade PVC insulated multi stand FRLS copper conductor cable confirming IS 694 through 25 mm dia PVC conduit on wall with saddle, interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.	Mtr	20	
6		LIGHTING FIXTURES :		10	
	а	Supply, installation and testing of 36W recessed mounted 2'X2' LED Panel with backlit technology & low height feature suitable for the Armstrong/ Grid ceiling. of make Legero Model Terra Cat No. LTP 1036 or equivalent. Rate to include cost of lamps. [CLT]	No	10	
	b	Supply, Installation, Testing and commissioning of recessed tpe 1x15 W LED Compact & sleek round LED backlit downlight made up of polycarbonate housing, high efficacy LEDs, high grade material diffuser to give uniform & glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. LRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]	No	10	
	c	Supply, installation and testing of 12W LED surface- mounted round edge-lit downlight with high efficacy LEDs with highly efficient and low glare diffuser for optimum light distribution of make Legero Model Coral Surface (R) Cat No. LRS 3112 or equivalent. Rate to include cost of lamps. [CL]	No	4	
	d	Supply, Installation, Testing and commissioning of 1x24 W Extruded Aluminium 4ft batten suitable for Surface, Wall & Conduit mounting (with accessories) of make Legero Model Lita Cat No. RBJ 100 0024 or equivalent including lamps, drivers etc. as required complete. [TL]	No	10	

	e	Supply, Installation, Testing and Commissioning of 1x10 W Decorative polycarbonate LED batten in rectangular shape with high efficient PC diffuser & nicely designed end caps of make Legero Model Kiri Cat No. LRS 9110 or equivalent including lamps, drivers etc. as required complete. [ML] Supply, Installation, Testing and Commissioning of Angle batten holder of make Anchor Penta Code 38538 or	No	1	
	f	equivalent make as required with 1x12 W LED Lamp. [BK]			
7		Ceiling Fan / Wall (Cabin Fan) / Exhaust Fan:			
	а	Supply, Installation, Testing and Commissioning of 1200mm sweep Ceiling Fans with connection of make Orient Model SUMMERKING (XI Aluminium Blades) or equivalent with all accessories.	No	2	
	b	Supply, Installation, Testing and Commissioning of 300mm sweep Exhaust Fans with connection from existing 6A socket outlet (rate for socket and connection to the socket to be taken separately)	No	4	
	с	Supply, Installation, Testing and Commissioning of 450 mm sweep Wall mounted Fans with connection from existing 6A socket outlet (rate for socket and connection to the socket to be taken separately)	No	8	
8		Earthing System:			
	а	Supply, Installation, Testing and Commissioning of Copper Plate Type Earth Pit as per I.S. 3043. Concrete Chamber with Mettalic cover, Funnel for adding water and Earth Strip Connector etc must be provided complete.	No	1	
	b	Repairing of existing Pipe/Plate Earthing including digging soil, filling with Salt and Charcoal, cleaning all debries and refillling with soil making concrete chamber, metallic cover, funnel etc. as necessary with suitable provision for connection with earth strip etc. complete.	No.	1	
	c	Second set of 2X 6 Sq.mm. PVC earth wires in Conduit to be taken from Earth Pit directly to the UPS room and connected to UPS Output D.B. from Earth Pit directly to the UPS of ATM and connected to UPS Output D.B.	Mtr.	50	
9		MISCELLENOUS MATERIALS.			

	а	Supply, Installation, Testing and Commissioning of Light Point with Timer for Branch Sign Board whose location may be decided in consultation with Branch Head.	No	1		
		TOTAL (A)				
			<u>   </u>			
		ELECTRICAL BOQ FOF CANARA BANK, TELIAMUR				
SI.No	<u> </u>	Description of Item		QTY	RATE	AMOUNT
1		Distribution System.		<u> </u>		Amoon
		Supply, Installation, Testing and Commissioning of Factory Manufactured Single/Three Phase & Neutral Double Door Distribution board made out of 16 SWG sheet steel enclosure, IP 43, with cutouts for operating MCB/MCCB/RCCB etc. knobs & consisting of Phase, Neutral & E arth Busbars with tapped holes, phase barriers, & covers with removable plates on Top & bottom for Incoming & Outgoing Cables. D.B.'s shall be flush mounting type for both single & three phase.				
	а	ATM(INPUT) DB	No	1		
		SITC of 8 way SPN Double Door MCB Distribution Board with following MCB/RCCB & cable end boxes at Input & Output. (Make L&T or equivalent)				
		25A DP MCB – 1 No.				
		20A SP MCB – 2 Nos.				
		25A SP MCB – 1 Nos.				
		Blank Plate - 3 Nos.				
	b	ATM D.B. :	No	1		
		SITC of 12 way SPN Double Door MCB Distribution Board with following MCB/RCCB & cable end boxes at Input & Output. (Make L&T or equivalent)				
		Incomer:				
		25 A DP MCB - 1 No.				
		25 Amp DP R.C.C.B., 100 Milliamp sensitivity- 1 No.				
		Outgoing:				
		20 Amp S.P. Amp M.C.B 2 Nos				
		16 Amp S.P. Amp M.C.B 1 Nos				
		10 Amp S.P. Amp M.C.B 5 Nos				
2		Light Point/Raw Power Point/UPS Point/Fan Point wirings				

		Wiring with I.S.I. marked 1.1 KV grade 2 x 1.5 Sq.mm + 1 x 1.5 sqmm (Green for earth) multi-strand F.R.L.S. Copper P.V.C. wires in 19/25 mm Medium grade I.S.I. marked steel conduits to be laid on wall/above false ceiling/Through Modular Furniture slots etc complete with all conduit accessories like bends, tees, Junction boxes with necessary hardware etc. including re- surfacing of the floor/wall etc. wherever necessary with Resurfacing material for Lights, fans, exhaust fans, 6Amps socket outlets etc. Point wiring to include cost of wiring in PVC conduits, Installation, Testing, Commissioning and fixing of switch, sockets, boxes, plates & accessories and circuit wiring with 2x2.5 sqmm + 1x1.5 sqmm (green for earth) multi-strand F.R.L.S. Copper P.V.C. wires in 19/25 mm Medium grade I.S.I. marked steel conduits to be laid on wall/above false ceiling including all accessories complete.			
	а	Two Light points controlled by one 6 Amp Switch.	No	2	
	b	6 Amps 3/5 Pin combination type socket with switch mounted on switch-box.	No	1	
_					
3		Raw Power + UPS Power, Power Points & AC Points			
	а	Supply, Installation, Testing and Commissioning of Recessed 3 Nos. 6 Amp 5 Pin Sockets controlled by one 16 Amp switch complete with Flush surface plate for UPS Power On Work-Stns including wiring with 2x2.5 sqmm + 1x1.5 sqmm Cu (green for earth) multistrand conductors with all accessories as necessary complete.	No	1	
	b	Supply, Installation, Testing and Commissioning of 2 Nos of 6 Amp Sockets controlled by one 16 Amp switch and 1 No of 6/16 Amp Sockets controlled by one 16 Amp switch housed in a Modular PVC switch Box including wiring with 2x2.5 sqmm + 1x1.5 sqmm Cu (green for earth) multistrand conductors with all accessories as necessary complete.	No	1	
	с	Supply installation testing and commissioning of Universal AC controller for 2 ACs with timer including wiring multistrand conductors with all accessories as necessary complete.	No	1	

d	Supply, Installation, Testing and Commissioning of point for 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.	No	2			
	SUB-MAIN WIRING					
	Supply, Installation, Testing and Commissioning of with 1100 V grade PVC insulated multi stand FRLS copper conductor cable confirming IS 694 through 25 mm dia rigid steel conduit on wall with MS bar saddle , interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.					
а	With 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth).	Mtr	5			
b	With 3 Core 6 sqmm Armoured Aluminum U.G. cable	Mtr	50			
	LIGHTING FIXTURES :					
а	Supply, installation and testing of 36W recessed mounted 2'X2' LED Panel with backlit technology & low height feature suitable for the Armstrong/ Grid ceiling. of make Legero Model Terra Cat No. LTP 1036 or equivalent. Rate to include cost of lamps. [CLT]	No	2			
b	Supply, Installation, Testing and commissioning of recessed tpe 1x15 W LED Compact & sleek round LED backlit downlight made up of polycarbonate housing, high efficacy LEDs, high grade material diffuser to give uniform & glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. LRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]	No	2			
	Earthing System:					
а	Supply, Installation, Testing and Commissioning of Copper Plate Type Earth Pit as per I.S. 3043. Concrete Chamber with Mettalic cover, Funnel for adding water and Earth Strip Connector etc must be provided complete.	No	1			
b	Second set of 2X 6 Sq.mm. PVC earth wires in Conduit to be taken from Earth Pit directly to the UPS room and connected to UPS Output D.B. from Earth Pit directly to the UPS of ATM and connected to UPS Output D.B.	Mtr.	15			
	a	for 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.SUB-MAIN WIRINGSupply, Installation, Testing and Commissioning of with 1100 V grade PVC insulated multi stand FRLS copper conductor cable confirming IS 694 through 25 mm dia rigid steel conduit on wall with MS bar saddle, interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.aWith 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth). bbWith 3 Core 6 sqmm Armoured Aluminum U.G. cableaLIGHTING FIXTURES : Supply, installation and testing of 36W recessed mounted 2'X2' LED Panel with backlit technology & low height feature suitable for the Armstrong/ Grid ceiling. of make Legero Model Terra Cat No. LTP 1036 or equivalent. Rate to include cost of lamps. [CLT]bSupply, Installation, Testing and commissioning of recessed tpe 1x15 W LED Compact & sleek round LED backlit downlight made up of polycarbonate housing, high efficacy LEDs, high grade material diffuser to give uniform & glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. LRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]aSupply, Installation, Testing and Commissioning of Copper Plate Type Earth Pit as per 1.S. 3043. Concrete Chamber with Mettalic cover, Funnel for adding water and Earth Strip Connector etc must be provided complete.bBuply, Installation, Testing and Commissioning of copper Plate Ty	for 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.SUB-MAIN WIRINGImage: Supply, Installation, Testing and Commissioning of with 1100 V grade PVC insulated multi stand FRLS copper conductor cable confirming IS 694 through 25 mm dia rigid steel conduit on wall with MS bar saddle , interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.MtrbWith 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth).MtrbWith 3 Core 6 sqmm Armoured Aluminum U.G. cableMtrcause of the suitable for the Armstrong/ Grid ceiling. of make Legero Model Terra Cat No. LTP 1036 or equivalent. Rate to include cost of lamps. [CLT]NobSupply, Installation, Testing and commissioning of recessed tpe 1x15 W LED Compact & sleek round LED backlit downlight made up of polycarbonate housing, high efficacy LEDs, high grade material diffuser to give uniform & glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. LRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]NoaSupply, Installation, Testing and Commissioning of copper Plate Type Earth Pit as per 1.S. 3043. Concrete Chamber with Mettalic cover, Funnel for adding water and Earth Strip Connector etc must be provided complete.NobSupply, Installation, Testing and Commissioning of copper Plate Type Earth Pit as per 1.S. 3043. Concrete Chamber with Mettalic cover, Funnel	for 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.SUB-MAIN WIRINGImage: Complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand commissioning of with 1100 V grade PVC insulated multi stand FRLS copper conductor cable confirming IS 694 through 25 mm dia rigid steel conduit on wall with MS bar saddle , interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.Mtr50aWith 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth).Mtr50bWith 3 Core 6 sqmm Armoured Aluminum U.G. cableMtr50aLIGHTING FIXTURES : Supply, installation and testing of 36W recessed mounted 2'X2' LED Panel with backlit technology & low height feature suitable for the Armstrong/ Grid ceiling. of make Legero Model Terra Cat No. TP 1036 or equivalent. Rate to include cost of famps. [CLT]No2aSupply, installation, Testing and commissioning of recessed top 115 W LED Compact & sleek round LED backlit downlight made up of polycarbonate housing, high efficacy LEDs, high grade material diffuser to give uniform & glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. LRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]No1a<	for 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sqmm + 1x4 sqmm Cu (green for earth) multistrand conductors in steel conduits with all accessories as necessary complete.SUB-MAIN WIRINGImage: Complete in all complete in all complete in all region of with 1100 V grade PVC insulated multi stand FRLS copper conductor cable confirming IS 694 through 25 mm dia rigid steel conduit on wall with MS bar saddle , interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.Image: Complete in all respect wherever required.aWith 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth). bMtrSoJUGHTING FIXTURES: Supply, installation and testing of 36W recessed mounted to include cost of lamps. [CLT]Image: Complete in all respect whereaver required.aUIGHTING FIXTURES: Supply, installation, Testing and commissioning of recessed to 1x15 W LED Compact & sleek round LED backlit downlight made up of polycarbonate housing, high efficacy LEDs, high grade material diffuser to give uniform & glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. IRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]Image: Complete in all supply, installation, Testing and Commissioning of consect of DIS Output D.B. from Earth Pit directly to be taken from Earth Pit directly to the UPS room and donnected to UPS Output D.B. from Earth Pit directly to <th>dor 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required (green for earth) multistand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sgmm + 1x4 sgmm Cu (green for earth) multistand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sgmm + 1x4 sgmm Cu (green for earth) multistand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sgmm + 1x4 sgmm Cu (green for earth) multistand conductors in steel conduits ingid steel conduit on wall with MS bar saddle , interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.Mtr5aWith 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth). With 3 Core 6 sqmm Armoured Aluminum U.G. cableMtr50bWith 3 Core 6 sqmm Armoured Aluminum U.G. cableNo2aSupply, installation and testing of 36W recessed mounted a '2x2' LED Panel with backlit technology &amp; low height feature suitable for the Armstrong / Grid Ceiling, or make Legero Model Terra Cat No. LTP 1036 or equivalent. Rate to include cost of lamps. [CLT]No2bSupply, installation, Testing and commissioning of recessed tipe X15W LED Compact &amp; sleek round LED backlit downlight made up of polycarbonate housing, high efficiency LEDs, high grade material diffuser to give uniform &amp; glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. LRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]No</th>	dor 1.0 TR AC with 25 Amp sockets housed in a Modular PVC switch Box and modular starters housed in a separate Modular MS Box with Face Plate etc. as required (green for earth) multistand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sgmm + 1x4 sgmm Cu (green for earth) multistand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sgmm + 1x4 sgmm Cu (green for earth) multistand conductors in steel conduits with all accessories as necessary complete.Image: Complete including wiring with 2x4 sgmm + 1x4 sgmm Cu (green for earth) multistand conductors in steel conduits ingid steel conduit on wall with MS bar saddle , interconnection, painting, making good to all damages etc. as required to be complete in all respect wherever required.Mtr5aWith 2 X 6 Sq.mm. + 1 x 6 sqmm (green for earth). With 3 Core 6 sqmm Armoured Aluminum U.G. cableMtr50bWith 3 Core 6 sqmm Armoured Aluminum U.G. cableNo2aSupply, installation and testing of 36W recessed mounted a '2x2' LED Panel with backlit technology & low height feature suitable for the Armstrong / Grid Ceiling, or make Legero Model Terra Cat No. LTP 1036 or equivalent. Rate to include cost of lamps. [CLT]No2bSupply, installation, Testing and commissioning of recessed tipe X15W LED Compact & sleek round LED backlit downlight made up of polycarbonate housing, high efficiency LEDs, high grade material diffuser to give uniform & glare free output with inbuilt energy efficient control gear of make Legero Model Mist (R) Cat No. LRC- R 2015 or equivalent including lamps, drivers etc. as required complete. [DL]No

CAT-6 RJ-45 loaded 24 port patch panel

Grand Total of Electrical and Lan works (A +B+C)

12 U wall mounted equipment rack

TOTAL AMOUNT (C)

6

8

7		MISCELLENOUS MATERIALS.			
	а	Supply, Installation, Testing and Commissioning of Light Point with Timer for Branch Sign Board whose location may be decided in consultation with Branch Head.	No	1	
		TOTAL (B)			

#### QTY UoM RATE SLNo **ITEM DESCRIPTION** AMOUNT Unshielded Twisted Pair CAT-6 cable laid through round 1 216 mtrs PVC conduits CAT-6 RJ-45 information outlets 10 | nos 2 5 3 **Dual Port Face Plates** nos 4 10 | nos 1 mtr Cat-6 UTP patch cord 5 10 nos 2 mtr Cat-6 UTP patch cord

#### **BOQ OF LAN - DATA & TELEPHONE**

1 nos

1 | no