

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	"A" INTERIOR FURNISHING WORK				
1	<p>Laminated Partition Providing & fixing partition, made of 50X50X1.6MM aluminium tube frame @ 2'0" c/c both ways) fixed rigidly at floor level as well as ceiling bottom, 6mm thick comm. ply of approved make with 1.00mm thick laminate of approved quality and shade shall be fixed on both faces of partition as per design with groove. Skirting shall be 100 high finished with 1.00mm thick laminate of approved quality and shade. The item includes 35mm thick flush door shutter finished with 1.00mm thick laminate on both sides with 12mm thick teak / beach edging all around with 75x50mm beach wood frame/ chowkhat .The item includes necessary hardware such as hinges, tower bolts, godrej locks with handle, door stopper etc. All exposed wooden surfaces shall be stained to approved colour finished with melamine.The rate includes making provision for electrical conduits, switches and junction boxes.</p>	525	sqft		
2	<p>Laminated / Glazed Partition Providing & fixing partition, made of 50X50X1.6MM aluminium tube frame @ 2'0" c/c both ways) fixed rigidly at floor level as well as ceiling bottom, 6mm thick comm. ply of approved make with 1.00mm thick laminate of approved quality and shade shall be fixed on both faces of partition as per design with groove. Skirting shall be 100 high finished with 1.00mm thick laminate of approved quality and shade. The item includes 35mm thick flush door shutter finished with 1.00mm thick laminate on both sides with 12mm thick teak / beach edging all around with 75x50mm beach wood frame/ chowkhat The item includes 6mm thick clear glass with 3M make film fixed at 3'0" height up to 7'0" fixed with beach wood beading .The item includes necessary hardware such as hinges, tower bolts, godrej locks with handle, door stopper etc. All exposed wooden surfaces shall be stained to approved colour finished with melamine.The rate includes making provision for electrical conduits, switches and junction boxes.</p>	150	sqft		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
3	Providing & fixing fully Glazed Partition / Glazing , made of 12mm thick polished edge toughened glass fixed rigidly at floor level and partition above glass with ENOX glazing profile EAPS-1032 or approved equivalent. The item includes Laminated Partition above 2400mm height in between False ceiling and glass, made of 50x50x1.6mm thick aluminium tube frame fixed rigidly at top with 6mm thick comm ply (BWP) finished with 1.00mm thick laminate on both side. item includes necessary hardware, fitting etc including P/F frosted film of 3M make fixed as per design, all complete in all respect	150	sqft		
4	Main Door / Cabin Door :Providing & Fixing single / double leaf glass shutter, made of 12mm thick (impact resistant glass) toughened glass with polish edges all around with 3M film fixed as per design fixed with PATCH FITTINGS of droma / ozone make assembly includes top and bottom patches, floor spring (of Dorma / ozone / ebco make,) lock (ozone / ebco make), SS brushed finished 1'6" long and 1" dia on both sides of shutter	46	sqft		
5	Low Height Partition (4'0" / 4'6" high				
	Providing & fixing partition, made of 50X50X1.6MM aluminium tube frame @ 2'0" c/c both ways) fixed rigidly at floor level as well as side walls with 6mm thick comm. Ply of approved make with 1.00mm thick laminate of approved ality and shade shall be fixed on both faces of partition as per design with groove. With 19mm th teak / beach wood edging on all exposed sides, / ends of Partitions. Skirting shall be 4" high finished with 1.00mm thick laminate. The item includes P/F 12 mm thick float glass with polished edges of 1'3" height with top corner chamfered / curved fixed with 1 ½" x 1" teak / beach wood beading, all exposed wooden surfaces shall be stained to approved colour finished with elamine.The rate includes making provision for electrical conduits, switches and junction boxes.	80	sqft		
6	Flap door Shutter / Wicket Gate				
	Providing & Fixing Wicket Gate, made of 25 mm thick flush door made of 25mm th comm ply (BWP) finished with 1.00mm thick laminate on both sides with wooden edging all around with 3" high skirting finished with 1.00mm th SS laminate of approved quality and shade with necessary hardware such as SS finish door lock, heavy duty brass hinges, SS handle, door stopper all exposed wooden surfaces shall be stained to approved colour inished with melamine	24	sqft		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
7	Cash / Single Window Partition (7'0" high)				
	Providing & fixing partition, made of 50X50X1.6MM aluminium tube frame @ 2'0" c/c both ways fixed rigidly at floor level as well as ceiling bottom, 6mm thick comm. Ply (BWP) of approved make with 1.00mm thick laminate of approved quality and shade shall be fixed on both sides of the partition as per design with groove. Skirting shall be 4" high finished with 1.00mm thick laminate. The item includes P/F 12mm thick toughened glass with polished edges at 4'0" height till 7'0" height with etching as per design fixed with 1 ½" x 1" beach wood beading, The side and intermediate partition will have an opening of 8"x4" in partition at 3'0" level, all exposed wooden surfaces shall be stained to approved colour finished with melamine. The item includes 35mm thick flush door shutter with 3"x2" beach wood frame finished with 1.00mm thick laminate on both sides with 12mm thick teak / beach wood edging all around with 6mm thick clear glass with etching as per design. The rate includes making provision for electrical conduits, switches and junction boxes. item includes necessary hardware such as hinges, tower bolts, door stoppers and Godrej make night latch. all complete as per design	50	sqft		
8	Cash Cabin Front Partition				
	Providing & Fixing 12mm thick toughened glass with polished edge with etching / film, in two pieces as per design fixed with D-brackets / beach wood beading with wooden frame of required size all complete as per design (Glass actual area shall be measured for payment)	20	sqft		
9	Gypsum Board False Ceiling				
10	Providing & fixing false ceiling as per design in perfect level and smooth finished with edge groove and cove lighting provision as per drawings, consist of G.I frame, which includes perimeter channels along with the parameter of ceiling, with intermediate channel of size 45mmx0.9mm thick with two flange of 15mm each @ 1220mm c/c with ceiling angle of size 25x10x0.55mm fixed to bottom of ceiling with G.I. cleat 27mmx37mmx25mmx1.6mm and steel expansion fastener, ceiling section of 0.55mm thick with knurled web of 80mm and two flanges of 26mm each with connecting clips of 2.64mm dia connecting clips in the direction perpendicular to the intermediate channel at 457mm c/c , 12.5mm thick Gypsum board shall be fixed with screw with filling and finishing the tapered edge with jointing compound, paper tape and painted with two or more coats of plastic emulsion paint over a cot of primer. The item includes P/F perimeter channel of size 20x27x30mm and 0.55mm thick for light fittings, AC grills, diffusers and cutouts i/c cutting of opening for light fixtures, A.C. etc All complete as per design. (The vertical and horizontal finished surface area shall be measured). Gypsum India make	900	sqft		
11	Arm Strong Grid False Ceiling				

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	Providing & fixing Grid false ceiling in the Banking hall with 16mm thick Armstrong (Make) Fine Fissured Classic tiles RH 99, with Arm strong TL 24mm exposed grid tee section, expose face shall be powder coated (white), main runner will be placed at 1200mm c/c securely fixed to the structural soffit with hangers @ 1200mm c/c and not more than 150mm from spliced joints, the last runner at the end of each main runner should not be greater than 600mm from the adjacent wall, 1200mm long cross tees to be interlock between main runners @600mm c/c to form 1200x600mm modules, 600x600mm modules to be formed by fitting 600mm long cross tee centrally between 1200mm long tees the erimeter trim to be Armstrong trulok equal wall angle of white colour secured to walls . all complete in all respect as per manufacture's specifications.	480	sqft		
12	Wall Panelling (Laminated)				
	Providing & fixing panelling on walls / columns made of 50x25x1.6mm Aluminium tube frame @ 2'0" c/c both ways or as per requirement fixed rigidly with wooden plug / rawl plug duly painted with fire resistant paint with 6 mm thick comm. ply (BWP) of approved make finished with 1.00 mm thick laminate of (approved quality and shade shall be fixed with groove as per design . Skirting shall be 4" high duly laminated with 1.00mm th Laminate . All exposed wood surfaces shall be finished with teak / beach wood moulding finished with melamine polish. The rate includes making provision for electrical conduits, switches and junction boxes. (a) Walls	500	sqft		
13	Cupboard / Storage.				

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<p>Providing & fixing 1'6" deep cupboards/ storage units with sides, Top, bottom , shutters ,partitions and shelves all made of 19mm thick Comm. Ply (BWP) of approved make The vertical partitions shall be spaced at a maximum spacing of 32" C/C and shelves shall be spaced at 18" C/C or as per drawing. The width of each shutter shall not exceed 18" The back shall be made of 6 mm thick comm. ply duly painted with anti-termite paint (on outer face) The shutter shall be made of 19mm thick comm. Ply (BWP) finished with 1.00mm thick laminate of approved quality and shade. Laminate shall be fixed on all exposed surfaces of the cupboard Top shall be made of 19mm thick comm. Ply (BWP) with wood edging finished with 1.00mm thick laminate of approved quality and shade as per design with groove on all exposed surfaces . The exposed edges / inner edges of the board / ply shall have laminate tape , Skirting shall 4" high duly finish with 1.00mm th. laminate The rate includes necessary hardware such as hinges (kich make) SS tower bolts, SS lock (ebco / europa) magnetic catchers, SS handle of approved design .</p> <p>All inner surfaces shall be finished with 0.60mm th laminate with laminate tape on exposed edges . All exposed wood surfaces shall be stained to approved colour finished with wood melamine.(The front elevation area shall be considered for payment.)</p>				
a.	Low Height Cupboard (3'0"high) Same as above but low height with 1.00mm th laminate on top and all exposed surfaces of approved quality and shade	75	sqft		
b.	Cupboard (7'0" high / up to false ceiling) same as above with laminate on all exposed surfaces	90	sqft		
c.	Electrical Panel Shutters : same as above, 19mm thick Bison Board shall be used inplace of Comm ply without back with 1.00mm thick laminate on all exposed surfaces all complete as per design with 12" x 6" powder coated aluminum (AC) grill in each shutter for ventilation with 6mm thick bison board on inner side of shutter.	40	sqft		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
14	<p>Tables</p> <p>Providing Table in position, Top shall be made 19 mm th comm. ply (BWP) with beach wood edging / molding all around as per design with 1.00mm thick laminate of approved quality and shade . The sides and apron shall be made of 19mm th comm. Ply (BWP) finished with 1.00 mm th laminate of approved quality and shade with laminate tape on all exposed ends of comm ply . The table shall have CPU trolley, foot rest made of hollock wood ,metallic key board tray on telescopic channels , cable manager of approved shade, Drawer unit consist of three drawer and tray with telescopic sliding channels with alround boxing made of 19mm th comm. Ply with vertical support of the table as one side. Drawer shall be made of 12mm comm ply wood with laminate on all surfaces .The drawer bottom shall be made of 6mm thick comm. ply The front face of the drawer shall be covered by laminate of approved shade and make. Each drawer shall have lock and SS handle.</p>				
	a) Table of Size 5'0"x2'6"x2'6" as above with three drawers	1	nos		
	b) Table of Size 4'6"x2'3"x2'6" with one drawer and storage below with laminated shutter with locks, handles etc	0	nos		
15	<p>Tables</p> <p>Providing Table in position, Top shall be made 19mm th comm. board with teak / beach wood molding as per design all around with 1.00 mm thick laminate The sides shall be made of 19mm th comm.. Board finished with 1.00mm th laminate as per design. with beech wood lipping / Laminate tape shall be fixed on all exposed ends of sides The front apron shall be made of 19mm th comm. board finished with 1.00mm thick laminate as per design of approved quality and shade. The table shall have CPU trolley, foot rest made of hollock wood ,metallic key board tray on telescopic channels , cable manager of approved shade, Drawer unit consist of three drawer with telescopic sliding channels with alround boxing made of 19mm th comm. Board with vertical support of the table as one side. Drawer shall be made of 12mm comm ply with veneer .The drawer bottom shall be made of 6mm thick comm. ply The front face of the drawer shall be covered by laminate of approved shade and make. Each drawer shall have lock and SS handle, all wooden surfaces shall be stained to approved colour finished with melamine</p>				
	a. Table of Size 6'0"x3'0"x2'6" with three drawers with locks	1	nos		
	b Extra for Providing and Fixing bevelled edge 10mm thick Clear Glass on top of Table including cutting of hole for cable manager	15	sqft		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
16	Side Rack / storage units sides, Top, bottom , shutters and shelves shall be made of 19mm thick comm. Ply (BWP) of approved quality and make finished with 1.00mm thick Laminate of approved quality and shade with 1 ¾" x 1" teak / beech wood edging./ matching laminated top Side unit shall have two drawer mounted on telescopic channel and storage box with open able shutter, The rear side shall be made of 6mm thick ply wood duly painted The top, sides, and shutter shall be finished with 1.00mm th Laminate of approved quality and shade as per design with groove . The exposed edges of the board shall have Wooden liping / Laminated tape , Skirting 4" high duly finished with laminate. The rate includes necessary ardware such as SS hinges , SS tower bolts, locks , magnetic catchers, 4" long SS handle of approved quality and design . All inner surfaces shall be finished with 0.6mm th laminate and all exposed wooden surfaces shall be stained to approved colour finish with melamine.				
	a) 3'6" x 1'6" x 2'3" (high) side rack	0	nos		
	b) 3'0" x 1'6" x 2'3" (high) side rack	2	nos		
17	CASH COUNTER				
	Providing & fixing Cash Counter of length 1350 / 1500 mm as per layout plan with Writing top, Upper top, front projected face, sides and front apron all shall be made of 19mm thick comm. Ply (BWP) of approved quality and make with wooden lipping / moulding on exposed ends of comm.. board. The writing top and front apron, projected face and exposed sides shall be finished with 1.00 mm thick laminate of proved shade and the upper top shall be provided with 20mm thick pre-polished granite stone of approved shade (as per the sample) with 19mm th. Comm. Ply (BWP) . The exposed edges of the granite shall be rounded on both the edges (outer & inner face) all exposed edges of counter top shall be 40mm thick finished with laminate tape, The skirting shall be 100mm high finished with 1.00mm thick laminate. There shall be a CPU shelf of size 600mm x 300mm made of 19mm commercial Ply (BWP) fixed at height of 150mm inside the counter with alround teakwood lipping with laminate on top and skirting. There shall be wooden foot rest made of hollock wood . There shall be metallic key board tray of approved make There shall be a drawer unit consists of three drawer with alround boxing made of 19mm thick comm. Ply with Vertical support of the counter as one side. The drawer shall be made of 19mm th. Comm Ply . The drawer bottom and rear side of the unit shall be covered by 6mm commercial plywood. The front face of the drawer shall be covered by 1.00 mm thick laminate of approved shade and make. Each drawer shall have multipurpose lock (godrej- metallic), drawer telescopic sliding channel and SS handle. All the non laminated surfaces shall be painted with enamel paint over a coat of wood primer. all exposed wooden surfaces shall be stained to approved colour finished with melamine. The overall dimensions shall be : Length = 1350 to 1500mm each unit Width of writing top = 800mm, width of upper /customer top = 400mm, height of writing platform= 750mm, height of customer platform above writing top = 400mm	10	Rft		
18	LOW HEIGHT COUNTER (SINGLE TOP)				

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
	<p>Providing & fixing running Low height Single top Counter as per layout plan with Writing top, upper top, sides and front apron and upper top shall be made of 19mm thick comm. Ply (BWP) of approved quality and make with rubber wood with lipping on exposed ends of comm. board. The front apron, exposed sides and drawer unit shall be finished with 1.00 mm thick laminate of approved quality and shade. The writing top shall be made of 19mm thick comm.. Ply with 1.00mm thick laminate with 40x40mm rubber wood edging on exposed faces of top. The skirting shall be 100mm high duly laminated. The exposed edges of the Counter shall be finished with 40mm wide laminate tape (outer & inner face) There shall be a CPU shelf of size 600mm x 300mm made of 19mm commercial block board fixed at height of 150mm inside the counter with around teakwood lipping. There shall be wood foot rest made of hollock wood. There shall be metallic key board tray of ebco make. There shall be a drawer unit with each unit, drawer unit consists of one drawer with storage unit with around boxing made of 19mm commercial block board with vertical support of the counter as one side. The overall dimension of the drawer unit shall be 16" wide and 24" deep all made of 19mm commercial block board. The drawer bottom shall be made of 6mm th. Comm.. ply and rear side of the unit shall be covered by 19mm th. Marine grade ply. The front face of the draw shall be covered by 1mm th. lamination of approved shade and make. Each draw shall have multipurpose lock (godrej) and SS handle. All the non laminated surfaces shall be finished with wood polish. The overall dimensions shall be : Length =1200 to 1350mm per seat, Width of writing top = 750mm, height of writing platform= 750mm.</p>	23	Rft		
19	<p>Texture Paint (Front Hall) Providing and applying texture paint of approved make in rustik / criss cross design of approved shade including preparation / repairing of surface with plaster of paris punning base with all complete in all respect as per manufacturer's specification</p>	600	sqft		
20	<p>Customer's Writing Stand Providing & fixing customer's writing table, made of 19mm th comm. Ply structure with with 1.00mm thick laminate on all inner and exposed surfaces with wooden lipping on all exposed ends of comm. board finished with melamine, top and vertical division shall be made of 12mm thick polished edge glass fixed with SS fittings. Size 4'0" x 1'6" x 6" high rest on 4'0" wide 3'0" high and 1'6" deep Low height cupboard made of 19mm thick comm. ply box with 19mm thick comm ply shutter with 1.00mm th laminate on all exposed surfaces and 0.6mm thick laminate on all inner surfaces with slit on both shutter for notice and complaints as per design with 19mm th comm ply shelves and partitions with neccessary SS hardware such as hinges, tower bolts, Godrej locks, magneticcatchers, handles etc items includes P/F laminate tape on all exposed ends of comm. ply, skirting shall be 4" high duly laminated</p>	1	nos		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
21	Providing & fixing wooden boxing over glazing to cover the rolling shutter, made of 50x50mm wooden frame frame including cutting of wall and embedded into wall with cement concrete with required supports, covered with 12mm thick Comm Ply (BWP) finished with three or more coats of enamel paint over a coat of primer including filling, sand papering and preparation of surface. Item includes making opening / shutter for covering of rolling shutter with closing arrangement at bottom	100	sqft		
22	Providing and fixing Aluminium Composite Panel for external wall cladding using 3mm thick ACP with aluminium foil thickness of 0.5mm on both sides and 2mm thick poly ethylene core of euro bond, Aluco Panel / Aludecor make. The panel should be of PVDF paint coating of Bank approved shade and size, and to be fixed properly to the aluminium frame work using trey system. Combination of shade should be used as per design. The frame work should be made of 48x25mm size and 2mm thick aluminium box section. The joint should be finished with silicon based weather proof sealent of Dow corning make with necessary hardware such as clamps, anchoring bolts, bolts, nuts and other fastening material . The rate should be include all the material, labour, wastage, scaffolding etc	60	sqft		
23	Providing & fixing Pin up board made of 12mm thick soft particle board of medium density covered with fabric of approved quality and shade.	36	sqft		
24	Providing & applying Oil bound Distemper to all internal walls with two coats of Oil bound Distemper of approved shade and colour of Asian Paints or equivalent make and a coats of wall primer of Asian Paints or equivalent make. scrapping and rubbing it with sand paper and repairing the surface wherever required . The rate shall include the coats of all materials, labour, scaffolding, cleaning the glass planes, floor for paint drops after completion of painting works etc., complete. (Back area, toilet block, passages etc)	2000	sqft		
25	Providing & fixing aluminium alloy silver metallic colour door closure (Ozone make)	8	nos		
26	Enamel Paint Providing & applying two or more coats of synthetic enamel paint on doors , grills shutter etc. over a coat of plaster and primer including cleaning, rubbing, sand papering and repairing of surface.,	500	sqft		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
27	Providing and fixing 35mm ISI marked flush door shutters conforming to IS :2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutter with 1.00mm thick laminate on both sides with teak wood edging with 100x 62.5mm beach wood chowkhate as required with polishing of door frame with necessary SS hardware such as hinges, tower bolts, godrej 6 lever lock with a set of decorative lever handle, door stoppers etc (Door Size 3'0"x7'0")	2	nos		
	(b) Door Size-- 2'6"x7'0"	2	nos		
28	Counter Front Partition: Providing & Fixing 12mm thick Float glass with polished edge with etching / film as per design fixed with D-brackets / beach wood beading with aluminium tube frame covered with 6mm thick Comm ply (BWP) finished with 1.00mm thick laminate of approved quality and shade as per detail drawings	40	sqft		
29	Providing & Fixing 6mm thick Powder Coated aluminium grill on top of cash cabin , of approved design with required frame duly laminated	40	sqft		
	"A" INTERIOR FURNISHING WORK (BRANCH)				
	"B" ATM FURNISHING WORKS				
1	Gypsum Board False Ceiling Providing & fixing false ceiling as per design in perfect level and smooth finished with edge groove and cove lighting provision as per drawings, consist of G.I frame, which includes perimeter channels along with the parameter of ceiling, with intermediate channel of size 45mmx0.9mm thick with two flange of 15mm each @ 1220mm c/c with ceiling angle of size 25x10x0.55mm fixed to bottom of ceiling with G.I. cleat 27mmx37mmx25mmx1.6mm and steel expansion fastener, ceiling section of 0.55mm thick with knurled web of 80mm and two flanges of 26mm each with connecting clips of 2.64mm dia connecting clips in the direction perpendicular to the intermediate channel at 457mm c/c , 12.5mm thick Gypsum board shall be fixed with screw with filling and finishing the tapered edge with jointing compound, paper tape and painted with two or more coats of plastic emulsion paint over a coat of primer. The item includes P/F perimeter channel of size 20x27x30mm and 0.55mm thick for light fittings, AC grills, diffusers and cutouts i/c cutting of opening for light fixtures, A.C. etc All complete as per design. (The finished surface area shall be measured).	55	sqft		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
2	Main Door / Cabin Door :Providing & Fixing single / double leaf glass shutter, made of 12mm thick (impact resistant glass) toughened glass with polish edges all around with 3M film fixed as per design fixed with PATCH FITTINGS of drama / ozone make assembly includes top and bottom patches, floor spring (of Dorma / ozone / ebco make,) lock (ozone / ebco make), SS brushed finished 1'6" long and 1" dia on both sides of shutter	21	sqft		
3	Front Glazing Providing & Fixing 12mm thick (impact resistant glass) toughened glass with polish edges on sides / joints with 3M film fixed as per design fixed with PATCH FITTINGS of drama / ozone make assembly includes top and bottom patches,	42	sqft		
4	Providing & fixing panelling , made of 25X50X1.6MM aluminium tube frame @ 2'0" c/c both ways) fixed rigidly at floor/ walls with wooden plug / rawl plug with 6 mm thick comm. ply of approved make finished with 1.00 mm thick laminate of (approved quality and shade shall be fixed with groove as per design . Skirting shall be 4" high duly laminated with 1.00mm th Laminate . All exposed wood surfaces shall be finished with teak / beach wood moulding finished with melamine polish. The rate includes making provision for electrical conduits, switches and junction boxes.	225	sqft		
5	Texture Paint Providing and applying texture paint of approved make of Flakes in two shades of approved shade including preparation of surface with plaster of paris punning all complete in all respect as per manufacturer's specification	0	sqft		
6	Providing and fixing Aluminium Composite Panel for external wall cladding using 3mm thick ACP with aluminium foil thickness of 0.5mm on both sides and 2mm thick poly ethylene core of euro bond, Aluco Panel / Aludecor make. The panel should be of PVDF paint coating of Bank approved shade and size, and to be fixed properly to the aluminium frame work using trey system. Combination of shade should be used as per design. The frame work should be made of 48x25mm size and 2mm thick aluminium box section. The joint should be finished with silicon based weather proof sealent of Dow corning make with necessary hardware such as clamps, anchoring bolts, bolts, nuts and other fastening material . The rate should be include all the material, labour, wastage, scaffolding etc	50	sqft		
7	Providing & applying two or more coats of synthetic enamel paint on doors , grills , rolling shutter etc. over a coat of plaster and primer including cleaning, rubbing, sand papering and repairing of surface.,	150	sqft		

BOQ for Furnishing Works AT ALTERNATE PREMISES FOR CANARA BANK, TAURU Branch & ATM DISTT NUH (HR)					
S.No	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
8	Laminated Partition Providing & fixing partition, made of 50X50X1.6MM aluminium tube frame @ 2'0" c/c both ways) fixed rigidly at floor level as well as ceiling bottom, 6mm thick comm. ply of approved make with 1.00mm thick laminate of approved quality and shade shall be fixed on both faces of partition as per design with groove. Skirting shall be 100 high finished with 1.00mm thick laminate of approved quality and shade. The item includes 35mm thick flush door shutter finished with 1.00mm thick laminate on both sides with 12mm thick teak / beach edging all around with 75x50mm beach wood frame/ chowkhat .The item includes necessary hardware such as hinges, tower bolts, godrej locks with handle, door stopper etc. All exposed wooden surfaces shall be stained to approved colour finished with melamine.The rate includes making provision for electrical conduits, switches and junction boxes.	60	sqft		
"B "ATM FURNISHING WORKS		TOTAL			
SUMMARY					
	"A" FURNISHING WORKS (BRANCH)				
	"B" FURNISHING WORKS (ATM)				
	TOTAL COST OF WORKS RS				
					Escluding GST