

**REQUEST FOR QUOTES [RFQ 074/2024-25]**

for

For Carrying out structured LAN cabling work at i) Planned renovation area at Head Office Annex in 3<sup>rd</sup> and 4<sup>th</sup> floor, Naveen Complex, Bengaluru, ii) Provisioning of additional ports at FCC Group, TO Wing, HO.

Issued by: **Canara Bank**  
**Centralized Procurement & Vendor Management Wing, HO (Annexe)**  
**1<sup>st</sup> Floor, Naveen Complex**  
**14, M G Road**  
**Bengaluru-560 001**  
**Phone No:080-25584873**  
**Email: [singletender@canarabank.com](mailto:singletender@canarabank.com)**

This bid is restricted to the following vendors who are empaneled in Canara Bank through EOI-03/2022-23 dated 04/01/2023.

1. M/s J K Networks
2. M/s Mass Network Solution Pvt Ltd
3. M/s Mould Training and Networks (India) Pvt Ltd
4. M/s Surabhi info

**BID SCHEDULE**

Sl. No.	Description	Details
1.	RFQ No. and Date	RFQ 074/2024-25 dated 09/01/2025 for Carrying out structured LAN cabling work at i) Planned renovation area at Head Office Annex in 3 <sup>rd</sup> and 4 <sup>th</sup> floor, Naveen Complex, Bengaluru, ii) Provisioning of additional ports at FCC Group, TO Wing, HO through Bank's empaneled vendors.
2.	Location Address for submission of Bid/s [Address for Communication]	The Senior Manager Canara Bank, Centralized Procurement & Vendor Management Wing, Head Office (Annexe) 1 <sup>st</sup> Floor, Naveen Complex 14, M G Road Bengaluru -560 001 Karnataka Tel - 080-25584873 Email: <a href="mailto:singletender@canarabank.com">singletender@canarabank.com</a>
3.	Date of Issue	09/01/2025, Thursday
4.	Last Date of Submission of Bids	30/01/2025, Thursday up to 03:00PM
5.	Date and Time of Opening Bids	30/01/2025, Thursday at 03:30PM

Dear Vendor,

Bank intends to carry out structured LAN Cabling work at Head Office Annex location - Naveen Complex, Bengaluru through Bank's empaneled vendors.

1.	Details of the Hardware/Software/IT Service	To Carry out structured LAN cabling work at i) Planned renovation area at Head Office Annex in 3 <sup>rd</sup> and 4 <sup>th</sup> floor, Naveen Complex, Bengaluru, ii) Provisioning of additional ports at FCC Group, TO Wing, HO through Bank's empaneled vendors.
2.	Scope of Work	As per Annexure-1
3.	Technical Specification of the Item	NA
4.	Time Lines for Delivery/ installation/Implementation	2 weeks
5.	Warranty Period (If applicable)	NA
6.	Payment Terms	As per Annexure -3.
7.	Bill of Material	As per Annexure-2
8.	Mode of Submission of Bid/Quote	Hard copy (The bid should be submitted in sealed cover addressed to the Bank at the below mentioned address within the date and time specified).
9.	Bid Submission Due Date & Time	30/01/2025, Thursday up to 03:00PM
10.	Other Terms and Conditions	As per RFQ 074/2024-25 dated 09/01/2025
11.	Any Other Information	Vendor may visit the locations before quoting the amount for better estimation.

Yours Faithfully,

Authorized Signatory

Note: For further clarification, if any, please contact us.

The Senior Manager  
Canara Bank,  
Centralized Procurement & Vendor Management Wing,  
Head Office (Annexe)  
1<sup>st</sup> Floor, Naveen Complex  
14, M G Road  
Bengaluru -560 001  
Ph. No: 080- 25584873.

**ANNEXURE-1**

**SCOPE OF WORK**

**SUB: To Carry out structured LAN cabling work at i) Planned renovation area at Head Office Annex in 3<sup>rd</sup> and 4<sup>th</sup> floor, Naveen Complex, Bengaluru, ii) Provisioning of additional ports at FCC Group, TO Wing, HO through Bank's empaneled vendors.**

**Ref: RFQ 074/2024-25 dated 09/01/2025.**

The Scope of work is mentioned below but not limited to the following:

- 1) Vendor has to do the Structured Lan cabling work at Identified desks using materials and spares of mentioned OEM make only.
- 2) Vendor has to ensure all the cables are concealed inside PVC conduit and not to be exposed to any kind of rodents.
- 3) Vendor has to attend the service calls in future as per need basis to restore network connectivity using excess materials and spares available at HO wings.
- 4) Vendor has to arrange Tapes/ Screws at his end for need based consumption of materials.
- 5) Vendor has to arrange required ladder/ LAN Tester/ Crimping Tool/ Drilling Machine and other necessary tools from his end.
- 6) Vendor has to use the hard flexible wherever required.
- 7) Vendor has to provide any one of the materials make, for example, if vendor provides cat 6 cable of Amp make, they've to provide rest of the materials of Amp make only.
- 8) Vendor has to provide one-year service warranty.
- 9) Vendor must take the remaining full quantities in case not used, without adding it to the invoice.

**Labour Related Instructions:**

1. Vendor should ensure that all the laborers who are executing project should have valid government approved ID Card and should display whenever asked/enquired.
2. Vendor should provide the list of all laborers along with the details [Name, Contact, Address, ID proof, ID Card No] who are coming to work priory to get the work permission.
3. Vendor is solely responsible for the safety of all the laborers who are involved while executing the project.
4. Vendor is solely responsible for any damage/ faults created either mistakenly/unknowingly or knowingly whatever might be the cause during the execution of the project, and the same will be recovered from the vendor either from the involved project cost or additionally.
5. Vendor has to co-ordinate with the other contractors who are present in site such as electricians, carpenter and masons in order carry out the work smoothly.
6. Vendor should be available immediately onsite within 30 minutes, till the work is completed.

7. Locations details are as mentioned below:

<b>Location 1</b>	Canara Bank, 3rd Floor, Head Office(Annex) Naveen Complex, #14, MG Road, Bangalore-560001  Contact Person Name: Mr. Vignesh U K Phone No.: 78490 76868
<b>Location 2</b>	Canara Bank, 4 <sup>th</sup> Floor, Head Office(Annex) Naveen Complex, #14, MG Road, Bangalore-560001  Contact Person Name: Mr. Vignesh U K Phone No.: 78490 76868
<b>Location 3</b>	Canara Bank, 6 <sup>th</sup> Floor, Head Office(Annex) Naveen Complex, #14, MG Road, Bangalore-560001  Contact Person Name: Mr. Vignesh U K Phone No.: 78490 76868

We comply to all the points mentioned in Scope of work, without any deviation.

Date:

Signature with seal

Name :

Designation :

**ANNEXURE-2**

**Bill of Material**

**SUB: To Carry out structured LAN cabling work at i) Planned renovation area at Head Office Annex in 3<sup>rd</sup> and 4<sup>th</sup> floor, Naveen Complex, Bengaluru, ii) Provisioning of additional ports at FCC Group, TO Wing, HO through Bank's empaneled vendors.**

**Ref: RFQ 074/2024-25 dated 09/01/2025.**

**Location 1: Planned renovation area in 3<sup>rd</sup> Floor, Canara Bank, Head Office (Annex)- Naveen Complex, Trinity Circle, Bengaluru.**

**Table-1A**  
**Material Charges**

[Amount in INR]

SNo.	Description Of the Item	Quantity	Unit Price	Total Amount (Excl of Tax)	% of Tax	Tax Amt	Total Price (Including Tax)
1	CAT6 100% Copper	21 boxes [6405 m]					
2	CAT6 I/O's	150					
3	Dual Face Plate and Backbox	79					
4	24 Port Loaded Patch Panel	7					
5	Cable Managers	7					
6	2 m Patch Cord	300					
7	100 x 50 PVC Channel	10					
8	100 x 100 PVC Channel	10					
9	1" PVC Pipe / Casing / Flexible	300 m					
10	1.5" PVC Pipe / Casing / Flexible	550 m					
11	2" PVC Pipe / Casing / Flexible	100 m					
12	C channel set with 8mm threaded rod, anchor fastner with nut. Bolt and washers	35					
13	Floor Standing Rack 42 U 600*800 650 depth [ With 2 vertical PDUs and 4 Fans ]	1					
<b>Total Amount</b>							

**Note:** All the materials make should be either Amp/ Commscope / Molex / Dlink.

**Table-1B**  
**Labour Charges**

[Amount in INR]

Sl. No	Description of Services	Qty	Unit Price	Total Amount (Excl of Taxes)	% of Tax	Tax Amt	Total Price (Including Tax)
1	Laying of the copper cable along with the PVC & accessories and labelling	6405					
2	Assembling and Dressing of 42 U Rack along with the accessories post the termination of I/O points	1					
3	Mounting of switches and patch panel	7					
4	Termination and Labelling of I/O points at both work station and patch panel end	150					
5	Removal of Existing Cables, 15 U Rack, patch-panels, Switches End-to-End from rack to end points	1 Lot					
6	Redressing of the existing 27 U Rack	1					
<b>Total Amount</b>							



**Location 2: Planned renovation area in 4<sup>TH</sup> Floor, Canara Bank, Head Office (Annex)-  
Naveen Complex, Trinity Circle, Bengaluru.**

**Table-2A**  
**Material Charges**

[Amount in INR]

SNo.	Description Of the Item	Quantity	Unit Price	Total Amount (Excl of Tax)	% of Tax	Tax Amt	Total Price (Including Tax)
1	CAT6 100% Copper	15 boxes [4575 m]					
2	CAT6 I/O's	140					
3	Dual Face Plate and Backbox	70					
4	24 Port Loaded Patch Panel	6					
5	Cable Managers	6					
6	2 m Patch Cord	280					
7	100 x 50 PVC Channel	10 m					
8	100 x 100 PVC Channel	10 m					
9	1" PVC Pipe / Casing / Flexible	250 m					
10	1.5" PVC Pipe / Casing / Flexible	600 m					
11	2" PVC Pipe / Casing / Flexible	100 m					
12	C channel set with 8mm threded rod, anchor fastner with nut. Bolt and washers	35					
13	Pigtails and Couplers for Fiber Shifting	6 Pairs					
<b>Total Amount</b>							

**Note:** All the materials make should be either Amp/ Commscope / Molex / Dlink.

**Table-2B**  
**Labour Charges**

[Amount in INR]

Sl. No	Description of Services	Qty	Unit Price	Total Amount (Excl of Taxes)	% of Tax	Tax Amt	Total Price (Including Tax)
1	Laying of the copper cable along with the PVC & accessories and labelling	4575 m					
2	Unmounting of existing switches and redressing of the existing 42 U rack post the termination of I/O points	1					
3	Mounting of switches and patch panel	6					
4	Termination and Labelling of I/O points at both work station and patch panel end	140					
5	Removal of Existing Cables, 15 U Rack, patch-panels, Switches End-to-End from rack to end points	1 Lot					
6	Rerouting of the 3-core Fiber Cable, splicing and re-termination	30 m					
<b>Total Amount</b>							

Location 3: 6<sup>th</sup> Floor, FCC Group, TO Wing, Canara Bank, Head Office (Annex)-Naveen Complex, Trinity Circle, Bengaluru.

Table-3A  
Labour Charges

[Amount in INR]

Sl. No	Description of Services	Qty	Unit Price	Total Amount (Excl of Taxes)	% of Tax	Tax Amt	Total Price (Including Tax)
1	Laying of the copper cable along with the PVC & Accessories and labelling	1500 M					
2	Mounting of 12 U rack, switch and accessories	1					
3	Mounting of Switches and Patch Panel	1					
4	Termination and Labelling of I/O points at both work station and patch panel end	20					
<b>Total Amount</b>							

**Table-4**

**Total Charges**

[Amount in INR]

<u>Location</u>	<u>Material Charges</u>		<u>Labour Charges</u>	
	<u>Exclusive of Taxes</u>	<u>Inclusive of Taxes</u>	<u>Exclusive of Taxes</u>	<u>Inclusive of Taxes</u>
Planned renovation area in 3 <sup>rd</sup> Floor, Canara Bank, Head Office (Annex)-Naveen Complex, Trinity Circle, Bengaluru.				
Planned renovation area in 4 <sup>th</sup> Floor, Canara Bank, Head Office (Annex)-Naveen Complex, Trinity Circle, Bengaluru.				
6 <sup>th</sup> Floor, FCC Group, TO Wing, Canara Bank, Head Office (Annex)-Naveen Complex, Trinity Circle, Bengaluru.	-----			
<b><u>Total Price(Material Charges + Labour Charges) (Exclusive of Taxes)</u></b>				
<b><u>Total Price(Material Charges + Labour Charges) (Inclusive of Taxes)</u></b>				

ANNEXURE-3

Payment Terms

**SUB: To Carry out structured LAN cabling work at i) Planned renovation area at Head Office Annex in 3<sup>rd</sup> and 4<sup>th</sup> floor, Naveen Complex, Bengaluru, ii) Provisioning of additional ports at FCC Group, TO Wing, HO through Bank's empaneled vendors.**

**Ref: RFQ 074/2024-25 dated 09/01/2025.**

1. There won't be any advance payment for the procurement or implementation.
2. Vendor should complete the implementation within the provided timelines, if failed to do so, the payment will be deducted on per day Rs. 2000/- with a maximum cap of 10% of entire order.
3. 100% payment should be released on submission of invoice, Confirmation of work completion from Network Administration Section, IT Wing, HO.
4. The payments will be released through NEFT/RTGS and the selected bidder has to provide necessary bank details like account number, bank's name with branch name, Correct IFSC code etc.

Date:

Signature with seal:

Name :

Designation :