

SCHEDULE OF QUANTITIES CIVIL WORK OF CANARA BANK AT SUBROTO PARK , BRANCH ,NEW DELHI					
S.No	Particulars	Quantity	Unit	Rate	Amount
	CIVIL WORK				
1	Dismantling of existing brick work, door chowket, door, electrical work , all existing sanitary fixtures namely W.C. wash basin , preparing surface by removing tiles on floor/walls and roughening the surface for fixing ceramic tiles on walls/floor all plumbing pipes, dismantling of floor removal of cinder filling and removal of malba etc. complete and dispose off the debris from the site.	1.00	Nos.		
2	12MM plaster cement sand 1:6 in walls (1 cement : 6 fine sand)	200.00	SQ.FT.		
3	P.C.C. IN FLOORING 1:2:4	210.00	S.FT		
	Providing & laying 4" thk. Cement concrete in flooring in 1:2:4 proportion, finished with a floating coat of neat cement slurry, etc. Complete. The rate shall be inclusive of compact soil filling for proper levelling.				
	TILING WORK				
4	Ceramic tile flooring :- providing and laying ceramic tile of approved make , quality and shade and pattern as per the drawing in cm 1:4 in proper line and level. Rate shall be inclusive of providing and laying necessary backing material and joint filling compound of the same shade of the tiles.	220	SQ.FT.		
5	Ceramic tile over the wall :- providing and laying ceramic tile of approved make , quality and shade and pattern as per the drawing in cm 1:4 in proper line and level. Rate shall be inclusive of providing and laying necessary backing material and joint filling compound of the same shade of the tiles.	1040	SQ.FT.		
6	Providing & Laying 32" x 32" x 8mm thick to 10mm thick Italian maeble finish vitrified tiles of First quality in approved colors to floor in required position fixed with bed of cement Morter (1:4) about 2" to 3" thick including 4mm thick to 5mm thick float of cement filling the joints withneat matching color cement slurry, rubbing, washing etc. complete as per the instructions of Architect. Cost to be inclusive of taping on all the joints & covered the entire flooring with good quality plastic (300 microns) & POP above cover & Tape to be removed before final cleaning etc. Complete as per detail drg. & instructions of Architect. (Basic cost of Vitrified Tile not less than Rs.	2040	SQ.FT.		

7	GRANITE SLAB (BLACK COLOUR) ON STAIR STEPS & PANTRY COUNTER	117.00	SQ.FT.		
	Providing and fixing 20mm thick granite slab of approved quality & shade as per approved pattern by Bank and according to specified sizes. The rate shall include machine polishing the edges with V Groove, necessary backing material, water proofing and joint filling compound of the same shade as that of the granite slab.complete with all.				
	WOODEN WORK				
8	Providing and fixing ISI marked flush doors of sizes(2'-6" to 3'-3" x 7'-0") . The door shutter conforming to IS : 2202 (PART 1) non - decorative type, core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face vaneers on front faces of shutter and back side with paint . The edges finished with steam beach lipping with melamine polish. Rate shall include approved (by bank) door closure, door stopper, door locks, a pair of handles 9" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items and with out door frames as mentioned above.	89.00	SQ.FT.		
9	Providing Door frames of size 5"x2.5" to all toilets and rooms using best quality hard wood marindy type with necessary clamps , hold fast and supports etc.. The frame should be made to support door shutters of 1" thick , ie, groves to be provided for holding 1" thick shutters.	70	R.FT.		
10	Providing & Fixing Stainless Steel Kitchen sink bow (overall size 25 x 18x9 inches and thickness 1.2mm appox. Or as per site requirement / directed by bank of make Hindware/ Kohler/Kaff) square design satin finish in the kitchen platform as under counter type in the granite slab neatly according to the size of sink complete as directed. The item includes waste coupling stainer drain drop connection to the floor trap, waste pipe including cost of all materials, labour charges etc. complete with all the fitting and accessories.	1.00	Nos.		
	PAINTING WORK				
11	Painting two or more coats of plastic emulsion paint nerolac allscapes required original shade after prepaing the wall surface smooth with primer and sand papering to achieve smooth surface, including	2400.00	SQ.FT.		

12	Enamel paint : Providing & applying 1st quality of paint of approved make , quality & shade . The rate shall include scrapping levelling & preparing the surface with primer quote.	480.00	SQ.FT.		
	SANITARY WORK				
13	Providing & fixing star white vitreous water closet European type WC (parryware make) including all necessary fitting like seat cover & C.I. chair brackets, cisten complete with all fitting and lid, with C.P. brass hinges and rubber buffers,with fitting and unious , C.P. flush bend etc. complete painting wherever required and cutting and making good the walls and floors: with necessary s & p traps on floor.	3.00	nos.		
14	P& F white glazed vitreous china wash basin with C.I. bracket ,15 mm C.P. piller tap, c.p. brass waste 32 mm of standard pattern c.p. bottle trap and unions and sealing of joints between wash basin and counter slabs around the wash basin with silicone rubber cement of approved make of matching colour all complete including cutting and making good the walls and floors where required. (Parryware make)				
	size 550 x 400 mm	2.00	Nos.		
15	Providing & fixing Urinal with all the fixtures, the rate for the following shall be inclusive of all necessary fixtures, labour charges accessories & attachments to make then operational.(Hindware/ Parryware make)	2.00	NOS.		
16	Providing & fixing Urinal partition of ceramic complete with all. (Hindware/ Parryware make)	1.00	NOS.		
17	P & F Chlorinated polyvinyl chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings fixing the pipe with clamps at 1.0 m spacing . This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in charge.				
	Concealed work including cutting , chases and making good the wall etc.				
	20 mm nominal outer dia pipes.	35.00	Rmt.		
	25 mm nominal outer dia pipes.		Rmt.		

18	Providing & fixing PVC pipes of supreme/prince make or equivalent in position of required size with special fittings, traps, bends, ys, floor & nahni traps etc. Including chemical sealed joints as required at site making necessary connections with existing lines for w.c. & waste water lines, chambers to be constructed wherever necessary, unused lines for w.c. & waste water to be removed, the rate shall include all incidental work, cutting & making good walls & floors etc. Complete. Please visit the site for inspection.				
	100 mm nominal outer dia pipes.	15.00	Rmt.		
	75 mm nominal outer dia pipes.	6.00	Rmt.		
19	P&F basin tap of superior quality and approved make.				
	C.P. Basin type , 15mm nominal bore.	2.00	Nos.		
20	P&F Bib cock brass 400gm. 15 mm nominal bore , superior quality and of approved make.	2.00	Nos.		
21	P&F concealed stop cock of 15 mm , superior quality and of approved make.(jaguar)	3.00	Nos.		
22	P&F c.p. inlet connection 15 mm brass (IS : 8931 Marked Angle valves) superior quality of approved make foe wash basin , geyser etc.	14.00	Nos.		
23	P & F CP cpat hook	2.00	Nos.		
24	P & F power coated jali on floor trap	9.00	Nos.		
25	P & Fixing CP Health Faucet with 120 cm ss flexible tube & ABC wall hook , complete.	2.00	Nos.		
26	Providing & Fixing 15mm dia CP Water jet for W.C. with connecting CP pipe, complete in all respect.	14.00	Nos.		
27	Providing & Fixing 15mm dia flexible pipe for W.C. and wash basin with connecting CP pipe, complete in all respect.	9.00	Nos.		
28	P & F SS soap dish fixed with SS screws of approved quality / make.	2.00	nos.		
29	P & F SS tower stand fixed with SS screws of approved quality / make.	2.00	nos.		

30	Providing & fixing Bevelled edge mirror of size 600 x 450 x 5 mm thick special glass of approved make (modi guard saint gobain or equivalent) complete with 6mm thick asbestos cement sheet ground fixed to wooden screw & washers.	2.00	nos.		
	Sub Total				
A	TOTAL FOR CIVIL WORKS (EXCLUDING GST)				
	Discount If any (Only on Excluding GST amount only)				
	Net Amount (After Discount if any - Excluding GST) (Discount if any shall be given on Amount in Sub part (A -Excluding GST) Not on sub part (C)).				
	GST as extra as applicable (For CIVIL works) - By Bank				
	<i>Internal</i>				
B	Buyback Amount for Old/Unused Items (Credit to Bank) (EXCLUDING GST)				
	The work includes giving credit to Bank towards the existing toilet, fittings, shutter, grill etc after carefully dismantalling and thereafter disposal of the same from the Branch site. No additional amount shall to paid for dismantalling, transportation, etc. works.				
	GST as extra as applicable (For Buy back) - By Vendor				
C	GRAND TOTAL {Civil Work Amount less Buyback Amount} [A -				
	GST as extra as applicable				
	PLACE:				
	DATE:			SEAL AND SIGNATURE OF THE CONTRACTOR WITH ADDRESS	