

BOQ FOR INTERIOR FURNISHING WORKS OF GHUNGOOR BRANCH AT SILCHAR, ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	CARPENTRY IN LAMINATE				
	<b>GENERAL NOTES FOR CARPENTRY WORKS</b>				
	1. All Plywood and Block board to be used in Carpentry works should strictly be of Century/ Green/ Duro ply/ Kitply/ Archid ply only				
	2. All Plywood/ Block Board used to be of commercial grade but of above make only				
	3. All laminates should strictly be 1.0mm thk of Century/Greenlam or Merino make				
A	<b>BRANCH FURNISHING WORK (A).</b>				
A	<b>TABLE , DESKS , DRAWERS AND STORAGES</b>				
	<b>ALL TABLES / WORK STATIONS SHOULD HAVE KEYBOARD TRAY, CPU TROLLEY(METAL), FOOT REST AND RATES SHOULD BE QUOTED ACCORDINGLY WITHOUT ANY EXTRA CLAIM</b>				
i	<b>Front Office/ Clerical Counter:</b>	RFT	24.00		
	Providing and fixing in position Front Office Counter 2'-6" wide as per drawing comprising of the following complete in all respects:-				
	i) Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1½"X1" Teak Wood moulding finished with melamine polish. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine finish.				
	ii) Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.				
	iii) Vertical drop box (horizontal band) of size 12" ht x 10" thickness(hollow inside) shall be provided suspended from the ceiling lvl on the facia above the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light,				
	iv) Glazed partition above working top(ON FRONT AN SIDES dividing each work station to be provided with 12mm thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.				
	v) vertical supports made with 18 mm thick plywood finished with white enamel paint.				
	vi) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.				
	vii) Footrest made with T.W. member of size 4"X1 ½ " finished with french polish.				
	viii) 3-Drawer units as per drawing shall be provided with multipurpose Godrej locks in				
	Each drawer. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.				
	ix) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.				
	<b>The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"x10" boxing as shown in the drawing. Necessary beadings with melamine polish for fixing the glass are to be provided</b>				
	<b>The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.</b>				
ii	<b>Cash Counter:</b>	NOS	1.00		
	Providing and fixing in position Cash Counter as per drawing comprising of the following :				
	i) Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1½"X1" Teak Wood moulding finished with melamine polish. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine polish.				
	ii) Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.				
	iii) Vertical drop box (horizontal band) of size 12" ht x 10" thickness(hollow inside) shall be provided suspended from the ceiling lvl on the facia above the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light,				
	iv) 1'-0" height solid partition over working top and fixed with a ledge(transaction top) of 12" wide @3'-6" from finished floor lvl and finished with laminate. The ledge should be such that it is 8" projecting outside the counter and 4" inside the counter				
	v) A gap of 4" should be left above the transaction top (all along the width of the teller counter)				
	vi) Glazed partition having height 1'.0" above the transaction top (in facia) and also above 4" clear gap shall be provided with 12 mm thick glass (itched) as per drawing. The edges of cut out and the top edge of glass are to be mirror polished and to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing.				
	vii) FULL Glazed (IN FRONT) partition provided with 12mm thick glass (itched) and Aluminium Jali partition on sides and back till 7'-0" lvl from ground level) to provided as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. . The exposed edges shall be finished in mirror polish.				

BOQ FOR INTERIOR FURNISHING WORKS OF GHUNGOOR BRANCH AT SILCHAR, ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	viii) Boxing (12"x 10") made with 18mm thick plywood as per drawing with horizontal (Boxing) extension at the top all finished with approved shade of laminate shall be provided for the counter				
	ix) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.				
	x) Footrest made with T.W. member of size 4"x1 1/2 " finished with french polish.				
	xi) Drawer units as per drawing shall be provided and each drawer should have vertical partitions for keeping the currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.				
	xii) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.				
	xiii) Side & back partition(excluding Door) with Alu Jaali/ 12 mm thk Glass or as directed by the Architect and as per design. The partition shall be solid with both side laminate till 4'-0" lvl from ground floor and then finished with Aluminium Jaali/ 12 MM thk Glass@3'-00"(&'-0" FROM GR LVL) AND THEN finished till ceiling level with solid partition with both side laminate again				
	<b>The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the Vertical drop and also in the 12"x10" boxing as shown in the drawing. Necessary beadings with matching melamine polish for fixing the glass are to be provided as per drawing/ as directed.</b>				
	<b>The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.</b>				
iii	<b>SINGLE WINDOW COUNTER</b>	NOS			
	Providing and fixing <b>Single Window Counter (SW)</b> of size 4'-6" X 6'-6" complete with 3" solid partitions on side and back as per design in front including rear doors of the design as approved by the bank. The counter should have an working top made up of 25 mm thk plywood and finished with approved shade of Laminate at an height of 2'-6" from floor level. The counter should have Laminated finish ledge as customer top 12" wide at places at specified in the detailed drawing of the Single Window Counter. The Counter should have necessary drawer 3-set as indicated in the drawing on telescopic channels, controlled with a central locking system. A Redy made key board tray of approved make should be provided. The Single window should include side cadenza with two drawers and shutters as per the drawing. The rates shall be inclusive of all partition , glass and all as mentioned above all complete in all respect. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
iv	<b>PASSING OFFICER CUBICLE</b>	NOS			
	Providing and fixing <b>Passing officer Cubicle</b> , placed between the side partition of Single Window on one side and Cash Counter on the other sides, in Laminate finish of size (4'-6" - 5'-0") X 6'-6" complete with 3" solid partitions on back and in front as per design excluding rear doors. The counter should have Working top at an height of 2'-6" from the finished floor level and a 12" wide laminated finish ledge as customer top should be provided at an height of 3'-6" from FFL. The ledge provided for customer top should have rounder edges on all sides. The shades of laminates and also the design of itching is as specified in the drawing or as directed by the architect on site. The counter should have a set of three drawer with central locking arrangement. The lock should be of Godrej Make. A metal Key Board tray should also be provided in the counter. The Cubicle should include side cadenza with two drawers and shutters as per the drawing. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
v	<b>Manager's Table of size 6'-0"(L) x 2'-6"(W) x 2'-6"(H) with 8mm thk clear Glass ( all edges mirror polished) on Top</b>	NOS	1.00		
	Providing and making Manager Table in laminate finish of size 6'-0" X 2'-6". It shall consist of 3/4" thk plywood top as per design( double edge on outer edge with 1 1/2" THK HALF ROUND MOULDING ON THE EDGES) supported on 3/4" thk plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate. The table should have metal keyboard tray, wire manager, and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
vi	<b>Officer's Table of size 5'-0"(L) x 2'-6"(W) x 2'-6"(H)</b>	NOS	1.00		

<b>BOQ FOR INTERIOR FURNISHING WORKS OF GHUNGOOR BRANCH AT SILCHAR, ASSAM</b>					
<b>SL</b>	<b>DESCRIPTION OF WORKS</b>	<b>UNIT</b>	<b>QNTY</b>	<b>RATE</b>	<b>AMOUNT</b>
	Providing and making Officer's Table in laminate finish of size 5'-0" X 2'-6". It shall consist of 3/4" thk plywood top as per design( double edge on outer edge with 1 1/2" THK HALF ROUND MOULDING ON THE EDGES) supported on 3/4" thk plywood verticals supported on wooden base(as designed by the architect) suitable wooden moulding as per architect's design with mellamine polish shall be provided to the edge of the top. All external surfaces to be finished with 1.0 mm thk laminate.The table should have metal keyboard tray,wire manager,and a foot rest as per drawing. A set of three drawers should be provided and fixed with the table as per design. The drawer should have a central lock arrangement. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
<b>vii</b>	<b>MAY I HELP YOU- TABLE</b>	NOS	1.00		
	Providing and laying a Plain Table for Security Gurd with a Pencil Drawers for over all size of top as mentioned above. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make. The front apron of the table should be fixed with 3'-0" x 1'-6" acrylic sheet on 4 nos S.S studs with coloured sticker of bank's logo as per design.				
<b>viii</b>	<b>Side Cadenza of size 1'-6"(W) x 3'-6"(L) x 2'-6" (H) (FOR MANAGER)</b>	NOS	1.00		
	Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit ( C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
<b>ix</b>	<b>Side Cadenza of size 1'-6"(W) x 3'-0"(L) x 2'-6" (H) (FOR OFFICERS)</b>	NOS	1.00		
	Providing and fixing 2'-6" height laminate finish Manager, officers , etc. Side storage unit ( C - 8) as per drawing. Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
<b>x</b>	<b>LOW HT RUNNING STORAGE(1'-6"DX2'-6"HT) (BACK CADENZA)</b>	SFT	142.00		
	Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make . Note- The Height of the running stoarge should be 2'-6" and should comprise of a 6" high drawe and shutters below. No shelves should be provided inside the shutters				
<b>xi</b>	<b>OVER HEAD STORAGE</b>	SFT	44.00		

<b>BOQ FOR INTERIOR FURNISHING WORKS OF GHUNGOOR BRANCH AT SILCHAR, ASSAM</b>					
<b>SL</b>	<b>DESCRIPTION OF WORKS</b>	<b>UNIT</b>	<b>QNTY</b>	<b>RATE</b>	<b>AMOUNT</b>
	Providing and fixing over-head storages which consists of 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & t.w lipping matching with approved laminate on all the edges. They shall consist of 3/4" thk plywood top , sides and bottom and 1/4" thk marine plywood back. A 3/4" thk ply wood palmet shall be provided below the storage to house the tube light. All the external surfaces shall be finished with 1.0mm thk laminate of approved shade. Divisions of shuttershall be made equally in accordance to the length of the storage. All internal surfaces shall be finished with french polish including the shutter. Rate shall be inclusive of all necessary hardware fittings of approved make like- hinges, locks, towerbolts, handles etc.Note- the pelmet for tubelights will not be considered as seperate item on in the measurement				
<b>xii</b>	<b>FULL HT. STORAGE</b>	SFT	422.00		
	Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk.comm. ply top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type higes of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages ( as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. 18mm thk. Comm. Ply shelves removable type supported on side steam beach wood battens on both sides at 16" interval ( approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.				
<b>B</b>	<b>PANELLING</b>				
<b>1</b>	<b>PANELLING ON WALLS/ COLUMNS IN LAMINATE FINISH</b>				
	Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consists of aluminium sections 50mm x 38mm(wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 18/19mm thk commercial grade plywood and finished with 1.0mm thk laminate or left naked as per the direction of the EIC/architect. Wooden moulding, lipping etc as directed by the architect shall be provided wherever required.				
<b>a</b>	<b>In 12 mm plywood finish in laminate for sealing of ventillator &amp; window near cash counter</b>	SFT	46		
<b>b</b>	<b>In Laminate Finish over Ply</b>	SFT	688		
<b>2</b>	<b>PANNELLING WITH LECQUERED GLASS OF APPROVED SHADE</b>	SFT	52.00		
	Providing and fixing of paneling with or without frame so as to receive a plain and even surface in exact plumb line , covered with 9mm thick commerial ply and finished with 8/9mm thick <b>TEMPERED LECQUERED GLASS</b> of approved shade and make as per the design . Rate shall be inclusive of 100 mm high skirting of siver metal laminate as and where required and as per the direction of the Consultant Architect/ Engineer.				
<b>C</b>	<b>PARTITIONS</b>				
	<b>(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca/ rcc ceiling/slab but the area of partition payable will be below the false ceiling only).</b>				
<b>1</b>	<b>Full Height Solid Partition B/S Laminate</b>	SFT	210.00		
	Providing & fixing in position solid Full Height Partition in frame work in 2'x 2' grid (horizontally and vertically) comprising of 2"x 2" T.W. Section with 8 mm thick plywood on both sides finished with 1 mm thick laminates of approved make and colour as shown in drawing. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
<b>2</b>	<b>FULL HEIGHT PARTLY GLAZED PARTITION</b>	SFT	84.00		
	Providing and fixing full ht. partly glazed partition at places as mentioned in the drawing and as directed by the Architect/ EIC. The partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures.The framing shall be fixed with 8/9 mm thk. commercial grade plywood on both side and finished with 1mm Laminate of approved shade and make . Approved make 5/6 mm thick itched Float glass or clear glass fixed with frosted film as per design, to be fixed at an height as mentioned in the drawing or as directed by the architect . The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine Polish.				
<b>5</b>	<b>FULLY GLAZED PARTITION WITH TOUGHENED GLASS(In Manager cabin Front , Self Service Area &amp; Front Glazing)</b>	SFT	176.00		

<b>BOQ FOR INTERIOR FURNISHING WORKS OF GHUNGOOR BRANCH AT SILCHAR, ASSAM</b>					
<b>SL</b>	<b>DESCRIPTION OF WORKS</b>	<b>UNIT</b>	<b>QNTY</b>	<b>RATE</b>	<b>AMOUNT</b>
	Providing and fixing of Fixed Glass partition with 10mm thick toughened glass using Standard fittings of above - mentioned makes at the top and grouting at the bottom with <b>U - Shaped Aluminium rails</b> and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealant wherever required. The top fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling. Rate shall be inclusive of frosted film and bank logo to be fixed over the glass surface as per design and as directed by the architect				
<b>6</b>	<b>Semi height Semi Glazed/ Solid Partition</b>	SFT	84.00		
	Providing and fixing in position Semi Height Semi Glazed/ solid Partition work as shown in the drawing in frame work at 2' x 2' grid (horizontally and vertically) with 6mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass with etching as per design and 2"x 2" T.W. member for glass sides to take 8 mm thick glass with etching and frosting. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.				
<b>7</b>	<b>FULL HEIGHT SOLID PARTITION FINISHED WITH ONE SIDE LAMINATE OVER PLY AND OTHER SIDE WITH A.C BOARD FINISHED WITH POP &amp; PAINT INCLUDING DOOR (Having Fire Rating of 3Hours for UPS Room)</b>	SFT			
	Providing & fixing in position Partition in Aluminium frame work in 2' x 2' grid (horizontally and vertically) comprising of 50mm x 50mm x 1.8mm thk Aluminium Section covered with with 8/10 mm thick Aesbestos Sheet and finished with POP and paint on one side and the other sides to be finished with 8/9mm thk Plywood and finished with approved shade of laminate. It shall also consist of a Flush door of required size and fixed with aesbestos Sheet on one side and laminate on other sides with the same specifications as mentioned in the above line. Rates shall be inclusive of all hardware fittings and fixtures such as - hinges, handles, locks, door closer, door stopper etc. all complete				
<b>D</b>	<b>DOORS</b>				
<b>a</b>	<b>SOLID DOORS- IN LAMINATE FINISH (BOTH SIDE LAMINATE)</b>				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall consist of 3 nos 2" x1" C.P teak wood styles and 3 nos 3" x 1" C.P teak wood bottom, middle and top rails. The wooden framing will be covered with 1/4" thk plywood on both sides. A door frame of size 3"x1 1/2" t.w section finished with mellamine polish shall be provided. Rates shall be inclusive of approved locking system (Godrejmake- Ultra mortise dead lock), door stopper, a pair of handles, tower bolts etc and misc. hardware items of approved make				
<b>i</b>	2'-6"-0"X7'-0"-IN LAMINATE FINISH (WITH 1 1/2X4" WOODEN FRAME)	NOS	5.00		
<b>b</b>	<b>PARTLY GLAZED DOOR</b>				
	Specification same as above except for 8mm thk Modi Guard clear float glass shall be provided at 4'-0" from floor lvl The door shall be finished in 1.0 mm thk laminate on both sides				
<b>I</b>	<b>PARTLY GLAZED DOORS / DOORS WITH VISION PANEL</b>	NOS	1.00		
<b>II</b>	<b>AT ENTRANCE TO SINGLE WINDOW COUNTER , PASSING OFFICER &amp; CASH COUNTER PASSAGE</b>	NOS			
<b>III</b>	<b>2'-6" X 6'-0" TELLER COUNTER &amp; SW COUNTER DOOR WITH NIGHT LATCH</b>	NOS	1.00		
<b>IV</b>	<b>4'-0" high Wicked Door as per design</b>	NOS	2.00		
<b>c</b>	<b>ENTRANCE DOORS - WITH TOUGHENED GLASS (PATCH FITTINGS)- AT ENTRANCE &amp; BM'S CABIN</b>	SFT	46.00		
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings (Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items. (ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)				
<b>E</b>	<b>FALSE CEILING AND POP WORKS</b>				
<b>1</b>	<b>GYPSUM BOARD CEILING</b>	SFT	1200.00		

BOQ FOR INTERIOR FURNISHING WORKS OF GHUNGOOR BRANCH AT SILCHAR, ASSAM					
SL	DESCRIPTION OF WORKS	UNIT	QNTY	RATE	AMOUNT
	Providing and fixing 1/2" thk Gypsum India Board false ceiling at levels as shown in the drg. From the FFL. Rate shall be inclusive of all Gypsum India Components contained G.I perimeter channels of size 0.55 thk having one flange of 20mm and another flange of 30mm and a web of 27mm along the perimeter of the ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws at 610mm centres. The suspending G.I intermediate channels of size 45mm, 0.9mm thk with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angles of width 25mm x 10mm x 0.55mm thk fixed to soffit with G.I cleat and steel expansion fastner at every 610mm c/c. Ceiling sections of 0.55mm thk having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in directions perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment. The board are to be jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edge of the boards with jointing compound & jointing paper tape. Rate shall be inclusive of any vertical ceiling part, cutouts for spot and tube lights, a.c grills, fire and security system cutouts. All Sections should adhere to the manufacturer's guidelines .				
2	<b>MODULAR FALSE CEILING- ARMSTRONG make</b>	SFT	560.00		
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm grid sections) false ceiling of size 24" X24" AT LEVELS AS SHOWN IN THE DRG. FROM THE FFL. Rates shall be inclusive of providing the total system with installation etc. The contractor has to maintain all ceiling tiles in good order and replace the defective tiles (at his own cost) before the handing over of the site.				
	<b>Note- Rates shall be inclusive of The drop/band of 6"-12" between the gypsum(at lower level) and Armstrong(at heigher level). No extra can be claimed for the same. Amount will be paid as per the measurement of the horizontal surfaces of Gypsum and Armstrong and nothing will be paid for vertical surface / band/ drop as it is all inclusive. Rate</b>				
<b>F</b>	<b>PAINTING</b>				
1	<b>LUSTRE PAINT WITH POP PUNNING ON GYPSUM FALSE CEILING</b>	SFT	1200.00		
	Providing & applying Luster Paint on walls, columns & ceilings over pop punning. The rate shall include scrapping, levelling & preparing the surface. with pop , jointing compound and Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.				
2	<b>DISTEMPER PAINTS FOR WALLS (TOILETS, STORE, UPS AND STRONG ROOM)</b>	SFT	4600.00		
	Providing and applying Distemper paint on walls , columns & ceilings. The rates shall include scrapping, levelling & preparing the surface. Primer coat +(MINIMUM) 3 coats to get evenly spread quality finish(roller Finish) of approved make, quality and finish shall be provided.Note- Rates shall also include - filling up the cracks in the wall & ceilings, making good surface .				
3	<b>WALL PUTTY/ POP PUNNING (ON BANKING HALL WALLS AND GYPSUM CEILING ONLY)</b>	SFT	2200		
	Providing and applying POP Punning on walls and columns (average 6mm thk). The rate shall include scrapping, levelling and preparing the surface. The rate shall include scrapping, levelling and preparing the surface. The rate shall be inclusive of all types of grooves above the skirting, around the windows and door frames. If the average thickness is found to be 4mm or less than POP will be considered as a putti finish and the rate shall be 50% of the quoted rate				
	<b>If Wall Putty is provided on RCC ceiling/ Slab and other area than banking hall, then the same shall not be payable</b>				
4	<b>PLASTIC EMULSION PAINT (ON BANKING HALL WALLS ONLY)</b>	SFT	1000		
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided.				
<b>G</b>	<b>MISC. ITEMS</b>				
1	<b>VERTICAL BLINDS</b>	SFT	142.00		
	Supplying and Fixing VERTICAL BLINDS Vista/Mac/Parytex make. Blinds made using 100% polyester with acrylic polymer coating, of the shade and colour as approved by the Arcitect/ Bank ffficial( <b>only for external windows. In case of front facia necessary approval need to be obtained</b> )				
2	<b>PIN UP BOARD IN BRANCH</b>	SFT	24.00		
	Providing and fixing Pin-Up board of sizes as mentioned in the drawing in 1/2" thk soft board of good density to be mounted over 12mm thk ply and fixed to partition/ walls or at places as directed by the architect. The soft board shall be covered with valver cloth of approved shade and make (BASIC RATE RS. 200 /R.MTS.) .				
3	<b>SHUTTER BOXING</b>	SFT	80.00		
	Providing and Fixing Shutter Boxing with 19mm thk Marine Ply and Finished with Approved Shade of laminate> The boxing of shutter should be made opennable type for periodic maintainance. <b>Note the mode of measurement would be the multiplication of the length and the height of the boxing</b>				
4	<b>NOTICE BOARD</b>	SFT	12.00		

<b>BOQ FOR INTERIOR FURNISHING WORKS OF GHUNGOOR BRANCH AT SILCHAR, ASSAM</b>					
<b>SL</b>	<b>DESCRIPTION OF WORKS</b>	<b>UNIT</b>	<b>QNTY</b>	<b>RATE</b>	<b>AMOUNT</b>
	Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
<b>5</b>	<b>SIDE/CORNER/CENTRE TABLE</b>				
	Providing and making corner/ side/ centre table of below mentioned sizes as per drawing. Table top shall consist of 12mm thk glass with chamfered edge with approved quality of itching. The base shall be made up of CP TEAK WOOD frame/ 3/4" plywood or as directed by the architect. All exposed faces shall be finished with natural polish(if wood frames are used) or with 1.0mm thk laminate of approved shade for ply. All inner surfaces should be finished with natural french polish				
<b>a</b>	<b>CORNER TABLE(1'-6" X 1'-6 X 1'-6HT)</b>	NOS	3.00		
<b>b</b>	<b>CENTRE TABLE(1'-6" X 2'-6 X 1'-6HT)</b>	NOS	1.00		
<b>6</b>	<b>WRITING LEDGE</b>	RFT	4.00		
	Providing and fixing Wall Mounted Writing Ledge Of Size 4'-0" x 1'-3" x 1"(H), made out of 19mm thk Plywood of approved make and finished with 1mm Thk approved shade of laminate. <b>This ledge should have 4 nos of Pockets made along 4' length with the Supporting wall as base with 3" clear space to house withdraws/deposit etc slips. All inner surfaces of the Ledge should also be laminated.</b> A 12mm thk Clear Glass, Mirror polished on all sides of size 4'-0" x 1'-3" shall be fixed with 4 nos 1-1/2" dia and 4" High S. S Studs should be fixed on the Top portion of the ledge.				
<b>7</b>	<b>COMPLAIN BOX &amp; SUGGESTION BOX</b>	NOS	1.00		
	Supplying and erecting free-standing complain box of overall size 300 mm long x 200 mm deep x 450 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete with hardware fittings and fixtures of approved make and quality.Top and all exposed surfaces of block board are to be finished with 1.00 mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.				
<b>8</b>	<b>CHEQUE DROP BOX</b>	NOS	1.00		
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.P teak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.Rate to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved designand quality.				
<b>9</b>	<b>10MM GLASS SHELVES- 250-300MM WIDE</b>	RFT	18		
	Providing and fixing 10mm thk Clear Glass Shelves, 250-300MM WIDE in mirror polished edges as per design. The Glass selves should be fixed with the help of Stainless Steel F Type Glass Shelf Bracket Square 12 Inches, with screws to walls / partitions/ pannelling, at an interval of 24-30" as per design and as directed by the achitect				
<b>10</b>	<b>DRY PLANTER BOX WITH POT &amp; PLANTS (WITH FLOWER POT)</b>	NOS	4		
	Providing and fixing dry Planters Boxes of avg. size 350mm x 350mm x 300- 450mm(H); The Planter Box shall be made out of 2 nos 18/19 mm thk. sandwiched WPC Board on sides and bottom and finished with 1.0 mm thk laminate of approved shade in approved style and pattern. All exposed side edges of shall be covered with WPC beading finished with similar finish. Rates shall be inclusive of 12-14" dia PVC Flower pot with indoor quality natural plants as per architect's / Bank Officials choice.				
<b>11</b>	<b>COLOURED ACRYLIC SHEET LOGO FO THE BANK, BACK LIT (600 X 600)</b>	NOS	1.00		
	Supplying , fabricating and installation of Canara Bank's Logo of 2 Nos of Triangle (Blue and Yellow Colour) made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings . This Coloured Acrylic sheet box logo should be fixed with strip light fitted from inside , as per the direction of the architect.				
	<b>TOTAL OF BRANCH FURNISHING WORKS (A)</b>				