

SCHEDULE OF QUANTITIES FOR PROPOSED BRANCH & ATM FOR CANARA BANK AT CHOUTUPPAL

INTERIOR WORK					
S.No	Description	Unit	Qty	Rate	Amount
1	GYPSON BOARD FALSE CEILING				
	Providing & fixing as per design with suspended false ceiling consisting of 12mm.thk.Gyp. board suspended on G.I. framework to consists of G.I. perimeter channels 0.55 mm thk. x 20mm .x 30mm. along perimeter of false ceiling; screw fixed to wall/partition with nylon sleeves & screws @ 600mm. dc. Suspending GI. Interme diate channels of size 0.9mm thk.x45mmx15mm. from the soffit at max. distance 1220mm. dc with ceiling angle 0.55mm. thk.x2n5mm.x10mm. Fixed to soffit using proprietary supplied GI. Cleats & steel expansion fasteners. Ceiling section 0.55mm thk. xweb size 51.5mm & flanges 26mm. Each & 10.5 mm. lips fixed perpendicular to intermediate channel at 457mm. c/c Gyp board is screw fixed to ceiling section with 25mm. drywall screws at 230mm. c/c. boards to be finished with proprietary supplied jointing tape & jointing compound & sand papered to achieve a smooth finish etc.complete or as directed by the Architec/Bank. Gyp ceiling where necessary as normal specification Rate should include all types of cut-outs, grooves ,moulding & plain troughs for tube lights / Down Lighter as directed by the designer. Note: Where RCC Slab is old and concrete is weal, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be carrid out before fixing Gypsum board fixing.Rate shall be inclusive of epoxy chemical and fixing of suspenders with chemical no extra will be given for vertical and borders.Rate will be include with 2 to 3 coats of putty ,paper, till smooth finish with 2 to 3 coats as per the site requirment and site conditions.	SM	60		
2	False ceiling - Grid				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x15/16 mm Dune Supreme RH 99 Prima tile with Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary cutouts for diffusers, light fittings,etc taping and finishing to proper line & level, including making grooves and trap doors in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint complete in all respects.(Note:- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.) measurement L X soffit of false ceiling	SM	75		
3	Internal wall paneling / column cladding				
	Providing & fixing wooden paneling of size 2"X 1" fixed at 2' center to center, covered with 9mm commercial ply confirming to IS 303. The exterior surface to be finished with 1mm thick laminate as specified in drawing.	SM	150		
4	Main Entrance Door				
	Providing and fixing fully glazed door made out of 100mmx75mm teak wood for the frame work and the door shutter frame of size 1 1/2" x 5". including finishing and polishing the wooden surfaces with sealer-melamine matt finish tinted to approved colour and shade. The filler shall be of 12 mm thk. Clear toughened glass with suitable beading given in the diagram. The item includes providing heavy duty floor spring (F32 of E-verite or equivalent.), tower bolts locks, handle, door stopper, latch etc as directed by Engineer - in - charge. The item also includes providing granite sill / jam / soffit with proper nosing.	SM	6		
5	Fixed glazing over TW Frame at Front.				
	Providing & Fixing clear glazing in front with teak wood sections of size 5" x 1 1/2" for top & bottom with 12 mm thk. Clear toughened glass to be placed with beading as per drawing. All wood work will be polished with melamine polish etc., complete for the finished item of work.	SM	10		

6	Solid partition with / without door				
	Providing & Fixing Full height partition with 2" x 2" saal wood section with both sides 9mm ply finished with 1mm thick laminate approved of shade & brand. All horizontal & vertical wooden sections are to be placed at 2'-0" c/c. Sections to be fixed to the RCC roof slab above for proper anchoring, including finishing and polishing the wooden surfaces with sealer-melamine matt finish tinted to approved colour and shade. 8mm glass with Frosted film etching with beading including finishing and polishing the wooden surfaces with sealer-melamine matt finish tinted to approved colour and shade. The rate includes providing 35 mm thick flush door with necessary lipping patti polished. Rate includes all necessary hardware (i.e. ball bearing hinges of approved make, door closer, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have approx. 75x12 mm matching wood Patti with groove in between or as directed by the bank / architect. All provisions to be made for all electrical, networking, telephone etc. boxes into partition framework at required heights/levels with necessary additional supports as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the bank / Architect etc. complete. Measurement (L X soffit of False ceiling height)	SM	35		
7	Half height glass partition				
	Providing and fixing low height partition up to 5' or 7' height as required, made out of 50 mm*50mm 18mm Gauge aluminum frames at 2' C/C vertically & horizontally with 6mm thick commercial plywood on both sides upto 3' height and above portion with 10mm toughened glass as per design or as directed by the bank / architect Finished with 1.00 thick laminate of approved shade and design. Measurement (L X End height of the partition not the height of the glass at the center)	SM	15		
8	Semi glazed partition with / without door				
	Providing & fixing 3" thick partly glazed partition with 10mm thick clear float glass for made up of 18 gauge 50x50 mm saal wood section framework at 600 mm c/c both ways (or as directed by the Architect); 12 mm commercial plywood & 1 mm laminate from both sides. Partition should be finished with specified finish as per design. The rate includes providing 35 mm thick flush door finished with 1mm laminate of approved make/shade on both sides with necessary lipping patti polished. Rate includes all necessary hardware (i.e. ball bearing hinges of approved make, door closure, Cylindrical Lock with key, Door stopper etc) Exposed edges of the partition should have 75x12 mm matching wood Patti with groove in between. All provisions to be made for all electrical, networking, telephone etc. boxes onto partition framework at required heights/levels with necessary additional supports &/or scaffolding as required. The rate includes all necessary hardware & cleaning of partition to the satisfaction of the Architect etc. complete Measurement (L X False ceiling height(soffit))	SM	25		
9	Tables				
	Providing & fixing counters / tables of 2'5" height,4'6", 5',6' length (or as per drawing / site) and 2' 6 " width, Counter / tables to be made up of 18mm. thk. Plywood framework with 10mm. thk. Clear glass on top. and open space for C.P.U. & small drawer above it on other side of Key Board drawer. The counter should have necessary holes of required sizes for wire managers. The counter should have necessary passages & ledges for data cables, electrical cables and telephone lines. The counter should be finished with 1.0mm. Thk. Laminate of approved colour & shade from external side and polish from inside. All the exposed edges of plywood including lower edges should have lipping patti. Lipping patti should be finished in polish. The cost should include necessary hardware Moulding .handles & Godrej make drawer locks with common key for cash drawers, footrest etc. complete as per design. Measurement (The front face of the table shall be measured.)	RM	15		

10	Cash counter				
	Providing & fixing cashier's counter of 5' length and 2' 6 " width with 12mm thick toughened from 3' height in front elevation fixed with necessary brass studs. Counter to be made up of 18mm. thk. Plywood framework and open space for C.P.U. & small drawer above it on other side of Key Board drawer. The counter should have necessary holes of required sizes for wire managers. The toughened glass above service counter to have 5 inch dia hole. The service top of counter should have 19 mm marble/granite in a stepped pattern of approved shade chamfered on edges. The counter should have necessary passages & ledges for data cables, electrical cables and telephone lines. The counter should be finished with 1.0mm. Thk. Laminate of approved color & shade from external side and enamel paint from inside. All the exposed edges of plywood including lower edges should have lipping patti. Lipping patti should be finished in polish. The cost should include necessary hardware Moulding .handles & Godrej make drawer locks with common key for cash drawers, footrest etc. complete as per design. Drawers to be made of 12 mm thick comm. plywood and finished with laminate on front and enamel painted inside. Measurement (The front face of the table shall be measured.)	RM	2		
11	Storages				
	Providing & fixing side unit made up of 18mm. thk. plywood framework & 6mm. thk. plywood as backing. Side unit should have 2 no. of drawers above & openable or slidding shutters below or as per design. Drawers should be made up of 18 thk. Plywood fascia, 12 thk. Plywood sides & 6 thk. Plywood bottom. Drawers should be mounted on heavy duty drawer sliders. Side unit should be finished with 1.0 mm. thk. Laminate of approved shade & colour on external surface & oil paint to non laminated surface. All exposed edges of 18 thk. & 12 thk. Plywood should have lipping patti All lipping patti's should be finished with paint/French polish on it. The cost should include necessary hardware, handles, Godrej make locks with common handles, Godrej make locks with common key for set of drawers etc. complete as per design. Drawers to be made of 12 mm thick comm. plywood and finished with laminate on front and enamel painted inside. Measurement (L X Height of the storage)	SM	40		
12	Front glass on OT/CT counters				
	Providing and fixing 12mm thick clear float glass on counters with SS patch fittings, hardware etc complete for the finished item of work. Measurement (L X height at the end portion of the partition not at the center)	SM	5		
13	WG / Doors				
	Supplying and fixing in position overall 30 mm thick solid core hot pressed phenol formaldehyde bonded flush door, with 1mm thk. Laminate on both sides including finishing and polishing the wooden surfaces with sealer-melamine matt finish tinted to approved colour and shade. Door will have provision of necessary hardware like lock, hinges, tower bolts, handles, door stopper etc. of approved make, complete for the finished item of work. Measurement (L X H)	SM	1		
14	Display board				
	Providing and fixing 12mm thk Soft Board, display covered with felt and teak wood border of size 6'-0" x 3'-0".The wooden border is 3"x1 1/4" All wood work will be polished with melamine polish etc., complete for the finished item of work. Measurement (L X H)	SM	2		
15	Rubber matt flooring for UPS				
	Supply & laying of 5mm thick rubber matt flooring of approved make & colour with solution & all required material, labour, transport complete for the finished item of work. Measurement (L X B)	SM	6		
16	Suggestion Box / Cheque drop box				

	Providing & fixing box made up 18 mm. thk. plywood framework, 6/12 mm. thk. plywood back as required as per design. Good quality blackboard shutters should be fixed on brass hinges should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminated surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks etc. complete as per design.	NO	2		
17	Writing Desk				
	Providing & fixing writing desk made up of 18 thk. Double plywood supports as shown in the drawing. Plywood supports shall be finished in laminate on it. from both sides & to edges with groove (kani) at corners. The frame shall have 6mm thk. Plywood back & it should be finished with laminate. The desk shall have 12mm. thk. Clear glass with plain diamond edge polish & with round corners on front side. 12 thk. Glass shall be fitted with D-brackets on partition & rubber vacuums on plywood supports. The desk shall have 8mm. thk. Clear glass with plain diamond edge polish from all four sides. This glass should be fitted on D-brackets. The writing desk will be of hanging type as shown in the drawing. The rate should be fitted on D-brackets. The writing desk will be of hanging type as shown in the drawing.	NO	1		
18	VERTICAL BLINDS				
	Providing and fixing vertical blinds of 100mm lenth of vista Lavour of approved shade and pattern. The rate shall include necessary scoch gurd treatment on both sides. The overlapping should be uniform and adequate.Necessary oparative arrangements,frames to be provided. The work to be completed as per specification and approval of the architect.MAKE(vista) at banking hall and cabins windows.	SM	10		
19	ALLUMINIUM GRILL with white/ivory powder coating for Cash cabin top	NO	1.00		
20	Providing and fixing cupboard with shutters for covering electrical panel board, etc., with 18mm BWR ply with 1mm thick shell finish laminate of approved shade and make on outside including painting of inside with primer and two coats of synthetic enamel paint, and providing teak wood beading to all exposed edges, inside of the entire cupboard is to be fixed with the bison board (Fire Proof) to the existing ply wood including all accessories hinges, handles, ballcatches, etc., complete.	SM	4		
21	Dining Platform				
	Providing & Fixing Dining Platform 2'-0" wide made with 18mm ply finished with 1mm thick laminate on all surfaces including verticals. The platform should be supported on 18mm tk ply verticals placed at 2'0" intervals. All the edges of the plywood are covered with 12mm tk. steam beech beeding duly painted.	SM	3.00		
22	Dressing Unit For Locker Room	NO	3.00		
23	Flush Door				
	Supply and fixing of Commercial Flush door single leaf shutters with teak wood frame of size 100x65mm and shutter made of 30mm thick commercial flush door finished with 1mm thk. Laminate on both sides including finishing and painting the wooden surfaces of approved colour and shade as per drawing. Door will have provision of necessary hardware like handles, aldrops, door lock etc., complete for the finished item of work.	SM	15		

24	SHUTTER BOXING - ACP PANELLING				
	OUT OF SHUTTER BOX Supply installation and fixing of ACP cladding with side pillars and front at the entrance to be cladded with standard approved bank colour and acp to be done one aluminum frames to be made as per the standard specifications and design given by the Architect.	SM	25		
				Total	0
	DISCOUNT				
	TOTAL AFTER DISCOUNT				
Amount in Rupees:- Rs.					
	Sign & Seal of the Contractor : -				
	Name & Address of the contractor : -				
	Date:				