

**Premises & Estate Section, Circle Office Guwahati, First Floor, DEE BEE GRANDE,**  
**6 MILE, PANJA BARI ROAD, GUWAHATI, PIN - 781022.**

**Phone : (91) (0361) 2334020; Email : pecoquw@canarabank.com; Website: www.canarabank.com**

**BOQ FOR AIR CONDITIONING WORKS AT CANARA BANK, JORHAT TARAZAN BRANCH (6681) OF REGIONAL OFFICE DIBRUGARH**

S. NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
<b>PART 'A'-SUPPLY</b>					
<b>1</b>	Supply of Ceiling mounted "Cassette" Air Conditioner by cutting false ceiling & comprising of Indoor & Outdoor units. The Indoor unit comprising multi-row DX coiling coil, Driver, expansion valve/devise, air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotary/Scroll compressor, condenser coil & fan, Cordless remote controller etc. including Refrigerant gas charging, water drain system ect. Acceptable makes AC: Daikin/Toshiba/O General/Carrier/Blue Star/Voltas/Hitachi				
<b>a.</b>	2 Ton Cassette A.C. as per specifications given in item no 1 above .	No.	2.00		
<b>2</b>	Supply of Hi Wall mounted Split A.C comprising Indoor & Out-door units. Indoor unit comprising Multi Row DX cooling coil, expansion valve, driver, motor driven airblower with metallic frame etc. Out-door unit will have rotary/scroll compressor, condenser coil, & fan, Cordless remote control unit etc. including refrigerant gas charging. Acceptable makes AC: Daikin/Toshiba/O General/ Carrier/Blue Star/Voltas/Hitachi				
<b>a.</b>	1.5 Ton Ton Hi-Wall Split A.C. as per specifications given in item no 2 above	No.	0.00		
<b>b.</b>	1.0 Ton Ton Hi-Wall Split A.C. as per specifications given in item no 2 above .	No.	2.00		
<b>PART A Total Amount Exclusive of GST</b>					
<b>GST @</b>					
<b>PART A Sub Total Amount Inclusive of GST</b>					
<b>PART 'B'--INSTALLATION</b>					
<b>1</b>	Supply of wall mounted hi lo cut off stabiliser with TDR, voltage range 140-280V,complete in all respects. Stabilizer: Servel/ V Gaurd/ Marc/ Stambh/Inmag/Microtek/Servokon, of KVA as mentioned below				
<b>a.</b>	4 KVA VOLTAGE STABILIZER	No.	2.00		
<b>b.</b>	5 KVA VOLTAGE STABILIZER.	No.	2.00		
<b>2</b>	Installation, Testing and commissioning of above mentioned cassette units with accessories as required along with removing and refitting of false ceiling as and wherever required as per site	No.	2.00		
<b>3</b>	Installation, testing and commissioning of above mentioned hi wall type splits units of 1.5 TR & 1.0 TR capacity with accessories as required as per site.	No	2.00		
<b>4</b>	pipe for 2.0 TR Cassette AC for gas and liquid line with 13 mm thick closed cell Class - O nital rubber insulation between indoor and outdoor units. All piping inside the room shall be properly supported on GI hanger/support	Mtr	20.00		
<b>5</b>	Supply, installation, testing & commissioning of interconnecting copper pipe for 1.5 TR & 1.00 TR Hi wall unit for gas and liquid line with 10 mm thick closed cell Class - O nital rubber insulation between indoor and outdoor units. All piping inside the room shall be properly supported on GI hanger/support as required.	Mtr	20.00		
<b>6(a)</b>	S.I.T.C OF 3 X Copper conductor flexible cable between Indoor & Outdoor Unit through holes made as above for Cassette/Invertor A.C.s	Mtr	20.00		
<b>6(b)</b>	S.I.T.C OF 3 X Copper conductor flexible cable between Indoor & Outdoor Unit through holes made as above for Split/Invertor A.C.s	Mtr	20.00		
<b>7</b>	S.I.T.C of 19/25 mm. PVC conduit pipe to be used as a drain water pipe through holes as made above for for Cassette/Invertor A.C.s	Mtr	20.00		

**Premises & Estate Section, Circle Office Guwahati, First Floor, DEE BEE GRANDE,**  
**6 MILE, PANJA BARI ROAD, GUWAHATI, PIN - 781022.**

**Phone : (91) (0361) 2334020; Email : pecoquw@canarabank.com; Website: www.canarabank.com**

**BOQ FOR AIR CONDITIONING WORKS AT CANARA BANK, JORHAT TARAZAN BRANCH (6681) OF REGIONAL OFFICE DIBRUGARH**

S. NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
8	S.I.T.C of 19/25 mm. PVC conduit pipe to be used as a drain water pipe through holes as made above for Split A.Cs	Mtr	20.00		
<b>8(a)</b>	<b>Outdoor Stand for Split type A.C.</b>				
	Supply and installation of robust MS angle, MS flat fabricated floor/wall mounting stand suitable for outdoor units of hi wall Split ACs, painted with one coat of primer and two coats of synthetic enamel outdoor type paint including its grouting and making good of damages, complete in all respects.	No.	2.00		
<b>8(b)</b>	<b>Outdoor Stand for Cassette type A.C.</b>				
	Supply and installation of robust MS angle, MS flat fabricated floor/wall mounting stand suitable for outdoor units of hi wall Split ACs, painted with one coat of primer and two coats of synthetic enamel outdoor type paint including its grouting and making good of damages, complete in all respects.	No.	2.00		
<b>Part-B Total Amount Exclusive of GST:</b>					
<a href="#">GST@</a>					
<a href="#">PART B Sub Total Amount Inclusive of GST</a>					
<b>TOTAL Installation Cost: (Part A+Part B)-Exclusive of GST</b>					
<b>TOTAL Installation Cost: (Part A+Part B)-Inclusive of GST</b>					