

SN	QUERIES	CLARIFICATIONS
1	FLOORING WORK TO BE DONE ON EXISTING FLOORING OR AFTER REMOVING EXISTING FLOORING	FLOORING WORK TO BE DONE ON AFTER REMOVING EXISTING FLOORING
2	Date of submission of Bids	extended till 15.12.2018 upto 2 pm

14



CIVIL WORKS FOR 'CANDI' BRANCH AT SECTOR 17, CHANDIGARH

S.NO.	EXISTING SPECIFICATION	MODIFIED SPECIFICATIONS
1	FLOORING: VITRIFIED TILE FLOORING (BANKING HALL): Providing and laying Vitrified tiles of size 1200mm x 1200mm to be laid on existing floor /skirting, over 20mm thick cement sand mortar 1:4 including grouting the joints with white cement slurry mixed with matching pigment, complete in all respects including filling the depressions, if any, as per approved pattern.	FLOORING: VITRIFIED TILE FLOORING (BANKING HALL): Providing and laying Vitrified tiles of size 1200mm x 1200mm to be laid by removing existing floor /skirting, over 20mm thick cement sand mortar 1:4 including grouting the joints with white cement slurry mixed with matching pigment, complete in all respects including filling the depressions, if any, as per approved pattern.
	<i>Shade: ALASKA WHITE (Glossy Finish) of SIMPOLO Make</i>	<i>Shade: ALASKA WHITE (Glossy Finish) of SIMPOLO Make</i>
b)	TILE FLOORING (ROBOT ROOM): Providing and laying Vitrified/Ceramic tiles of size 600mm x 600mm to be laid on existing floor /skirting, over 20mm thick cement sand mortar 1:4 including grouting the joints with white cement slurry mixed with matching pigment, complete in all respects including filling the depressions, if any, as per approved pattern.	TILE FLOORING (ROBOT ROOM): Providing and laying Vitrified/Ceramic tiles of size 600mm x 600mm to be laid by removing existing floor /skirting, over 20mm thick cement sand mortar 1:4 including grouting the joints with white cement slurry mixed with matching pigment, complete in all respects including filling the depressions, if any, as per approved pattern.
	<i>Shade: METALLIC SILVER (as per approved sample)</i>	<i>Shade: METALLIC SILVER (as per approved sample)</i>
c)	WOODEN LAMINATED FLOORING: Providing & Laying Laminated wooden flooring with planks of size 1215 x 195 x 8mm (AC-4 Grade) having T&G interlocking system, laid over 4mm thick layer of foam pasted on floor using Fevicol SR505 adhesive. The work shall include providing 4" high skirting & edge profile wherever required as per site, complete in all respects.	WOODEN LAMINATED FLOORING: Providing & Laying Laminated wooden flooring with planks of size 1215 x 195 x 8mm (AC-4 Grade) having T&G interlocking system, laid over 4mm thick layer of foam pasted on floor using Fevicol SR505 adhesive by removing existing floor. The work shall include providing 4" high skirting & edge profile wherever required as per site, complete in all respects.
	<i>Shade: BL-407 (Prime Walnut) of EURO or equivalent of PERGO / ACTION-TESA / ARMSTRONG</i>	<i>Shade: BL-407 (Prime Walnut) of EURO or equivalent of PERGO / ACTION-TESA / ARMSTRONG</i>

17

