

**Replies to Pre-bid queries - Retender for COMPREHENSIVE CIVIL REPAIRS, PAINTING WORKS AND CONSTRUCTION OF TOILET BLOCK,
CANARA BANK BEACH ROAD BRANCH, NO.55, TUTICORIN, TAMILNADU**

Tender Ref No: CB: MDU: P&E: RO: TUT: 03: 2018 dated 07.12.2018

Item No	Query	Reply by the Consultant
9	Plinth Protection item include semi circular pipe, If Include What is the dia of Pipe and item filling of good earth	All sides Drainage lines are already available there, So Semi Circular pipe is not Required. Bitumen filling to junction to required depth (Min: 25mm)
9	Plinth Protection - Including steel (or) Excluding steel	Excluding cost of Reinforcement steel, Steel to be paid separately
10	Arch and Wall crack treatment	Using Weld wire Mesh 50mm x 50mm x 3mm As per Tender Drawing
16 (i)	Interior Wall Painting	Interior Plastic Emulsion Paint to be applied
16 (ii)	Oil bound Distemper	Internal wall to be apply Plastic Emulsion Paint through One coat of Primer and POP then will apply Plastic Emulsion 2 or More Coats, Oil Bound Distemper not Required
16 (iii)	Plaster of Paris (POP)	Wall putty should be applied only on internal wall surface, not required for ceiling
17	Exterior Wall Painting	Acrylic Exterior Emulsion Paint to be applied
21,22,23	Basic rate of Tiles	As per Tender Document Page No:149
24	Door Frame with Polish (or) Without Polish	With Polish
25	Door Shutter with Polish (or) Without Polish	With Polish
32	Puf Sheet wooden section required to make calculation	As per Tender Document
53	Dismantling and Replacement of Rainfall Pipe	Existing Concealed Rainwater Pipe to be removed and the holes to be filled with Brick jelly using Cement Mortar
Note: Permission for using M-Sand		Since the Building is a Heritage Building, We advice to use River sand only. M-Sand not Permitted.

Date: 24.12.2018

Sd/-
Deputy General Manager
Canara bank
P & E Section
Circle Office
Madurai