

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE					
CANARA BANK - GANDHINAGAR					
Sr. No.	Description	Qty.	Unit	Rate	Amount
	CONCRETE WORKS				
1	Providing and Laying plain cement concrete PCC of 1:3:6 of AVERAGE thickness of 40mm over the entire floor area in line and level as indicated by the Architect. Maximum size of Coarse aggregate shall be 10mm	2000	SMT.		
Rate in words:					
	Vitrified Flooring Work				
2	Providing & laying Vitrified tiles of minimum 10mm thickness in flooring laid on a bed of 20 mm thick C.M. 1:4 (1 Cement : 4 Coarse sand). thickness and level has to be maintained according to electrical's consultant requirement so thickness of bottom filling can be more than 20mm to 30mm mm and no extra cost will be provide for the same) and providing 3mm spacer at joint and fied with epoxy filler material in selected colour. (Size - 1 Mt. X 1 Mt.) (A) Light Shade. Basic rate of tiles is 75.00 Rs/ Sqft	1275.00	SMT.		
Rate in words:					
3	Providing & laying ITALIAN FLOORING not less than 15 mm thick in flooring, treads of steps & landing laid on a bed of 20 mm thick C.M. 1:4 (1 Cement : 4 Coarse sand)The thickness and cordination has to be done by civil contractor & thickness and level has to be maintained according to consultant requirement so thickness of bottom filling can be more than 20mm to 30mm and no extra cost will be provide for the same) and providing 3mm spacer at joint and fied with epoxy filler material in selected colour. Light Shade. Basic rate of Italian is 350.00 Rs/ Sqft	685.00	SMT.		
Rate in words:					
4	Wall painting (two coats) with Emulsion paint of approved brand and manufacture on undecorated wall surface to give an even shade including throughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth..	4030.00	SMT.		
Rate in words:					
5	Applying two coats of Birla or Asian acrylic lapi (putty) & two coats of primer approved brand and manufacture on new wall surface to give an even shade including throughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth	2400.00	SMT		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
6	Texture Paint : Texture paint (Insider and outside) :Wall/ Ceiling painting two coats (1 base plus 1 texture) with low VOC as per approved brand in any shades and colour as directed on wall surface to give an even shade including applying coat of putty, Penetrating primer or equivalent and two coats of paint, scaffolding to at any height with all labour and material thoroughly brushing the surface free from mortar droppings and other foreign matter and sand prepared smooth etc. complete. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer/ paint application is to be done with the rollers. Rate shall be including crack filling and levelling as per manufacturers specification. Top coat should have. 1) Low VOC content. 2) Crack Bridging ability upto 2.6 mm. 3) 100% pure acrylic emulsion. 4) Anti-Carbonation concrete protection. 5) Very Low Flame spread. 6) Superior Washability.	62.62	SMT		
Rate in words:					
7	Brick work using common burnt clay building bricks having crushing strength not less than 35 Kg./ sq.cm. in super structure above plinth level (upto floor two level) in cement mortar 1:6 (1 cement : 6 Fine sand) (B) Conventional	6.90	SMT		
Rate in words:					
8	Internal Plaster : Providing 15mm. Thick cement plaster on interior brick / concrete work for plastering comprising of base coat of 12mm thick cement plaster in (i) Cement mortar 1:4 (1 cement :4 coarse sand)in rough finishing and 8mm thick top coat of cement mortar 1:2 (1 cement :2 coarse sand) finished with trowel incl. scaffolding, curing etc complete.	103.77	SMT		
Rate in words:					
9	Providing and applying BRICK BAT BASE chemical water proofing treatment to the terrace, sunk slab including roughing cleaning the surface opening the cracks in "V" grooves pattern and filling the same with water proofing mortar 1:1 (1 Cement :1 sand) including brick bats bedding as directed to have proper slope over a layer of C.M.1:6 (1 Cement : 6 sand) and filling the joints with C.M. 1:1 (1 Cement : 1 sand) including finishing the top surface with 40 mm thick water proof cement concrete 1:2:4 with using 6 mm grit in C.M. 1:3 (1 Cement : 3 sand) and finished with a floating coat of neat cement slurry using chemical water proofing compound as per manufactures specifications (as per indian water proofing co.surat or equivalent) including curing at specified period as directed and imprinting false square of 0.30 x 0.30 mt gradient including making vata of 10 cmx10 cm (quarter round) on inside periphery of the parapet in C.M. 1:1 (1 Cement : 1 sand) etc. Complete as directed by Engineer in charge.	22.37	SMT		

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
Rate in words:					
10	Constructing of wash basin platform (sandwich type) 80cm high resting on Kota stone / granite stone in C.M 1:3 with providing and fixing 25 mm thick rough kota stone at bottom and 25mm thick Granite stone (single piece) top and polished granite stone (single piece) 25mm thick on top with 75mm high machine cut polished Granite round moulded facia patty including polishing, rubbing, edge finishing, chamfering, etc. complete as per drawing and specification without stainless steel sink including necessary cutting for sink & making necessary required hole for fixing P.V.C bend of 25 mm dia. Basic rate of Granite is 150.00 Rs/Sqft	3.00	SMT		
Rate in words:					
11	Providing and laying Ceramic tiles 6 mm thick in flooring treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1-cement : 3- coarse sand) and providing 3mm spacer at joint and fied with epoxy filler material in selected colour (Size - 0.60 Mt. X 0.60 Mt.) (A) Light Shade. Basic rate of tiles is 55.00 Rs./Sqft	22.37	SMT		
Rate in words:					
12	Providing and laying ceramic - glazed tiles 6mm thick in skirting risers of steps and dedo on 10mm thick cement plaster 1:3 (1-cement : 3- coarse sand) and jointed with white cement slurry and providing 3mm spacer at joint and fied with epoxy filler material in selected colour (Size - 0.60 Mt. X 0.30 Mt.) (A) Light Shade. Basic rate of tiles is 60.00 Rs./Sqft	72.64	SMT		
Rate in words:					
13	Providing and fixing Wash Basin vitreous china oval shape under counter (without counter) wash basin size 560mm x 450 mm in white colour. Like JAQUAR CNS-WHT-903 SIZZE OF 425X340X175 MM with single hole for pillar tape with CP or MS brackets painted white including cutting holes and making good the same including (1) Providing and fixing SS waste coupling of 32 mm dia size half theread with 80mm height like JAQUAR ALD - CHR-769L 250 X 190 for wash basin with rubber plug (2) Providing and fixing SS bottle trap with internal partition of 32mm size with 250mm &190mm long wall flange connection pipes and wall flange like jaquar ALD-769 L250X190 of approved quality with necessary fitting for wash basin (3) Providing and fixing SS finish Pillar cock quarter turn like JAQUAR FUS--CHR-29021N with necessary fittings etc. complete (4) Providing and fixing SS finish Angular Stop Cock quarter turn like Jaquar code AQT-CHR-3057P with necessary fittings (5) Providing and fixing SS finish soap dispenser with metallic bottle like Jaquar code-ACN-CHR-1135N etc. complete	3.00	NO		

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE					
CANARA BANK - GANDHINAGAR					
Sr. No.	Description	Qty.	Unit	Rate	Amount
Rate in words:					
14	Providing and fixing approved quality Urinal of white earthen ware flat back type like Hindware flat back large Cat No.60002 of size 590mm x 360 mm x 375 mm including (1) Providing and fixing SS finish waste coupling of 32 mm dia size half thread with 80mm height like jauar - ALD - 709 for wash basin with rubber plug (2) Providing and fixing waste pipe.	3.00	NO		
Rate in words:					
15	Providing and fixing wash down water closet European type WC pan (Wall Hung) like JAQUAR CNS-WHT-961S SIZE OF 365X535X360 MM and P trap distance 23.5 cms with integral P trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 find sand) including providing and fixing of 1) Health Faucet heavy duty with SS braided hose 1.2 mt long pipe Jaquar ald chr 573 with control plate fusion JAQUAR-CHR-292415, Single piece concealed cistern flush tank Jaquar JCs WHT 2400, etc complete	3.00	NO		
Rate in words:					
16	Providing and fixing 600mm x 450mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. sheet or plywood sheet and fixing to wooden pluge with C.P. brass screws and washers.	3.00	NO		
Rate in words:					
17	Providing and fixing cast iron (spun) Nahni trap of the following nominal diameter of self cleansing design with C.I sread down or hinged grating including the cost of cutting and making good the walls and floors 100 mm inlet and 50 mm outlet.	6.00	NO		
Rate in words:					
18	Providing and fixing SS finish bib cocks with wall flange of 15mm dia. Size like Jaquar code FUS-CHR-29041 or equivalent with all necessary fittings etc. complete.	4.00	NO		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE					
CANARA BANK - GANDHINAGAR					
Sr. No.	Description	Qty.	Unit	Rate	Amount
19	Providing and fixing C.P. brass towel rail SS finish towel ring square like Jaquar code-ACN-CHR-1121BN complete or equivalent with C.P. brass brackets fixed to wooden plugs with C.P. brass screws.(B) 600mm x 20mm size.	3.00	NO		
Rate in words:					
20	Providing and fixing toilet paper holder.(A) C.P. Brass TOILET PAPER HOLDER like JAQUAR ACN CHR 1151N or equivalent	3.00	NO		
Rate in words:					
21	Providing & fixing HAND DRYER - LIKE-HDR-SAPM99ACS or equivalent as suggested & directed by EIC.	2.00	NO		
Rate in words:					
22	Providing and fixing SS finish exposed part kit of concealed stop cocks SS finish exposed part kit of concealed stop cocks LIKE KUP-CHR-35083KPM or equivalent with fitting sleeve perating lever & adjustable wall flange & with REGULAR BODY OF CONCEAL STOP COCK SUITABLE	3.00	NO		
Rate in words:					
23	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure polythene pipes of the following outside Dia. Low density, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(F) 75mm	25.00	RMT		
Rate in words:					
24	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure poluthene pipes of the following outside Dia. Low density, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(G)110 mm	20.00	RMT		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
25	Providing. Laying and jointing in true line & level 15 mm dia. U.P.V.C. pipe (Sch 40) for cold water in ground OR on wall including fittings of make PRINCE/SUPREME/ASTRAL/FINOLEX or equivalent as approved by EIC. pipe shall be fixed on the wall with the help of clamp at every two meter C/C or shall be cancelled as directed including necessary fittings etc and fixing the same with adhesive solvent including testing of pipe & joints including cost of all materials etc complete.	25.00	RMT.		
Rate in words:					
26	Providing. Laying and jointing in true line & level 25 mm dia. U.P.V.C. pipe (Sch 40) for cold water in ground OR on wall including fittings of make PRINCE/SUPREME/ASTRAL/FINOLEX or equivalent as approved by EIC. pipe shall be fixed on the wall with the help of clamp at every two meter C/C or shall be cancelled as directed including necessary fittings etc and fixing the same with adhesive solvent including testing of pipe & joints including cost of all materials etc complete.	25.00	RMT.		
Rate in words:					
27	Providing. Laying and jointing in true line & level 32 mm dia. U.P.V.C. pipe (Sch 40) for cold water in ground OR on wall including fittings of make PRINCE/SUPREME/ASTRAL/FINOLEX or equivalent as approved by EIC. pipe shall be fixed on the wall with the help of clamp at every two meter C/C or shall be cancelled as directed including necessary fittings etc and fixing the same with adhesive solvent including testing of pipe & joints including cost of all materials etc complete.	25.00	RMT.		
Rate in words:					
28	Providing. Laying and jointing in true line & level 40 mm dia. U.P.V.C. pipe (Sch 40) for cold water in ground OR on wall including fittings of make PRINCE/SUPREME/ASTRAL/FINOLEX or equivalent as approved by EIC. pipe shall be fixed on the wall with the help of clamp at every two meter C/C or shall be cancelled as directed including necessary fittings etc and fixing the same with adhesive solvent including testing of pipe & joints including cost of all materials etc complete.	15.00	RMT.		
Rate in words:					
29	Providing. Laying and jointing in true line & level 50 mm dia. U.P.V.C. pipe (Sch 40) for cold water in ground OR on wall including fittings of make PRINCE/SUPREME/ASTRAL/FINOLEX or equivalent as approved by EIC. pipe shall be fixed on the wall with the help of clamp at every two meter C/C or shall be cancelled as directed including necessary fittings etc and fixing the same with adhesive solvent including testing of pipe & joints including cost of all materials etc complete.	15.00	RMT.		

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE					
CANARA BANK - GANDHINAGAR					
Sr. No.	Description	Qty.	Unit	Rate	Amount
Rate in words:					
30	Providing and fixing Sink Cock like Jaquar FLR-CHR-5347N or equivalent with regular swinging spout with wall flange with screws, shanks and back nuts. (i) 15mm dia..	3.00	No.		
Rate in words:					
31	Supplying & fixing of T-Line make Toilet Cubicle (of following standard dimension which includes 600mm door size width) made of heat, bacteria, water, chemical, scratch impact and anti bacterial resistant 12mm thick solid compact laminate panels tested by shriram Test House. Finish of the compact laminate should be suede/ *Raw silk, which includes doors, pilasters & intermediate panels finished with approved texture/shade as per the detail drawings & as per IS 2046 (Indian Standard) and as per fire retardant BS-476/97 standard. The product should have Green Guard Certificate. This also includes providing and fixing in position necessary hardware made out of S S 304 & Aluminium powder coated top rail as per manufacturer's specifications & Architects instructions like (1) Door Knob, (2) Gravity Hinges, (3) Thumb turn lockset indicators, (4) Aluminum Top Rail, (5) Coat Hooks, (6) Aluminium UChannels, (7) Adjustable Foot,(8) Aluminium h channel, (9) Aluminium Corner Profile, (10) Noise Deafening Tape (11) S.S Screws & wall plugs etc. All screws will of 304 Grade in stainless steel with satin finish. Top rail is extruded Aluminium will be powder coated or anodized (Grade 6063 Micron Aluminium). All pilasters are supported by S S 304 palm design pedestal footing with non corrosive steel inserts. The base diameter 65mm and neck diameter of 33mm anchored to the floor with grade 304 satin finish stainless steel screws with push fit capping at a clearance height of 150mm. Model is Heat and Bacteria Resistant Polyamide in which aluminium U-Channel will be used for the fixing of intermediate panels to the wall. - Toilet Cubicle with standard dimension of 1998mm Height x 1800mm Width x 1980mm Depth, which includes 600mm door size width). "Dimensions should be as per Drawings"	2.00	No.		
Rate in words:					
32	Providing & Fixing of T Line make Urinal Partition with S S 304 Clamp which has a interconnection between which the Water, Chemical, Heat, Bacteria, Fire, Impact & Scratch Resistant 12 mm T Line Compact Laminate will be fixed and the other side of the clamp will be screwed in the wall from both sides. (size : 900mm height x 400mm depth)	2.00	No.		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
33	<p>FULL HEIGHT PARTLY GLAZED PARTITION UP TO FALSE CEILLING (ONE SIDE LAMINATE FINISH ONE SIDE VENEER FINISH):-Providing & Fixing One side laminated & one side veneer partly glazed partition up to false ceiling ht (thickness of partition is 67 mm) having 06 mm thick MR grade plywood both side on aluminum framing . Aluminum framing size for vertical & horizontal support is 50 mm x 25 mm having guage of 16.. Grid of aluminum framing is 600 mm x 600 mm. Exposed framing made with peripheral 3" ply patta .and centrally having 12 mm thk toughen glass provision with suggested frosted film (plane/colorful) All exposed surfaces of one side finished with 1 mm thick laminate & at another side finished with 4 mm veneer complete with PU mat polish spray polish of approved shade. Make necessary grooves as per shown in drawing. Necessary framing to be erected above false ceiling (up to beam and slab height.) No extra cost to be paid for the same. Before installation, make hole/face plate for conduit pipes of electrical / networking cables with open able stud from partition Including all materials and labor etc. For glazing using of 12 mm thick toughen clear glass with proper crystal edges & with suggested frosted films on glass. All joints are covered with burma border bidding Patti finished with laminate/veneer as per actual site finish. Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/Engineer In charge. Contractor has to provide all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.</p>	71.62	Sq.Mt		
Rate in words:					
34	<p>FULL HEIGHT PARTLY GLAZED PARTITION UP TO FALSE CEILLING (LAMINATE FINISH)L:- :- Providing & Fixing both side laminated partly glazed partition up to false ceiling ht (thickness of partition is 64 mm) having 06 mm thick MR grade plywood both side on aluminum framing . Aluminum framing size for vertical & horizontal support is 50 mm x 25 mm having guage of 16.. Grid of aluminum framing is 600 mm x 600 mm. Exposed framing made with peripheral 3" ply patta .and centrally having 12 mm thk toughen glass provision with suggested frosted film (plane/colorful) All exposed surfaces of one side finished with 1 mm thick laminate of approved shade. Make necessary grooves as per shown in drawing. Necessary framing to be erected above false ceiling (up to beam and slab height.) No extra cost to be paid for the same. Before installation, make hole/face plate for conduit pipes of electrical / networking cables with open able stud from partition Including all materials and labor etc. For glazing using of 12 mm thick toughen clear glass with proper crystal edges & with suggested frosted films on glass. All joints are covered with burma border bidding Patti finished with laminate/veneer as per actual site finish. Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/Engineer In charge. Contractor has to provide all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.</p>	195.65	Sq.Mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
35	<p>FULL HT FLUSH PARTITONS UP TO FALSE CEILLING (ONE SIDE LAMINATE ONE SIDE VENEER FINISH)):-Providing & Fixing One side laminated & one side veneer flush partition up to false ceiling ht (thickness of partition is 67 mm) having 12 mm thick MR grade plywood both side on aluminum framing . Aluminum framing size for vertical & horizontal support is 50 mm x 25 mm having guage of 16.. Grid of aluminum framing is 600 mm x 600 mm. All exposed surfaces of one side finished with 1 mm thick laminate & at another side finished with 4 mm veneer complete with PU mat polish spray polish of approved shade. Make necessary grooves as per shown in drawing. Necessary framing to be erected above false ceiling (up to beam and slab height.) No extra cost to be paid for the same. Before installation, make hole/face plate for conduit pipes of electrical / networking cables with open able stud from partition Including all materials and labor etc. All joints are covered with burma border bidding Patti finished with laminate/veneer as per actual site finish. Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/Engineer In charge. Contractor has to provide all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.</p>	157.68	Sq.Mt		
Rate in words:					
36	<p>FULL HEIGHT FLUSH PARTITION UP TO FALSE CEILLING (VENEER FINISH):- FULL HEIGHT FLUSH PARTITION UP TO FALSE CEILLING (VENEER FINISH):- Providing & Fixing veneer finish flush partition up to false ceiling ht (thickness of partition is 70 mm) having 12 mm thick mr grade plywood both side on aluminum framing . Aluminum framing size for vertical & horizontal support is 50 mm x 25 mm. Grid of aluminum framing is 600 mm x 600 mm having guage of 16. All exposed surfaces of finished with 4 mm veneer complete with PU mat polish spray polish of approved shade. All complete with pu polish. Make necessary grooves as per shown in drawing. Necessary framing to be erected above false ceiling (up to beam and slab height.) No extra cost to be paid for the same. Before installation, make hole/face plate for conduit pipes of electrical / networking cables with open able stud from partition Including all materials and labor etc. All joints are covered with burma border bidding Patti finished with pu polish /veneer as per actual site finish. Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/Engineer In charge. Contractor has to provide all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.</p>	143.78	Sq.Mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
37	<p>FULL HEIGHT ACAUSTIC FLUSH PARTITION UP TO FALSE CEILING :- Providing & Fixing acaustic finish flush partition up to false ceiling ht having 12 mm thk acaustic sheet on 6 mm ply (acaustic sheet (plane or colorful)) suggested sides (single or both side) on aluminum framing . Aluminum framing size for vertical & horizontal support is 50 mm x 25 mm. Grid of aluminum framing is 600 mm x 600 mm. To fill absorb wool in all alu framing . All exposed surfaces of ply finished with suggested shed acoustic sheet/panels as per given pattern in design. acaustic sheet is fitted with 10 mm thk foam with gripper acaustic sheet with help of stapplers on uniformly distances . Create necessary colorful patterns with using acaustic panels/suggested fabric as per shown in drawing. Necessary framing to be erected above false ceiling (up to beam and slab height.) No extra cost to be paid for the same. Before installation, make hole/face plate for conduit pipes of electrical / networking cables with open able stud from partition Including all materials and labor etc. All joints are covered with bidding Patti finished with polish/color/fabric as per actual site finish. Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/Engineer In charge. Contractor has to provide all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it. gripper fabric acaustic sheet basic cost is 140 rs sq ft .</p>	143.63	Sq.Mt		
Rate in words:					
38	<p>LOW HT PARTLY GLAZED PARTITION UPTO 1.21 MT HT: Providing & Fixing partly laminated & partly glazed partition up to 1.21 m ht (thickness of partition is 68 mm) having 6 mm thick MR grade plywood is 303 grade both side of aluminum framing of gauge 16 Aluminum framing size for each support is 50 mm x 25 mm. having grid of 600 mm x 600 mm. Finished with 1 mm thick laminate at all exposed surfaces of approved shade. Make necessary grooves as per shown in drawing. Using of 12 mm thick frosted glass with proper crystal edges. Using of 12 mm thick toughen clear glass with proper crystal edges & with suggested frosted films/color films on glass. Glass starts from 1.00 mt lvl . All joints are covered with Burma border bidding Patti finished with Laminate/polish. Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/consultant/Engineer In charge. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	223.89	Sq.Mt		
Rate in words:					
39	<p>FLUSH PARTITION (laminate finish) : FLUSH PARTITION (laminate finish) : Providing & fixing flush partition up to false ceiling ht (thickness of partition is 64 mm) having 06 mm thick mr grade plywood IS 303 both side on aluminum framing. Aluminum framing having 16 guage and size for vertical & horizontal support is 50 mm x 25 mm. All exposed surfaces finished with 1 mm thick laminate of approved shade without any air gap and grooving as per design. Necessary framing to be erected above false ceiling. No extra cost to be paid for the same. Before installation, make hole/face plate for conduit pipes of electrical / networking cables with open able stud from partition Including all materials and labor etc. Make necessary grooves as per shown in drawing. All bottom ends are covered with burma border bidding Patti finished with laminate Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/consultant/Engineer In charge. Contractor has to provide all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.</p>	274.15	Sq.Mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
40	<p>Vineer Finish Trophy Storage :- Providing & fixing Veneer Finish trophy cupboard having depth of 375 mm , FOR SHUTTER:- framing of 18 mm Thick. MR grade Ply Wood with all necessary proper adhesive and hardwares,having 12 mm extra clear toughen glass with crystal edges & frosted effects for shutter fixed in ply framing . All complete with hole ,cut work etc. Pheripheral frame make with 18 mm MR grade ply finished with 4 mm thk vineer and suggested PU spreay polish .</p> <p>FOR STORAGE BODY :- Having pheripheral vertical sandwich supports & horizontal single selves as per given in detail drawings made out of 18 mm Thick. MR grade Ply Wood. Backside of storage is covered with 12 mm thick MR grade plywood. All exposed and internal Joints complete with burma border bidding patti finished with laminate/ polish . All exposed surfaces covered with 4 mm veneer and finished with PU Polish with mat finish and internal surfaces covered with 1 mm thick approved shade laminates as instructed by Architect/consultant/Engineer In charge. Complete with all necessary hardwares like handles, glass to glass locks/Conceal Mortise Locks,with all hardware like MS nails, SS-304 screws, magnet, Stoppers, L - hinges, table chain, etc. as per details given in drawing and as per instructions of Architect/Engineer In charge .</p>	3.78	Sq.Mt		

Rate in words:

41	<p>PARTLY GLAZED DOUBLE LEAF DOOR (ONE SIDE LAMINATE ONE SIDE VENEER FINISH):-</p> <p>Providing & fixing flush Double leaf Door/Single leaf , (finished size of door is 56 mm) of size 900 mm x 2400 mm (for each door.) considering blockboard flush door sheet of 35 mm thickness covered both side by 4 mm mr grade ply & finished with 1 mm thick laminate of suggested shed at single side and 4 mm veneer another side complete with pu spray polish on sides of shutters fixed with appropriate burma border patti , rest on floor spring of 100 kg & Top-Bottom wooden fitting for door-pivot. All exposed framing made by Burma border wood complete with laminate/veneer. Finishing with all necessary hardware like conceal handles, conceal locks,stoppers,tower bolt,MS nails, SS-304 screws etc.</p>	7.40	Sq.Mt		
----	--	------	-------	--	--

Rate in words:

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
42	FULLY GLAZED DOOR WITH PHERIPHERIAL VINEER PLY FRAMING :- Providing material & labour charge for making Fully Glazed Door with pheripheral ply framing based on aluminium framing of size 900 mm x 2225 mm having 12 mm extra clear toughen glass with crystle edges & frosted effects . All complete with hole ,cut work etc. Glazed Door supported on floor spring of 100 kg & pivots with fitting on top/bottom/corner patch fittings . Pheripheral frame make with 12 mm MR grade ply finished with 4 mm thk vineer and suggested PU spreay polish based on 50mm x25 mm aluminium section (16 guage) Complete with all necessary hardwares like 450 mm high handles, glass to glass locks/Conceal Mortise Locks etc as per details given in drawing and as per instructions of Architect/Engineer In charge.	14.80	sq mt		
Rate in words:					
43	FULLY GLAZED DOOR WITH PHERIPHERIAL LAMINATE PLY FRAMING Specification:- Providing material & labour charge for making Fully Glazed Door with pheripheral ply framing based on aluminium framing of size 900 mm x 2225 mm having 12 mm extra clear toughen glass with crystle edges & frosted effects . All complete with hole ,cut work etc. Glazed Door supported on floor spring of 100 kg & pivots with fitting on top/bottom/corner patch fittings . Pheripheral frame make with 12 mm MR grade ply finished with 1 mm thk suggested shed laminate based on 50mm x25 mm aluminium section (16 guage) Complete with all necessary hardwares like 450 mm high handles, glass to glass locks/Conceal Mortise Locks etc as per details given in drawing and as per instructions of Architect/Engineer In charge.	27.95	sq mt		
Rate in words:					
44	SINGLE LEAF FLUSH DOOR (VENEER FINISH):- Specification:- Providing Material & Labour charge for making Flush Door (finished size of door is 61 mm) of size 900 mm x 2250 mm considering blockbord flush door sheet of 35mm thkness covered both side by 4 mm commercial ply & finished with 4 mm thk vineer on both sides of shutter supported by SS -304 finish ryel hinges . All exposed framing of 50 mm x12 mm made by Burma border wood patti complete with pu polish. Finishing with all necessary hardwares like wood handles or SS handles as suggested ,conceal mortise locks, cylinders with 6 nos of keys , stopers,tower bolt,MS nails, SS-304 screws etc. as per details given in drawing and as per instructions of Architect/Engineer In charge. Please see the Attached Make List for Apporoved Makes.	12.33	sq mt		
Rate in words:					
45	SINGLE LEAF FLUSH DOOR (lamimate finish) : Specification:- Providing Material & Labour charge for making Flush Door (finished size of door is 55 mm) of size 900 mm x 2250 mm considering blockbord flush door sheet of 35mm thkness covered both side by 9 mm commercial ply & finished with 1 mm thk laminate of suggested shed on both sides of shutter supported by SS -304 finish ryel hinges . All exposed framing of 50 mm x12 mm made by Burma border wood patti complete with suggested polish or laminate . Finishing with all necessary hardwares like wood handles or SS handles as suggested ,conceal mortise locks, cylinders with 6 nos of keys , stopers,tower bolt,MS nails, SS-304 screws etc. as per details given in drawing and as per instructions of Architect/Engineer In charge. Please see the Attached Make List for Apporoved Makes.	106.86	sq mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
46	<p>GLASS VINEER FINISH CENTRAL TIPOI Providing & making centre tipoi having 12 mm glass top and as self of 600 mm x 450 mm based on 18 mm ply frame at top and bottom as per view, with all necessary proper solutions, hardware etc as suggested in detail drawing. Base frame size is 450 mm x 440 mm. Glass top is fitted with pheripheral frame support . and self is rest on both vertical leg support. Base box covered with tie frame . .All exposed surfaces finish with 4 mm thick veneer finish with PU spray Polish mat finish. Tipoi have rolled on conceal caster wheels. All Details as per shown in detail drawings & as per instructions of architect/consultant / incharge engineer.</p>	3.00	No		
Rate in words:					
47	<p>CORIAN TOP VINEER FINISH BACK CREDENZA:- Providing & fixing Corian Top Veneer Finish back credenza having depth of 375 mm , with corian top (top width is 450 mm (which covers sides, edges & 50 mm bottom of ply,front edge1.5")) based on 19mm Thick. MR grade Ply Wood with all necessary proper solution, finished with rubbing and buffing. Having vertical sandwich supports for shutters & horizontal single self as per given in detail drawings drawers made out of 18 mm Thick. MR grade Ply Wood. Backside of credenza is covered with 12 mm thick MR grade plywood. All exposed and internal Joints complete with burma border bidding patti finished with laminate/melamine polish . All exposed surfaces covered with 4 mm veneer and finished with PU Polish with mat finish and internal surfaces covered with 1 mm thick approved shade laminates as instructed by Architect/consultant/Engineer In charge. Complete as per detail Drawings, with all hardware like MS nails, SS-304 screws, magnet, Stoppers, L - hinges, table chain, 4" mat finish SS handles etc.</p>	12.18	sq mt		
Rate in words:					
48	<p>ITALIAN TOP VINEER FINISH BACK CREDENZA UP TO 0.76 MT HT Providing & fixing Italian Top Veneer Finish back credenza having depth of 375 mm , with italian top (top width is 450 mm (which covers sides, edges & 50 mm bottom of ply,front edge1.5")) based on 18 mm Thick. MR grade Ply Wood with all necessary proper solution, finished with rubbing and buffing. Having vertical sandwich supports for shutters & horizontal single self as per given in detail drawings drawers made out of 18 mm Thick. MR grade Ply Wood. Backside of credenza is covered with 12 mm thick MR grade plywood. All exposed and internal Joints complete with burma border bidding patti finished with laminate/melamine polish . All exposed surfaces covered with 4 mm veneer and finished with PU Polish with mat finish and internal surfaces covered with 1 mm thick approved shade laminates as instructed by Architect/consultant/Engineer In charge. Complete as per detail Drawings, with all hardware like MS nails, SS-304 screws, magnet, Stoppers, L - hinges, table chain, 4" mat finish SS handles etc.</p>	2.96	sq mt		
Rate in words:					
49	<p>LAMINATE FINISH BACK CREDENZA UP TO 0.76 MT HT:- Providing & fixing Laminate Finish Low ht back credenza having depth of 375 mm , with 18 mm mr grade ply top, based on sandwidth vertical supports made by 18 mm Thick. mr grade Ply Wood with all shutters & horizontal single self (made by 18 mm thick MR grade ply) as per given in detail drawings. Backside of low ht storage is covered with 12 mm thick plywood. Shutters made with 18 mm ply with conceal handles. All exposed and internal Joints complete with burma border bidding patti finished with melamine polish. All exposed and internal surfaces covered with 1 mm thick approved shade laminates as instructed by Architect/consultant/Engineer in charge. Complete with all hardware like MS nails, ss-304 screws, magnet, Stoppers, L - hinges, 19 mm multilocks, table chain, conceal handles etc.</p>	85.74	sq mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
50	<p>CORIAN TOP VINEER FINISH SIDE CREDENZA: Providing & fixing Corian Top Veneer Finish back credenza having depth of 375 mm , with corian top (top width is 450 mm (which covers sides, edges & 50 mm bottom of ply, front edge 1.5")) based on 19mm Thick. MR grade Ply Wood with all necessary proper solution, finished with rubbing and buffing. Having vertical sandwich supports for shutters & horizontal single self as per given in detail drawings drawers made out of 18 mm Thick. MR grade Ply Wood. Backside of credenza is covered with 12 mm thick MR grade plywood. All exposed and internal Joints complete with burma border bidding patti finished with laminate/melamine polish . All exposed surfaces covered with 4 mm veneer and finished with PU Polish with mat finish and internal surfaces covered with 1 mm thick approved shade laminates as instructed by Architect/consultant/Engineer In charge. Complete as per detail Drawings, with all hardware like MS nails, SS-304 screws, magnet, Stoppers, L - hinges, table chain, 4" mat finish SS handles etc.</p>	3.59	sq mt		
Rate in words:					
51	<p>LAMINATE FINISH SIDE CREDENZA UP TO 0.60 MT HT. Providing Material & Labour charge for making Laminate Finish Low ht side credenza having depth of 375 mm , with 18 mm mr grade ply top, based on sandwidth vertical supports made by 18 mm Thk. mr grade Ply Wood with all shutters & horizontal single self (made by 18 mm thk mr grade ply) as per given in detail drawings. Backside of low ht storage is covered with 12 mm thk plywood. Shutters made with 18 mm ply with conceal handles. All exposed and internal Joints complete with burma border bidding patti (25 mm x 12 mm) finished with melamine polish. All exposed and internal surfaces covered with 1 mm thk approved shade laminates as instructed by Architect/Engineer In charge. Complete with all hardwares like MS nails, ss-304 screws, magnet, Stoppers, L - hinges, 19 mm multilocks, table chain, conceal handles etc</p>	31.12			
Rate in words:					
52	<p>LAMINATE FINISH STORAGE UPTO 1.52 MT HEIGHT:-Providing & fixing low ht storage having suggested length & 2400 mm height and having depth of 600 mm, having skirting of 75 mm, with proper locks. 5 nos of vertical supports & 3 no of horizontal shelves made by 18 mm thick MR grade ply, having shutters of 8 mm thick double sandwich ply with using 12 mm thick MR ply for framing. All complete with proper Burma border bidding. Back ply is 12 mm MR grade ply. All exposed & internal surfaces are covered with 1 mm thick laminate. External & internal joints covered with bidding Patti complete with laminate finish. All complete with proper hardware like locks, S.S. Screws, MS Nails, Magnets, table chains, cable manager SS 304 Handles of 250 mm and 100 mm dia etc. All Details as per shown in detail drawings & as per instructions of architect/consultant / in charge engineer</p>	75.15	sq.mt		
Rate in words:					
53	<p>LAMINATE FINISH TABLE:- Providing & fixing laminate finish table having given size with height of 750 mm (as per attached detail drawing) Table having 36 mm Thick .at top made by 18 mm thick sandwich ply . Top is cantilever then its base supports. Base supports made by 18 mm thick sandwich ply. A Table having drawers and a shutter in a pedestal and a key board tray at single end. Drawers & Keyboard tray rest on telescopic channels. Shutters & drawers having thickness of 24 mm which are made by 18mm + 6 mm ply to create conceal grooves as handle. Drawers & keyboard, sides, Bottom is covered with 18 mm MR grade ply & Back of pedestal are made up of 12 mm thick MR grade Ply Wood. Having 3" high Footrest of 18 mm ply. At Front facade (covered with grooves as per given patterns. All internal and external surfaces covered by 1mm thick laminate. all complete with given nos of key board tray, drawers on telescopic channels, locks, stoppers, SS Screws, MS nails, Auto hinges, Cable Manager etc as per shown in detail drawings & as per instructions of architect/consultant / in charge engineer. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	59.37	sq.mt		

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
Rate in words:					
54	<p>CORIAN TOP VINEER FINISH TABLE:- Providing & fixing corian top veneer finish table having given size with height of 750 mm (as per attached detail drawing) Table having 40 mm Thick. at top made by corian finish with buffing polishing etc rest on 18 mm MR grade ply . Top is cantilever then its base supports. Base supports made by 18 mm thick sandwich ply . A Table having two nos of drawers and a shutter for both sides in a pedestal and a key board tray at mid of table. Drawers & Keyboard tray rest on telescopic channels. Shutters & drawers having thickness of 18 mm which are made by 18 mm ply to create conceal grooves as handle. Drawers & keyboard side, Bottom & Back of pedestal are made up of 12 mm thick mr grade Ply Wood. Having 3" high Footrest of 18 mm ply.(</p> <p>(1) In elevation of GM table have a provision of 30mmx30mm veneer finish patties finished with PU polish. and top is rest on that patties on one end and at another side top is rest on 50 to 100 mm SS stud. (2)In elevation of DGM table top is partly covered with corian top and sides have trapezoid vertical support as shown in detail drawing of 18 mm sandwich ply.) All Exposed surfaces covered with 4 mm thick veneer complete with PU polish. And internal surfaces covered by 1mm thick laminate. all complete with given no of key board tray, drawers on telescopic channels, locks, stoppers, SS Screws,MS nails, Auto hinges, Cable Manager etc as per shown in detail drawings & as per instructions of architect/consultant / in charge engineer. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	7.03	sq.mt		
Rate in words:					
55	<p>GLASS TOP VINEER FINISH MEETING TABLE:- Providing & fixing glass top veneer finish meeting table having 12 MM thk toughen glass on top with all bewale and crystle edges fitted with pvc buffers . base support made with 12 mm thk sandwich ply of square box base size of 450mm x 450 mm with 12 mm deep suggested grooves /patties as suggested in pattern finish with 4 mm thk veneer complete with suggested pu polish. veneer finish meeting table 750 mm height , 900 mm diametre table have base of 12 mm + 12 mm (top,bottom & all sides) thick sandwich plywood for supporting vertical supports. Ply for grooving as indicated in drawing. (as per details given in sectional drawing) Edges of the table covered by burmaborder bidding Patti finished with veneer/polish. All external surfaces covered by 4mm thick veneer, complete with PU spray polish.All internal surfaces covered with All complete as per shown in detail drawings & as per instructions of architect / in charge engineer. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	0.81	sq.mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
56	<p>ABSORB WOOL FOR ACOUSTIC PARTITION/ PANELING Providing and Fixing in position 50mm thick absorb wool in slab form of density 48 Kg/cum or any other approved make behind wall/ceiling/between partition paneling as shown in the drawings and manufacture's specification. The Installation shall be as per following steps:</p> <p>1. Fix framework / Batten out backside of wall paneling to suit width of insulation slabs</p> <p>2. Insulation slabs shall be fixed snugly between frames without gaps.</p> <p>3. Fixing shall be done on vertical batten with staples or flat head nails or adhesive solution. Ply/paneling item shall be paid as per tender item. Item shall be operated, measured and paid if and only not mentioned in relevant tender item.</p>	169.85	sq.mt		
Rate in words:					
57	<p>CORIAN TOP VINEER FINISH CONFERENCE TABLE :- Providing & fixing corian top veneer finish conference table 750 mm height , 600 mm wide & 17259 running mm longitudinal meeting table having 12mm Thick. Corean Top based on 18 mm thick MR grade plywood finished by rubbing ,buffing & pasting (Core an top covers 300 mm bottom of table at longitudinal side & 300 mm bottom of table at shorter side including edges) table have base of 18 mm thick MR grade plywood for footrest & supporting vertical supports made by of 12mm+8 mm thick sandwiched Ply for grooving as indicated in drawing. At internal sides use of 0.30 mt ht 5 mm smoke mirror which are pasting on ply with use of appropriate silikon. (as per details given in sectional drawing) Base of the table covered by burmateak bidding Patti finished with veneer. All external & internal surfaces covered by 4 mm thick veneer, complete with PU spray polish All complete as per shown in detail drawings & as per instructions of architect / in charge engineer. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	17.24	R mt		
Rate in words:					
58	<p>GYPSUM FALSE CEILLING:-</p> <p>The works include supply and installation & fixing of Gypsum Board Ceiling which Incorporates a fully concealed GI fixing grid of ultra channel 18 guage. Complete with all necessary hardware, fittings and accessories. Board joints are not visible and all gaps are filled with gypsum jointing compound like gypsum powder . The job also includes providing access panels, cutting of spot lights, luminaries, speaker, etc. Sheets in size 4' x 8' in thickness ½" (or 3/8") screwed on steel stud system. The steel stud frame consisting of main furring GI channel at every 600 mm and cross channel at every 600 mm . Both main and cross channels are attached though jaw clip. Screws will be corrosion proof either Chromites or Cynated. Screw fixing is done mechanically with drilling machine & suitable attachment. Finally the boards are to be jointed & finished so as to have a flush look which includes filling & finishing with jointing compound, paper tape and two coats of top coats of gyp board, etc completed.</p> <p>The gaps will be initially filled with joining gypsum plaster compound and then taped by self adhesive covered with proper jointing compound like gypsum powder. Contractor has to provided all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	1002.25	sq.mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
59	<p>PLY VINEER CEILING:</p> <p>The works include providing & fixing of Ply Board (12mm thick) Ceiling which Incorporates a fully concealed Aluminum grid. Complete with all necessary hardware, fittings and accessories. Finish with suggested laminates. The job also includes providing access panels, cutting of spot lights, luminaries, speaker, etc. Sheets in size 8' x 4' VINEER 4 mm in thickness. finish with pu mat polish . 1/2" (or 3/8") screwed on steel stud system. The steel stud frame consisting of main furring Alum channel at every 600 mm and cross channel at every 600 mm. Both main and cross channels are attached though jaw clip. Screws will be corrosion proof either Chromised or Cynated. Screw fixing is done mechanically with drilling machine & suitable attachment. The gaps will be initially filled with jointing compound and then taped by self adhesive covered with proper jointing compound..Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	41.24	sq.mt		
Rate in words:					
60	<p>ARMSTRONG "WOODWORKS GRILLE WITH BACKER MADE OF NATURAL BAMBOO WITH ARMSTRONG 24MM PRELUDE 43 BLACK" SYSTEM:-</p> <p>PROVIDING & FIXING OF ARMSTRONG WOODWORKS GRILLE WITH BACKER MADE OF NATURAL BAMBOO WITH ARMSTRONG 24MM PRELUDE 43 BLACK EXPOSED GRID.</p> <p>The Woodworks (WW) Grille panel of nominal size 35x300x2400mm comprising 8 blades of 35x16x2376mm with on center spacing of 37.5mm fixed thru Backer of size 12x22x300mm with on center spacing of 300mm and additional end backers at 150mm from both the edges. Ledger of 6.5x24x2400mm to be used for covering face of wall angle. WW Grille should comply with ASTM-E84: Class A and have Relative Humidity of RH70. The panels are UV coated to Natural or Carbonized shades</p> <p>Optional : Open edges may be covered using "Edge Caps" of 44x19x2400mm and "Blade Junction" of 66x38x2400mm to be used along the connection of two WW Grille Panels.</p> <p>The grid should be of "Armstrong" make Prelude 43 with 24mm wide T - section flanges Black powder coating having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 43mm for the main runner & the Cross Tees and with a load carrying capacity of 20 Kgs/M2. Black backer clips of spring steel to be used for fixing panel to suspension system.</p> <p>INSTALLATION: To comprise main runner spaced at 1200mm centers securely fixed to the structural soffit using Armstrong suspension system (specifications below) at 1200mm maximum center. The First/Last Armstrong suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.</p> <p>Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm center to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees.</p>	49.00	sq.mt		

Perimeter trim to be Armstrong wall angles of size 19x19x3000mm, secured to walls at 450 mm maximum centers.

Backer clips are used to fix the panel to suspension with a grid formation of 600mm along the slat and 2 pieces along each dowel for every individual panel

ARMSTRONG SUSPENSION SYSTEM: accessories supplied by Armstrong World Industries consisting of M6 Anchor Fasteners with hanger hole, pre Straightened Hanger wire of dia – 2.5 mm of 1.80 m length having a tensile strength of 344-413 MPa, along with Adjustable hook clips of 0.8mm thick, galvanized spring steel for 2.5 mm wire with a minimum pull strength of 110 kg. The adjustable clip also consists of a 4 mm aquiline wire to be used with the main runner.

Rate in words:

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
61	<p>MDF ACRYLIC CEILING:The works include providing & fixing of MDF Ply Board Ceiling which Incorporates a fully concealed Aluminum grid. Complete with all necessary hardware, fittings and accessories. Finish with suggested laminates. The job also includes providing access MDF 3D panels/regular sheet , back side cover with suggested 6 mm acrylic sheet ,MDF sheet finish with PU spray polish. cutting of spot lights, luminaries, speaker, etc. MDF sheet finished with suggested PU mat polish.. ½" (or 3/8") screwed on steel stud system. The steel stud frame consisting of main furring Alum channel at every 600 mm and cross channel at every 600 mm. Both main and cross channels are attached through jaw clip. Screws will be corrosion proof either Chromised or Cynated. Screw fixing is done mechanically with drilling machine & suitable attachment. The gaps will be initially filled with jointing compound and then taped by self adhesive covered with proper jointing compound..Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	10.00	sq.mt		
Rate in words:					
62	<p>LIGHT WEIGHT CALCIUM SILICATE CEILING: Providing and fixing eco-friendly light weight calcium silicate false ceiling tiles having Tegular edge & 15 mm Thick edges on the Tile Periphery for Extra Strength The Light weight calcium silicate ceiling tiles shall have , light reflection 85% non-combustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity 0.043° w/m KC.for the best thermal Insulation . The Light weight calcium Silicate tile shall be of approved texture Fine fissured/ Spintone/Cosmos having NRC value of 0.5 & Globe having NRC value of 0.75 NRC or equivalent of size 595 X 595 mm to be laid on true horizontal level suspended inter locking metal grid of hot dipped galvanized steel sections (galvanizing @120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and size of 24X38mm made from 0.30 mm thick (minimum) sheet, 1200mm centre to centre, and cross 'T' of size 24X28mm made out of 0.33mm (Minimum) sheet spaced 1200mm along spaced between main 'T' at 600mm centre to centre to form agrid of 1200X600mm and secondary cross 'T' of length 600mm and size 24x28mm made of 0.30 mm thick (Minimum) sheet to be interlocked at middle of the 1200X600mm panel to form grid of size 600X600mm resting on periphery walls/partitions on a perimeter wall angle pre-coated steel of size (24X24X3000mm made of 0.40mm thick (minimum) sheet with the help of rawl plugs at 450mm centre to centre with 25mm long dry wall screws @ 230mm interval and laying 15mm thick Densified edges light weight calcium silicate ceiling tiles of approved texture (Fine Fissured/Cosmos/Spintone) in the grid including, cutting /making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required, Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25X35X1.6mm fixed to ceiling with 12.5mm dia and 50mm long dash fasteners, 4mm G.I. adjustable rods with galvanized steel level clips of size 85X30X0.8mm, spaced at 1200mm centre to centre long main 'T' bottom exposed with 24mm of all T-sections shall be pre-painted with polyester baked paint, for all heights, as per specifications, drawings and as directed by engineer-in-charge.</p>	371.88	sq.mt		
Rate in words:					
63	<p>CEMENT SHEET CEILING The works include supply installation and fixing of Cement Sheet Ceiling which Incorporates a fully concealed GI fixing grid. Complete with all necessary hardware, fittings, Luster paint , and accessories. The job also includes providing access panels, cutting of spot lights, , etc. . The steel stud frame consisting of main furring GI channel at every 600 mm and cross channel at every 600 mm. Both main and cross channels are attached through jaw clip. Screws will be corrosion proof either Chromised or Cynated. Contractor has to provided all necessary cut outs for Electrical works & no extra payment shall be made for it.</p>	246.08	sq.mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
64	ITALIAN TOP VINEER FINISH RECEPTION TABLE Providing Labour & Material for making half circular (where running length is 5850 mm) reception table having 12mm Thk. Italian Top based on 18 mm thk MR grade plywood with all necessary proper solution, finished by rubbing and buffing (Italian top covers 100 mm bottom of ply at front of table & 50 mm bottom of ply of inner side including edges of reception table, having three nos of base boxes of size 450x525x500 mm with providing drawers with telescopic channels & shutters made up of 18mm thk MR grade Ply, Having 3" high Footrest between each box support & bottom of the table covered by 25 mm x 25 mm thk bidding patti, centre suggested part of reception have 150 mm high & bottom patta with 75 mm high patta of 5 mm thk smoke mirror pasting on ply with proper silicon. All exposed surfaces covered by 4 mm thk vineer finished with suggested PU polish. Internal area of table is covered with 1 mm thk laminate of suggested shed. All complete with two nos of key board tray, drawers on telescopic channels, locks, stoppers, SS Screws, MS nails, Auto hinges as per shown in detail drawings & as per instructions of architect / incharge engineer. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it. Please see the Attached Make List for Approved Makes.	1.00	No		
Rate in words:					
65	REST ROOM WALL HUNG UNIT: Providing & fixing wall hung tv unit as per given design & sizes having single shelf as shown in detail drawing made by 18 mm thick mr grade ply. All exposed and internal surfaces covered with 4 mm thick vineer finished with pu mat polish. All complete with proper hardware like, S.S. Screws, MS Nails etc. Providing all necessary cutouts for electrical fittings. All Details as per shown in detail drawings & as per instructions of architect/consultant / in charge engineer. Complete as per detail drawings and instructions given by architect/consultant/ Engineer In charge. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it.	2.03	sq.mt		
Rate in words:					
66	ITALIAN MARBLE WALL CLADDING Providing & cladding machinecut, mirror polished, 18 mm thick (+/-1mm) Italian Marble stone (olive beige, crema beige and similar type as approved by architect) selected & sorted free from cracks, fissures & flakes, wall plain Cladding as per drawing laid in any pattern and laid on over a bed of 12 mm thick cement sheet base on aluminium framing with use of modified adhesive like cheracol (conforming to ISO 13007) with pigment to match/contrast the shade of Stone making sure that the bond between the marble and the surface of the sub-base is firm and the laid sample to be approved for workmanship and quality acceptance. Cost to include for laying with any gap which will be filled with Epoxy stain free (SP-100) grout / c necessary pigmentation to match with the colour of stone, cutting, metering, curing, cleaning with complete grinding and Mirror Polishing with diamond pad setc. including all other necessary related works as per specifications and schedule and reference drawing or directed by Engineer In-charge. Rate has to include the change in go stones which gets damaged due to site-working, until the site-handover. Rate shall also include preparation of base surface and covering of finishing material with the help of polythene/jute where ever required and removing the same before handover, work at all levels as directed by engineer-in-	17.26	sq.mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
67	<p>• SOFT BOARD PANELING: Providing and fixing on wall/partition 12mm thick approved quality soft board with cotton cloth/fabric of approved make and shade on 12 mm thick mr grade ply with oak wood beading all around including semi glossy PU polish, as approved sample and as directed by Architect/consultant. The work shall be measured & paid in Sqm. for all floors, all level and at all heights including all costs (basic rate of cotton cloth /fabric for 54" wide shall be Rs. 400/ meter The rate shall be inclusive of polish to all the exposed wooden members. Only the clear elevation area of the cloth/fabric shall be measured and paid. sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from ENGINEER IN CHARGE and Architect/consultant</p>	96.49	sq.mt		
Rate in words:					
68	<p>• LAMINATE COLUMN PANELING: Providing & fixing column paneling having suggested aluminum grid of 37mm x 37mm or 50mmx 25 mm framing (whichever requires.)Having 16 guage) of size 600 mm x600 mm by aluminium sections of given size. Grid frame is covered with 6mm thick mr grade plywood. To create suggested groove & neices. All grooves are finished with laminate. All exposed surfaces covered with 1 mm thick laminates of approved shade as instructed by Architect/consultant/Engineer In charge. Complete with all hardwares like s nails, ss screws, adhesives etc. shown in detail drawings. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it. Amount shall be paid only for the Paneling between the False Ceiling & Flooring.(</p>	243.45	sq.mt		
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE

CANARA BANK - GANDHINAGAR

Sr. No.	Description	Qty.	Unit	Rate	Amount
69	<p>• VINEER COLUMN PANELING: Providing & Fixing column paneling having aluminum grid framing (50x25 or 37x37mm having 16 gauge) of size 600 mm x 600 mm by aluminum sections of said size. Grid frame is covered with 6 mm thick mr grade plywood paneling to create suggested nieces & suggested grooves. Use of SS patties of suggested sizes on column as per given pattern. All grooves are finished with 4 mm thick veneer finish with pu mat polish. All exposed surfaces covered with 4 mm thick veneer of approved shade complete with PU polish as instructed by Architect/consultant/Engineer In charge. Complete with all hardwares like s nails, ss screws, adhesives etc. shown in detail drawings. Contractor has to provide all necessary cut outs for Electrical works & no extra payment shall be made for it. Amount shall be paid only for the Partition between the False Ceiling & Flooring.</p>	66.03	sq.mt		
Rate in words:					
70	<p>WOOD BLINDS:- Providing and fixing wood blinds as per approved make spring drive system with steel ball chain/one touch with speed control action wood blind with palmet, end brackets with head rail, components, bottom bar. Solar protection Fabric of Color with manual operation and warranty etc as per manufacturer's specifications. material to be as per approved sample. All the work complete as per the detailed drawing and instruction of Architect/consultant/ENGINEER IN CHARGE.(Contractor shall provide treated wooden pelmet complete in all respects on which all blinds shall be fixed and should also take load of all the manual blinds).</p>	100.00	sq.mt		
Rate in words:					
71	<p>ROLLER BLINDS: Providing and fixing Roller blinds of approved make and shade on glass façade</p>	100	sq.mt		
Rate in words:					
72	<p>Frosted sparking glass film:- Frosted sparking glass film: Providing and fixing frosted glass film of approved make Translucent, cast PVC, self-adhesive vinyl, special CRYSTAL-effect film to reproduce Sand-blasting effect on glass with customised designs. MCS warranty of 3 (if exposed to direct sunlight) to 10yrs (indoors) must be endorsed by manufacturer. Rate shall be inclusive plotter cutting design as per Architect/consultant/SUDA suggestion. .work complete including all type of tools, tackles, scaffolding etc complete as per suggestion of Architect/consultant/SUDA. If in case any application finishing will not as per satisfaction contractor shall remove all film at their cost. Contractor shall do a sample mock of 5 Sqm minimum of glass film), shall be approved from Architect/consultant/SUDA.(static cling window film)</p>	544.39	sq.mt		
Rate in words:					
73	<p>PREFUNCTIONAL SERVICE COUNTERTS:- Providing & fixing prefunctional service counter under granite platform having 12 mm +9 mm thick MR grade plywood as shutters both side 1 mm laminate finish including hinges, magnet, table chains, complete with bidding patties and all hardwares. All exposed and internal surfaces finished with 1 mm thick laminate of approved shade. All joints are covered with Ghana teac bidding patti finished with laminate. complete including require nos of drawer and shutter all type of fittings, fixtures, hardware approved make etc complete. SS 304 grade conceal handle shall be provide as per approved selection & detailed drawing and instruction of Architect/consultant/ PMC Contractor has to provided all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.</p>	2.55	sq.mt		

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE					
CANARA BANK - GANDHINAGAR					
Sr. No.	Description	Qty.	Unit	Rate	Amount
Rate in words:					

ABSTRACT SHEET - CIVIL & FURNISHING WORK ESTIMATE					
CANARA BANK - GANDHINAGAR					
Sr. No.	Description	Qty.	Unit	Rate	Amount
74	GLASS TOP ON TABLE FINISH TOP:- Providing & fixing 12 mm thick clear annealed glass on top on laminate finish table rest on vacuums as requires. Glass have bewel edges. Fitting as per details given in drawing and as per instructions of Architect/consultant/Engineer In charge. Contractor has to provided all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.	7.27	sq.mt		
Rate in words:					
75	SS 304 MAT FINISH DIRECTION SIGN Providing & Fixing signage on 1 mm SS 304 mat finish 0.8mm- 1 mm with 5 mm black acrylic direct pasting with silicon tape on any surface expect un finished wall (18"x4"=72 sq inch for each) (as per the approved size & shade) including fixing by using necessary hardwares (Fixing/bonding on wall /ply wherever it requires with its proper silicon pasting /studs ,screws,nails etc). completely with printing in suggested colors for each cabin/Utilities area above each door/wood surfaces/wall surfaces Before making the letters the font & size will be got approved from authority .	63.00	sq.mt		
Rate in words:					
76	10MM+3MM ACRYLIC AS PER LOGO COLOR:- Fixing with bolt or silicon tape as per the background and suggested logo in glossy finish size .cost including all laser cutting.	432.00	sq inch		
Rate in words:					
77	5 MM ACRYLIC BOX HANGING BOX:- provide all with vinyal and hanging SS wire studs/ss chain/ms chain approx size 24"x6".	1440.00	sq inch		
Rate in words:					
78	ALUMINIUM EMBOSS LETTERS:- Providing and fixing Aluminium emboss letter aluminium channl letters, front side acrylic,side wall pu color, inside high glow led modules,power supply for led, all installation as suggested by architect/incharge. (approx size 12"x4")	144.00	inch		
Rate in words:					
79	AC TRAP DOOR Providing & fixing cassette AC trap door boxes to fix in false ceiling.with using 18 mm mr grade ply .box size is 600 mm x 600mm x 1200 mm (= 10% variation in size)as per approved samples of ceiling panels. panels comprise of a powder- coated beaded steel frame with door. Each panel features a push –latch closing mechanism with door retaining safety cable & hook. Complete with hangers and all necessary hardware. Exposed surfaces finished with 1 mm thick laminate/paint of approved shade. Complete with all necessary hardware & adhesives as per details given in drawing and as per instructions of Architect/consultant/Engineer In charge. Contractor has to provided all necessary cut outs (race ways.) for Electrical works & no extra payment shall be made for it.	10.00	nos		
Rate in words:					
				TOTAL RS...	
Amount in words:					