

RENOVATION OF QUARTERS FOR CANARA BANK AT JAMNAGAR					
Sr. No	Description	Quantity	Unit	Rate	Amount
Note : Rate should be inclusive of material,labour,tools, machinery, scaffolding,					
Basic Rate of Items are Excluding GST					
1.00	EARTH WORK				
1.10	EXCAVATION WORK	36.00	CMT		
	Excavation in all types of soil, including murum, for foundations of wall, columns, plinth beams etc. including shoring strutting, bailing out water/pumping off water if required, refilling the trenches, foundatin pits, ramming, watering consolidating in 15 cms to 20 cms layers, removing and stacking simultaneously the excavated stuff as directed within the site area upto a lead of 300 m and/or spreading soils in layers for site development and consolidating as directed etc. complete.				
	TOTAL OF EARTH WORK -1				
2.00	CONCRETE WORK				
2.10	P/L PCC 1:4:8 FOR WALL FOUNDATION AND FLOOR ETC.	1.00	CMT		
	Providing and laying machine mixed Plain Cement Concrete 1:4:8 (1 part cement: 4 parts coarse sand : 8 parts of stone agreegat of size 40 mm and down.) for specified thickness, for foundaitons below walls, column footings, below floor ,Raft etc. including centering and shuttering if required, laying spreading, ramming, consolidating as per requirement and curing etc. complete as directed.				
2.40	P/F REINFORCEMENT BARS FOR DAMAGED BARS (FE 500GRADE)	100.00	KG		
	Providing and fixing reinforcement bars wherewere required in place of damaged reinforcement bars in RCC slab reinforement bars shall be welded with existing reinforcement bars as per instructions complete at all levels..				
2.50	REPARING OF DAMAGED RCC WORK	100.00	Kg		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Disemntalling damaged RCC work, applying "CONBONDSNA or equivalent Epoxy Rasin to concrete and reinforcement, covering reinforcement with concrete using 'EXPACRETE SN70' Non shrink free flow grouting product in 75 mm thickness, including, leak proof centering shuttering, curing and carting away debris. Rate is all levels. 'CONBONDSNA' & 'EXPACRETE SN70' Mfg. by ESSEN SUPPLEMENTS (I) LTD. or equivalent chemicals admextures as per the manufacturer's detail and instructions of the Engineer-in-charge. While repairing the column/slab/beam the surrounding structural member shall be edquat supporting. (Cost of Reinforcement shall be paid seperatly as per Item No 2.4).				
	TOTAL OF CONCRETE -2				
3.00	MASONRY WORK				
3.10	P/C BRICK WALLS (230 mm Thick)	1.84	CUMT		
	Providing and constructing brick masonry in CM 1:6 (1 cement & 6 coarse sand) with approved first class bricks having minimum crushing strength of 35 kg/sq.cm including scaffolding, racking out the joints, curing etc. Complete as directed by Engineer - in charge. For Wall at all levels below and upto plinth level.and above plinth level all heights				
3.20	P/C 115 MM THICK BRICK PARTITION WALLS	11.06	SMT		
	Providing and constructing 115 mm thick brick masonry in partition walls with approved good quality bricks having a crushing strength of 35 kg/sq.cm for super structure in CM 1:4 (1 cement : 4 coarse sand) including scaffolding, racking out joints, reinforcement of 2 nos. 8 mm dia MS bars at every fouth leayer , curing etc. complete as directed at all heights as follows. (Rate includes the cost of MS bars or Iron hoop)				
	TOTAL OF MASONRY -3				
4.00	FINISHING WORK				
4.10	P/A 12 MM THICK CEMENT PLASTER ON OLD WALL AND CEILLING	100.00	SMT		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Providing and applying 12mm thick finish cement plaster on internal walls of required damaged plaster area in 1:4 cement mortar to the walls, beams, ceiling, stair, column, pattias, patch work grooves including scaffolding, curing & finishing smooth. The plaster surface shall be rubbed with 'Iron plate'. till the surfae shows cement paste in line and level complete as directed. Including dismantling existing plaster.cleaning the site and carting away debris at all levels. Its disposal also Rates includes removing switch board plates and refixing same after plastering.				
4.1.1	P/A 12MM THICK FINISH CEMENT PLASTER ON NEW WALL AND CEILLING	350.00	SMT		
	Providing and applying 12mm thick finish cement plaster at all heights and below plinth in 1:4 cement mortar to the walls, beams, ceiling, stair, column, pattias, grooves including scaffolding, curing & finishing smooth. The plaster surface shall be rubbed with 'Iron plate'. till the surfae shows cement paste in line and level complete as directed. Plaster on New walls and ceiling				
4.20	P/A 19MM THICK SAND FACED CEMENT PLASTER	100.00	SMT		
	Providing and applying 19 mm thick sand faced cement plaster in two coats at all damaged plaster surface on external walls with first coat of 12 mm with cement mortar 1:4 (1 part cement : 4 parts of sand) and second coat of 7 mm with cement mortar 1:3 , rough finish with using sponge/ " Tipani ", on all types of concrete/brick surfaces making grooves,plastre pattas,projecting pattas paches work as per detail, including scaffolding, curing etc. complete as directed. Including dismantling existing plaster.cleaning the site and carting away debris at all levels. Its disposal				
4.30	P/A 19MM THICK CEMENT PLASTER WITH WATER PROOF COMPOUND FOR PARAPET WALL	209.00	SMT		
	Removing existing cement plaster from parapet walls and laying new 19 mm thick cement plaster in 1:4 proportion admixed with water proof compound Conplast X421 IC of Fosroc or equilant incl. curing complete as directed.Including dismantling existing plaster.cleaning the site and carting away debris at all levels.				

Sr. No	Description	Quantity	Unit	Rate	Amount
4.40	P/A POLYMER MORTAR PLASTER OR WATERPROOF PLASTER	150.00	SMT		
	Removing the loose plaster & concrete damages surfaces, cleaning the concrete surface with wire brush and reinforcement with rust remover, welding new reinforcement with Existing reinforcement if required applying epoxy resin to concrete & reinforcement surface of approved Brand and covering the surface with average 35 mm th. Polymer mortar of watreproof branch such as fosroc, magiccrete, evercrete etc as approved by Bank's engineer including scaffolding for repairing RCC slab, beam complete as directed (Rate including cleaning the site and carting away debris at all levels) . New reinforcement if required shall be paid as per Item No 2.5				
4.50	FILLING CRACK IN WALL AND PLASTER	100.00	RMT		
	Filling crack in wall & plaster by making V shape joint with high strength epoxy or PU or non shrink free flow cement such as Fosroc (Chemical Rendroc CF) or equivalent. Finishing the joint with Polymer cement mortor. Rate also includes cleaning the site and carting away debris at all levels.				
4.60	PAINTING WORK				
[a]	P/A ACRYLIC EMULSION PAINT (PLASTIC P	3091.97	SMT		
	Providing and applying (with rollers only) Acrylic emulsion paint of required shed and approved make on new/old work in two or more coats to give an even shed including the preparation of surface for painting, applying FULL primer and putty, at all heights complete as per manufacturer's specification and as directed.				
[c]	P/A SYNTHETIC ENAMEL PAINT	587.20	SMT		
	Providing and applying synthetic enamel paint, at all heights of required shade and approved make on old work including the scrapping/cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.				
[d]	P/A APEX PAINT	1354.10	SMT		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Providing and applying Apex paint (Asian Paint Advanced Anti Algal weather proof emulsion) on New/Old surface at all heights and levels. Work including preparation of surface cleaning and scraping by wire brush. Filling cracks with "Rendroc cs" (fosroc) and applying coat of Hydroproof liquid mixed with white cement. Applying primer coat as per company specifications and apply 2 or more coats of paint to give uniform shed at all levels complete.				
	TOTAL OF FINISHING-4				
5.00	FLOORING WORK				
5.5.1	P/F POLISHED KOTAH STONE PATTI FOR RAMP	12.00	SMT		
	Providing and fixing selected KOTAH STONE, Rough polish, 18mm to 19 mm thick with machine cut edges in required length and 75mm to 100mm width as per architects detail for Ramp etc. for measurement shall be Sqmt and paid in square meter only.				
	Measurement : Plan area shall be measured and paid				
5.60	P/F POLISHED GREEN KOTAH STONE FLOORING IN machine room	18.00	SMT		
	Providing and laying polished green kotah stone flooring using one side pre polished chiesel dressed green kotah stone in uniform shade of size 17"x17" / 17"x23" / 23"x23" (thickness of the stone 30 mm to 35 mm) over 37 mm thick cement mortar 1:6 with flush pointing of joints with cement paste mixed with green pigment colour, machine and hand polishing, daily moping with water and kerosene as directed for atleast 15 days etc. complete as directed.				
5.70	P/L CERAMIC TILES FLOORING IN TOILET	55.20	SMT		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Providing & fixing 600 x 600 mm coloured ceramic Tiles Flooring of approved make first quality ceramic tiles for flooring as per design, Laying Tiles in CM in 1:4 over cement mortar beading laid to proper slope, line & level as specified. The rate includes curing acid cleaning, cutting etc. complete. Rate shall be same for all levels (Toilet). Sample of the tiles must be got approved from Architect/Bank. Rate includes dismantling of existing tiles flooring and disposal complete as directed. (Basic price of tiles shall be Rs.400=00 Per Sqmt)				
5.7.1	P/L CINDER CONCRETE FILLING IN SUNKEN SLAB AT FIRST FLOOR	20.70	CMT		
	Providing and laying cinder concrete 1:8 Proportion in toilet block, drop slabs including compacting etc. complete at all levels.				
5.80	WATER PROOFING IN SUNK AT ALL FLOOR TOILET	46.00	SMT		
	1. Clean surface with wire brush, blower and water.				
	2. Open the cracks & cut a rectangular groove (aprx 4 mm wide & 8 mm deep) and Filling the groove with PU sealant of 5000% elongation.				
	3. Apply neat coat of BASF SBR 131 (35 Sqft /Liters) Then apply 6 mm thick plaster in 1:2 C.M with integrated water proofing compound of BASF 141 then apply 3 coat of 1cement:2 Kg Cement: 4 Liters water subsequently. Then do brick bat coba concrete to cover the drainage pipe and finish the top surface in 1:2 cement mortar finally apply a coat of 1 SBR: 1 water and again repeat 1:2:4 as above and pond testing to be done				
	4. Curing for 3 to 5 days				
	The contractor should give 5 year Guarantee to any leakage on stamp paper				
5.8.1	Providing and Laying 75 mm thick water Proof Indian pattern stone in 1:2:4 concrete Mix.In Toilet Sunk Slab	46.00	SMT		
	Providing and laying plain cement concrete flooring (PCC) 1:2:4 (1 Cement:2 Coarse Sand: 4 Stone aggregate 20 mm nominal size) admixed with water proof compound Conplast X421 IC of Fosroc or Equivalent company. curing etc. complete as directed.				

Sr. No	Description	Quantity	Unit	Rate	Amount
5.90	P/F CERAMIC TILES DADO ON WALL	454.70	SMT		
	Providing & laying wall dado of 5 to 6 mm thick coloured tiles of 600 x 600 of approved make first quality fixed cover 12mm thick plaster in CM 1:3, including providing groove upto 3mm wide if directed to do so and using grey cement in pointing of joints and applying neat cement paste about 3 Kg/Sq.m. The rate shall be inclusive of centre point fittings i.e. extra labour, material etc. to be considered so as to get outlet of plumbing/sanitary fittings at the junction. Rate shall be same for all levels. Sample of the tiles must be got approved from Architect/Bank. Rate all so includes backing coat of rough cement plaster. Rate includes dismantling of existing tiles and disposal complete as directed. (Basic price of tiles shall be Rs.400=00 Per Sqmt)				
5.12.1	P & L Water Proofing Treatment in terrace.				
	Note: The responsibility of the effectiveness of the treatment should be fully, entirely and unqualifiedly be that of the main contractor for the work. Only visible plan area to be measured for payment. Contractor shall provide waterproofing guarantee for min. 10 years as per Bank norms (furnishing of guarantee on a stamp paper in approved format for at least 10 years).				
	For Terrace - • Application of waterproof overcoat compound of Evercrete Top Seal or Magicrete or equivalent which is just applied over existing China mosaic.	135.06	SQMT		
5.13	P/L ROUND SHAPE CEMENT CONCRETE VATTA	100.00	RMT		
	Removing old fillets (Vatas) and making new Vatas in round shape up to 150 mm height using cement concrete 1:2:4 admixed with water proof compound Conplast X421 IC of Fosroc or equivalent company, curing etc. complete as directed.				
	Repolishing (Mirror) the existing Mosaic tiles/Kotah Sotne/Marble flooring with all labours and materials	152.00	SMT		
	TOTAL OF FLOORING-5				
6.00	ALUMINIUM / STEEL /WOODEN WORK				
6.10	P/F ALUMINIUM SLIDING WINDOW	1.00	SMT		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Providing and fixing powder coated aluminium Two track sliding shutter glass windows using aluminium sections of following sizes outer frame of 63.50 x 38.10 x 1.41 mm thick wt. 0.818 kg. Rmt. Top and sides frame 61.85 x 18 x 1.30 mm thick Wt. 0.659 Kg/Rmt bottom frame 61.85 mm x 31.75 x 1.20 mm thick Wt. 0.695 Kg/Rmt Shutter Top & Bottom 40.00 x 18.00 mm x 1.29 mm thick Wt. 0.456 Kg/Rmt Shutter Interlock 40.00x18.00+8.34 x 1.29 mm thick Wt. 0.547 Kg/Rmt Shutter Side (Handle) 40.00x18.00x1.29mm thick Wt.0.456 Kg/Rmt 5mm thick glass shall be framed in Alluminium section of 40.0 x 18.0 mm with necessary slidding channel and locking arrangement size of the shutter shall be as directed. Alluminium sections shall be of powder coated.				
	Rate includes all necessary fixing arrangements, Neoprine lining, filling the gaps the between AL. section and wall with sealent as directed. (Aluminium sections to be used shall be of Jindal make of Series 18 mm or equivalent section of Hindalco etc. as approved by the Architect in charge).There can be variation of plus or minus 10% in the thicknees and weight of aluminum sections.				
6.1.1	P/F MS GRILL IN WINDOWS	100.00	KG		
	Supplying Providing & Fixing M.S grill as per following description ,using Hollow pipe/ Angle section for vertical and horizontal section with providing 12 sq. mm M.S bars on both side at 4" C/C in between properly weld to steel section complate as directed including painting of synthetic enamel paint over a coat of primer etc. complete as directed.				
6.1.2	Removing verycarefully the existing windows with frame and shutter etc complete including stacking debris and reusable material as directed including carting away debris all levels.	120.00	SMT		
6.20	P/F ALUMINIUM VENTILATORS	7.20	SMT		
	Providing and fixing in position powder coated aluminiam frame size 63.50x38.10 x 1.28 mm thick with adjustable 100 mm wide and 4 mm thick glass louvers with mechanisim ventilators Sample of one ventiletor with adjustable mechanisim shall be got approved from Consultant/Bank.				
6.30	P/F FLUSH DOOR SHUTTER WITH BOTH SIDE LAMINATE FINISH WITHOUT FRAME	107.10	SMT		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Providing & fixing flush door shutter 30 mm thk BWP of Archid/Green Lam/Kit ply/Century or Approved ISI make , Water proof, thermosetting synthetic resin bond solid batten core of blockboard construction with 30 mm thick lipping of first quality teak wood battens on all edges of shutters with both side laminate as per architect's detail, supplying & fixing approved fixtures & fittings such as S.S hinges 4" long,tower bolts 8" long, handles 6" long ,Aldrops 12" Long, as per the details flush shutters are without frame (measurement will be out to out of shutter only). at all levels.[Approx Size 650/750 mmx2050mm				
	P/F PANTRY PLATFORM CUB BOARD SHUTTER	10	SQMT		
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 12 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface				
	Providing and fixing ready made 304 grade stainless steel Modular kitchen basket and accessories such as right angle basket (Plain Cup & Saucer, plant, Partition, Bottle rack, Thali, Cutlery) kitchen utensil basket, Dinner set basket, kitchen grain basket, Multipurpose basket as per site requirement including finishing (wherever required) and fittings. The same shall be fixed with necessary stainless steel nuts & bolts, Stainless Steel screws & telescopic channel etc. as per direction of Engineer-incharge.	28.00	SQMT		
	TOTAL OF ALUMINIUM/ STEEL-6				
7.00	MISCELLANEOUS WORK				
7.10	Charges for dismantling work including stacking debris and reusable material as directed including carting away debris all levels.				

Sr. No	Description	Quantity	Unit	Rate	Amount
[a]	Dismantling Brick wall/ Brick partition wall with or without plaster etc.	20.00	CMT		
[b]	Dismantling Stone rubble masonry wall with or without plaster etc.	10.00	CMT		
[c]	Dismantling very carefully the RCC Weather shade /slab/beam/ lintel etc with or without plaster Rate including cutting of existing reinforcement bars etc complete	10.00	CMT		
[d]	Removing of Existing Plaster and carting away debris	160.00	SMT		
[e]	Dismantling tile work in floors and roofs laid in cement mortar including stacking material	60.00	SMT		
[f]	Dismantling of sunken portion of toilet floor which include BBCC, PCC, Filling, Water Proofing up to slab top complete as directed. and carting away debris	27.60	SMT		
[g]	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking				
[i]	Of area 3 sq. metres and below	10.00	NO		
[ii]	Of area beyond 3 sq. metres	1.00	NO		
[h]	Dismantling of toilet accessories like Urinal, Wash Basin, W.C Pan, EWC, NT , Flush cock Bib Cock, Stop cock, GI/CI Pipe, PVC Pipe line of any dia etc. [Quote for 1 No Toilet]	10.00	LOT		
[j]	Dismantling ,removing and disposing off the M.S>Pipe.Angle/Channel Fabrication work of existing lift in lift well and machine room with all laours and materials	1.00	Job		
TOTAL OF MISC. WORK-7					
8.00	WATER SUPPLY WORK				
8.10	Providing and fixing concealed SDR-13.5 CPVC water supply line ISI approved mark, including all necessary specials, making zaries, making holes, cutting floors and making good after work is complete etc. complete as directed for. Pipe shall be Astral/Supreme make. at all levels				
[a]	- Do - for 15 mm dia line.	70.00	RMT		
[b]	- Do - for 25 mm dia line.	70.00	RMT		

Sr. No	Description	Quantity	Unit	Rate	Amount
[c]	- Do - for 38 mm dia line.	70.00	RMT		
[d]	- Do - for 40 mm dia line.	70.00	RMT		
8.1.1	Providing and fixing Open/concealed in structure SDR13.5 CPVC water supply line ISI approved mark, including all necessary specials, making zaries, making holes, cutting floors and making good after work is complete etc. complete as directed for. Pipe shall be Astral/Supreme make. at all levels				
[a]	- Do - for 20 mm dia line.	70.00	RMT		
8.20	Providing and fixing following fixtures of Jaquar make or its equivalent with chromium plated disce etc. complete for concealed pipe lines.as directed by Architect				
	Jaquar CP continental ISI Marked or equivalent make				
[a]	Providing and fixing Bib Cock of Catalogue No - 037	20.00	NO.		
[a1]	Providing and fixing Auto closing system Bib Cock of Catalogue No - PRS-CHR-043 (PRESS MATRIC)	1.00	NO.		
[a2]	Providing and fixing Auto closing system pillar Cock of Catalogue No - PRS-CHR-031 (PRESS MATRIC)	20.00	NO.		
[b]	Providing and Fixing Wall Mounted Sink Cock of Catalogue No - 347	10.00	NO.		
[c]	Providing and fixing concealed stop cock of Catalogue No -083	40.00	NO.		
[d]	Providing and fixing angle cock of Catalogue No -053	20.00	NO		
[d1]	Providing and fixing Auto closing system angle Cock of Catalogue No - PRS-CHR-077 (PRESS MATRIC)	1.00	NO.		
[e]	Providing and fixing 25 mm, chromium plated brass Flush valve Catalogue No - 1081A[Continental Range]. [Control Valve]	20.00	NO		
[f]	Providing and fixing 25 mm dia handle valve of approved Zoloto quality, for pipe lines etc complete as directed.	15.00	NO		

Sr. No	Description	Quantity	Unit	Rate	Amount
[f1]	Providing and fixing 15 mm dia handle valve of approved Zoloto quality, for pipe lines etc complete as directed.	5.00	NO		
[g]	Providing and Fixing brass chromium plated soap dish of approved make & quality etc. complete as directed. Sample shall be got approved from Bank/Architect.	20.00	NO		
[h]	Providing and fixing brass chromium plated Napking Ring of approved make etc. complete as directed.	20.00	NO		
[i]	Providing and fixing brass chromium plated towel rail of approved make for length between 50 to 60 cm and diameter of 20 mm including holders on both ends etc. complete as directed. Sample shall be got approved from Bank/Architect.	20.00	NO		
[j]	Providing and fixing Shower with Shower Arm 190mm Long Heavy Casted Body with Flange of Catalogue No - 483 & 491	20.00	NO		
[k]	Providing and fixing Health Faucet [No 573]	20.00	NO		
[l]	Providing and fixing wall mixer with telephone shower RANGE CON CHR 267KN	20.00	NO		
[m]	Providing and fixing telephone shower	1.00	NO		
8.30	Providing and Fixing Over head PVC Water tank 350/500/1000/2000/5000 Lit Cap. Of Sintex brand or equivalent making 120mm thick Brick masonry base with IPS on Top & side plastering including pipe connection complete as per the instruction the Engineer in charge at all levels.	5000.00	LITRE		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Cleaning of terrace/loft water storage/Under ground water tank (inside surface area) upto any capacity at all heights with coconut brushes, duster etc., removal of silt, rubbish from the tank and cleaning the tank with fresh water disinfecting with bleaching powder @ 0.5gm per litre capacity of tank including marking the date of cleaning on the side of tank body with the help of stencil and paint and disposing of malba all complete as per direction of Engineer-in-Charge. (The old date already written on tank should be removed with paint remover or black paint and if date is not written with the stencil or old date is not removed deduction will be made @ Rs. 0.10 per litre) (if during cleaning any GI fittings or ball cock is damaged that is to be repaired by contractor at his own cost and nothing extra will be paid on this account)	10000.00	LITRE		
	TOTAL OF WATER SUPPLY-8				
9.00	SANITARY WORK				
9.10	Providing & laying & fixing UPVC SWR drainage line concealed/open in the structure as per details and requirement with necessary specials such as Y-2, T-2, offset, plugs, bends and filling the joints with approved adhesive including cutting of wall floor and making good after the work is cover etc. all as above. Pipe shall be Prince/Supreme / Astral make at all levels.				
[a]	For 75 mm dia 6 Kg/Cm2	100.00	RMT		
[b]	For 100 m dia pipe 6 Kg/Cm2	150.00	RMT		
[c]	Providing laying & fixing concealed 38 mm dia P.V.C. waste water pipe line complete as directed.	70.00	RMT		
9.20	P/F RAIN WATER DISPOSAL PVC PIPE				
	Providing & Fixing 110 mm dia PVC pipe 4 Kg/Cm2 for rain water disposal including welding of joints, Fixing with M.s Clamps as per approved design from Architect details and as directed. This also includes fixing of shoe band. The item shall be measured in RMT and nothing extra shall be paid for the fitting. Pipes shall be Finolex/Prince/Supreme make at all levels.	70.00	RMT		

Sr. No	Description	Quantity	Unit	Rate	Amount
9.30	P/F UPVC NAHNI TRAP	40.00	NO		
	Providing and fixing UPVC Nahni Trap of Astral or Supreme. Rate includes cutting of floor/wall, necessary outlet pipe with necessary adhesive. Upto downtake pipe, Fixing PVC Jali of approved make complete as directed.				
9.40	P/F EWC FLOOR MOUNTED	10.00	NO		
	Providing and fixing EWC first quality Hindustan , Nycer, Cera or equivalent type snow white glazed vitrous china, EWC M Cera S1056101 [COVENTIONAL With Built in Jet] of with heavy type black or white plastic seat, lead with CP brass hinges, rubber buffers with fittings, brakcets, providing and fixing the 25mm dia flush cock of Jaquar Catalogue No -1081A[Continental Range] , 25 mm dia CP brass flush bend including cutting and making providing and fixing jet spray in EWC of approved ISI quality etc complete as directed.				
9.70	P/F WASH BASIN	20.00	NO		
	Providing and fixing first quality Snow white wash basin of 550 mm x 400 mm size, M Cera Cat No. S2040103 [Cornet] approved shape as per detail of approved make and quality such Cera/Hindustan/Nycer or equivalent with necessary specials, one chromum plated brass pillar cock 15 mm size of Jaquar make cat. No-021[Continental], one 15 mm CP angle valve of Jaquar Cat. No-053[Continental]chromium plated , connecting PVCpipes with nuts and all fittings, 32 mm dia CP waste coupling of Jaquar make cat. No-709 [ALLIED] and rubber plug heavy brackets with two coats of aluminium paint over brackets, and 32 mm dia CP brass bottle trap of Jaquar make cat. No-773[ALLIED] with necessary connection pipe wall flange etc. complete as directed				
9.7[a]	P/F TABLE TOP WASH BASIN	10.00	NO		

Sr. No	Description	Quantity	Unit	Rate	Amount
	Providing and fixing first quality Snow white wash basin of 445 mm x 445 mm size, M Cera Cat No. S2020134 [Casta] approved shape as per detail of approved make and quality such Cera/Hindustan/Nycer or equivalent with necessary specials, one chromum plated brass pillar cock 15 mm size of Jaquar make cat. No-021KN [Continental], one 15 mm CP angle valve of Jaquar Cat. No- 053KN [Continental] chromium plated , connecting PVC pipes with nuts and all fittings, 32 mm dia CP waste coupling of Jaquar make cat. No-709 [ALLIED] and rubber plug heavy brackets with two coats of aluminium paint over brackets, and 32 mm dia CP brass bottle trap of Jaquar make cat. No-773[ALLIED] with necessary connection pipe wall flange etc. complete as directed				
9.7.1	P/F MIRROR	10.00	NO		
	Providing and fixing 1'-6"x2'-0" Mirror above wash basin 6 mm thick Mirror of approved make shall be fixed with 2" long S.S. Studs, 4 Nos. complete as directed.				
9.80	P/F S.S SINK	10.00	NO		
	Providing and fixing stainless steel sink of Nirali make or approved equivalent make Standard rangers of overal size 17" x 17" (Bowl size 14"x14" x 7" depth in to in) including all necessary fittings such as CI brackets, overflow, rubber plugs, Cp brass chain, PVC connection and PVC waste pipe applying two coats of aluminium paint to the brackets etc. complete as directed.				
TOTAL OF SANITARY-9					

Note:

1.00 **Rate** includes Dismanttaling of exisiting toilet accessories

SUMMARY

1.00 EARTH WORK	Rs. _____
2.00 CONCRETE WORK	Rs. _____
3.00 MASONARY WORK	Rs. _____
4.00 FINISHING WORK	Rs. _____

Sr. No	Description	Quantity	Unit	Rate	Amount
5.00	FLOORING WORK		Rs.		
6.00	ALUMINIUM/STEEL WORK		Rs.		
7.00	MISCELLANEOUS WORK		Rs.		
8.00	WATER SUPPLY WORK		Rs.		
9.00	SANITARY WORK		Rs.		
TOTAL COST OF [1 TO 11]			Rs.		