

# **CANARA BANK**

## **INVITATION TO TENDER**

**ONLY FOR EMPANEL CONTRACTORS**

**OF**

**CIRCLE OFFICE KOLKATA**

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

**INSTRUCTION TO BIDERS**

**AND**

**GENERAL CONDITIONS OF CONTRACT**

**FOR**

**CIVIL & INTERIOR FURNISHING WORKS**

**AT**

**CANARA BANK – RAJARHAT BISHNUPUR BRANCH,**

**KOLKATA**

TENDER NO.: 04/22-23/SP

**NAME OF THE CONTRACTOR:** .....

.....

**ADDRESS:** .....

.....

SEAL & SIGNATURE OF TENDERER

## **NOTICE INVITING THE TENDER**

To,

M/s .....

Sealed tenders on item rate basis are invited from panel Contractors for **Furnishing Works at RAJARHAT BISHNUPUR Branch.**

Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **13-04-2022 till 21-04-2022.**

**Earnest Money Deposit : NIL**

**Period of completion : 20 days**

**Last date, time and place for Submission of tender : On or before 3:00 Pm, 21-04-2022 to  
The Divisional Manager,  
Premises & Estate section  
Canara Bank, Circle Office  
Kolkata**

**Time and date of opening of tender : 03.30 Pm on 21-04-2022**

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**Divisional Manager  
Premises & Estate Section  
Canara Bank, Circle Office  
Kolkata**

.....

Date: 16-04-2022

SEAL & SIGNATURE OF TENDERER

## **GENERAL RULES & INSTRUCTIONS TO TENDERERS**

### **Name of the work: Furnishing Works to be carried out at RAJARHAT BISHNUPUR Branch**

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

**GST WILL BE PAID EXTRA.**

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 20 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

### **TENDERS:**

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

**SEAL & SIGNATURE OF TENDERER**



The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

#### **AGREEMENT**

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

#### **EARNEST MONEY AND SECURITY DEPOSIT:**

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 3% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

#### **CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:**

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together whether the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents.

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipments and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, electrical wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

#### **LIQUIDATED DAMAGES:**

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

**.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.**

<b>TIME PERIOD FOR COMPLETION: 20 days from the date of award of work.</b>
----------------------------------------------------------------------------

SEAL & SIGNATURE OF TENDERER



## **FINAL PAYMENTS**

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

## **ESCALATION:**

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

## **CONTRACTORS EMPLOYEES:**

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

## **PAYMENTS:**

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement, after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

SEAL & SIGNATURE OF TENDERER



The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part thereof if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

#### **ARBITRATION:**

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or breach of the contract [other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sole arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as aforesaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as aforesaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

SEAL & SIGNATURE OF TENDERER

The arbitrator shall be deemed to have entered on the reference the date he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

**Date:**

**Signature of the Contractor  
With seal and address**

**SEAL & SIGNATURE OF TENDERER**



APPROVED MAKE OF MATERIALS		
1	False Ceiling / Channels	India Gypsum / Armstrong / Saint Gobain
2	Wood Frame Work / Wood Section : All Wood, Must be well seasoned, free from knots, other defects decay and defects due to handling and Transportation. Wherever necessary, provide with anti – termite Treatment.	Malaysian Sal / Kapoor
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach / White Cedar / CP Teak
4	Wood Preservative	STP Pentaphene Pale / Termiseal by PCI /
5	Fire Reterdant Paint	Industrial grads of Noble / Viper
6	BWR Ply (IS : 710)	Century / Green/ Sylvan/ Globe
7	Flush Door / BWP Block board (IS : 1659)	Century / Green / Sylvan / Globe
8	Laminate (1.0 mm thk.) (IS : 2046)	Green lam / Century mica / Sunmica (Aica) / Airolam
9	Door Closure ( Heavy Duty )	Godrej / Archi / Sterling ( DC 2000)
10	Floor Spring ( Heavy Duty )	Godrej / Archi / Sterling ( FS 3000 )
11	Door Lock ( Dead )	Godrej / Hafele /Hettich / Kich / Doorset / Yale
12	Door Handles	Godrej / Hafele /Hettich / Kich / Doorset
13	Drawer / Storage Handle	Godrej / Hafele /Hettich / Kich / Doorset
14	Drawer / Storage Lock ( Multipurpose )	Ebco / Hafele /Hettich /Doorset
15	Night latch	Godrej / 4C Acme
16	Screws	GKW / Nettle fold
17	Hinges	CIEF
18	Sliding Telescopic Drawer Channel	Ebco / Earl Behari / Efficient Gadjets
19	Cable Organiser	Ebco / Innofitt Systems ( CM 63.C )
20	Adhesive	Fevicol SH / Fevimate TL
21	Soft Board	Jolly Board
22	Vertical Blinds	Mac / Annums / Window Fashion
23	Glass	Modi /AIS / Saint Gobain
24	Paints (Synthetic Enamel / Acrylic Emulsion)	Asain Paints / Berger / ICI
25	PVC Flooring	Krishna Vinyl / Armstrong / Birla
26	Texture Paint	Spectrum
27	Glass	Modi / AIS / Saint Gobain
28	European WC / Washbasin	Hindware /Parryware
29	Sanitary Fittings	Jaquar / Essco Delux
30	G.I. Pipe	Tata ( Medium )
31	Cement	Ultratech / Lafarge / ACC
32	Footmat	Birla 3M / Approved Equivalent
33	Vitrified Tiles	Johnson / Naveen / Kajaria
34	Ceramic Tiles	Johnson / Naveen / Kajaria
35	All other items not covered above	As per sample approved by Employer/Consultant



PROPOSED REFURBISHING WORK FOR RAJAHAT BISHNUPUR BRANCH PREMISES (19776)					
CANARA BANK CIRCLE OFFICE KOLKATA					
I. SCHEDULE OF QUANTITIES FOR FURNISHING AND ALLIED CIVIL WORKS					
ITEM NO.	DESCRIPTION	QNTY.	UNIT	RATE RS. P.	AMOUNT RS. P.
1	<p>LOW HEIGHT PARTLY GLAZED/SOLID WOODEN PARTITIONS FOR UPS BATTERY RM &amp; CANTEEN &amp; WORKSTATION DIVIDER</p> <p>Supplying and erecting low height opaque partitions ( from 5'-00" 4' high) as per drawing and conforming to the following specifications :</p> <p><u>Basic Framework</u> : Well seasoned Malayasian sal wood sections, treated with two coats of wood preservatives, 50mm x 50mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions. Vertical Members shall be suitably anchored and at ceiling level to ensure rigidity.</p> <p><u>Skin Membrane</u> : 6 mm thick BWR grade plywood on each face with 4 mm grooves formed as per drawings/Instructions.</p> <p><u>Finishing</u> : 1.0mm thick laminate sheet of combination shades as per Instructions on both sides.</p> <p><u>Skirting</u> : 100mm high plywood skirting finished in 1mm thk. Laminate of combination shades as per instruction and drawing.</p> <p>Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc ( Materials of wiring conduits and switch boxes shall be separately paid for.)</p>	125	sqft.		
2	<p>FULL HEIGHT SOLID PARTITION ON BOTH SIDE LAMINATE</p> <p>Supplying and erecting full height opaque partitions ( from 8'-6" 10ft. high) as per drawing and conforming to the following specifications :</p> <p><u>Basic Framework</u> : Well seasoned Malayasian sal wood sections, treated with two coats of wood preservatives, 50mm x 50mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions. Vertical Members shall be suitably anchored and at ceiling level to ensure rigidity.</p> <p><u>Skin Membrane</u> : 6 mm thick BWR grade plywood on each face with 4 mm grooves formed as per drawings/Instructions.</p> <p><u>Finishing</u> : 1.0mm thick laminate sheet of combination shades as per Instructions on both sides.</p> <p><u>Skirting</u> : 100mm high plywood skirting finished in 1mm thk. Laminate of combination shades as per instruction and drawing.</p> <p>Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc ( Materials of wiring conduits and switch boxes shall be separately paid for.)</p>	100	sqft.		
1	<p>FULL HEIGHT PARTLY GLAZED WOODEN PARTITIONS</p> <p>Supplying and erecting full height partly glazed partition (varying from 8'6" to 10ft high) as per drawing and conforming to the following specifications :</p> <p><u>Basic Framework</u> : Well seasoned Malayasian sal wood sections, treated with two coats of wood preservatives, 50mm x 50mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions.</p> <p><u>Skin Membrane</u> : (Opaque portion upto 900mm from floor level with 1x6 mm thick BWR grade plywood on each face with 4x4mm grooves formed at the top layer as per drawings/Instructions.</p> <p><u>Glazing</u> : 8mm thick clear float glass fixed with continious White or Steam Beech wood glazing beads of approved shape ( finished 35x25 mm) all around, polished &amp; coated with NC lacquer finish. The rate should also include cost of decorative etching on one side of the glass.</p> <p><u>Finishing</u> : 1.0mm thick laminate sheet of same or combination shades on both sides as per Instructions.</p> <p><u>Edge Moulds</u> : All free top/end surfaces shall have polished white or steam beech wood moulds of apprived shape ( from 80x 25mm sections) with LC lacquer in mat finish.</p> <p><u>Skirting</u> : 100mm high x 12 mm thick polished white or steam beech wood skirting on both faces with NC lacquer in Matt finish.</p> <p>Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc ( Materials of wiring conduits and switch boxes shall be separately paid for.)</p>	190	Sq.Ft.		

3	<p><b>WORKSTATIONS</b></p> <p>Providing, fixing and fitting in position free standing work station made of 19 mm thk. BWP Ply + 1.0 mm. Laminate of approved make and colour for the table top, sides &amp; front apron. The table is supported on the left side by a 1'-6" wide &amp; 2'-0" deep drawer unit consisting of a tea tray, one drawer &amp; a shuttered cabinet all in 1.0 mm thk. laminate finish and Ply partition on the right side. The table is provided with a readymade metallic CPU Holder with swivel facility, (CPU HL SW / INNOFIT systems or similar) &amp; readymade key board drawer of engineering Plastics (KD 575 P MT/ INNOFIT System or similar) shall be suspended below the table top. Quoted rates shall also include cost of polished white or steam beech wood moulding ( finished 40x20 mm section ) to edges of table top; polished white or steam beech wood lipping (6mm thick) to free edges of block board/ plywood surfaces; approved drawer - slides, concealed type auto-closing shutter hinges and locks with keys in duplicate; other necessary hardware and accessories including satin finish S.S. handles, knobs and wire - managers etc. of approved quality &amp; the table top is finished with 5mm thick glass.</p> <p>A) Approx. size of 1800 x 900 x 750 mm</p> <p>B) Approx. size of 1500 x 750 x 750 mm</p>	1 5	No. No.		
4	2ft. Wide Running Table for Canteen area for sitting arrangement of 6persons.	7.5	RFT		
5	<p><b>SIDE CREDENZO</b></p> <p>The side unit is of size 3' (L) X 1'-4" (W) X 2'-6" (H) consisting of a top row of two sets of 4" high drawers with cabinets below with sliding shutters, made of 19mm thick BWR grade block boards all finished in 1.0mm thk.laminate. Exposed block board surfaces shall be finished with 1.00mm laminate sheet of approved shade and make. Inner faces of sliding shutters shall be polished in approved color. Free edges of block board shall have polished white or steam beech wood half round moulds ( out of 20 x 20 mm sections). Inner faces of cabinet units shall be polished in approved shade quoted rates shall include cost of necessary hardware . Viz handles, locks with keys in duplicate, etc.</p>	6	Nos.		
6A	<p>Cash Counter and front Apron &amp; Front Glazed partition</p> <p>Providing fixing &amp; fixing 2'-6" wide &amp; 2'-6" high staff working top made of 18mm thick BWP block board of approved make finished with 1.0 mm laminate of approved make &amp; shade. The customer transaction top shall be 1'-6" wide projecting 6" on the customer side at a height of 1' above the staff working counter thus making a total height of 3'-6". The customer top is made of 3/4" thk.Granite top(Black galaxy) placed on 18mm thick BWP blockboard which is cut &amp; shaped with edges round polished. Below the working top/counter will be 1'-4" wide drawer cum shuttered cabinet unit on one side &amp; metallic CPU trolley on the other side with key board tray with slide channels &amp; foot rest in between for each of the cash counters specs same as Banking Counters. All the specification of the drawer unit/CPU trolley is same as that of Work station in Item no 6. Below the Transaction top the portion which is overlapping with the working counter of 10" deep will be covered by 2 sets of sliding shutters with a intermediate shelf with all locking arrangement for keeping currency notes. Both the staff working top &amp; the transaction top is rested &amp; supported together by a front Apron or Double skin partition which is similar in design and specification as that of Banking counters. There will be necessary grooves between the two different decorative laminates as shown in the detail drawing &amp; as directed. The counter will be provided with wire manager. The front portion of cash cage above the transaction top (from 3'-6" to 7'-0" height) will be provided with 2 nos. of 12 mm thick float glass leaving a gap of 2" between the two glass panes so as to allow conversation between the customer &amp; the cashier &amp; a cut out of 8" x 4" at the central bottom part of each of the transaction top.</p>	5	Rft.		



6B	<p>Providing supplying &amp; fixing of Cash Cage Side &amp; rear Partitions with door</p> <p>The intermediate/side/rear partition with doors between Cash Cabins as Partly glazed Wooden Partition upto 7'-0" height with the following specification:</p> <p><u>Basic Framework</u>: Well seasoned Malaysian sal wood sections, treated with two coats of wood preservatives, 50 mm x 50mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions. Vertical Members shall be suitably anchored at floor level to ensure rigidity.</p> <p>Exposed frame members in the glazed portions shall have wider spacing ( approx. 1800 mm clear ) as per instructions.</p> <p>Exposed members shall be finished with 1.0mm thick laminate sheet of same or combination shades, over 6 mm BWR grade plywood including 4 mm grooves at locations as per instruction.</p> <p><u>Skin Membrane</u>: (Opaque portion upto 1050 mm(3'-6") from floor level with 6 mm thick BWR grade plywood on each face with 4x4mm grooves formed as per drawings/ instructions.</p> <p><u>Finishing</u>: 1.0mm thick laminate sheet of combination shades as per instruction and drawing.</p> <p><u>Skirting</u>: 100mm high plywood skirting finished in 1mm thk. Laminate of combination shades as per instruction and drawing.</p> <p><u>Glazing</u>: Strips of 8 mm thick clear float glass fixed with continuous White or Steam Beech wood glazing beads of approved shape ( finished 35x25 mm) all around, polished &amp; coated with NC lacquer finish. The rate should also include cost of decorative etching on one side of the glass.</p> <p>Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc ( Materials of wiring conduits and switch boxes shall be separately paid for.)</p> <p>All exposed edges of the BWP ply &amp; blockboard are to be finished with 12 mm thk. Rubber wood lipping which are to be polished as directed.</p> <p>Provision for extra wooden frame work of same section for intermediate glazing to be included in the rate.</p> <p>There will be provision for small trays/windows for transferring of small copy either from the banking area to the cash cabins or between the cash cabins as directed by the architect.</p> <p>The cost of all fittings of the door :handle locks, aldrops handles, hydraulic door closer, night latch all of approved make of the doors wherever required in the cash section to be included.</p>	140	SQFT.		
7	<p>P/F/F Full height /Low height filing cabinet/Over head Cabinet 1'-6" deep made of 18mm BWP blockboard with intermediate shelves. The back of the cabinet to be made of 6mm thk. BWP ply fixed on the wall.</p> <p>There will be one horizontal division and vertical dividers of same block board at approx. 3ft. apart with sliding shutters for low height &amp; overhead cabinet.</p> <p>All exposed surfaces &amp; the shutters are finished with 1.0 mm thk. decorative laminate of approved make &amp; shade. Cost of all fittings like brass hinges, godrej locks, magnetic hinges, godrej locks, magnetic catches, steel matt finish "D" type handles shall be inclusive.</p>	75	Sqft		
8	<p>FLUSH DOOR(SOLID/PARTLY GLAZED)</p> <p>Supplying and fixing in position overall 37mm thick solid core hot pressed phenol formaldehyde bonded approved flush door shutter finished door shutter finished with 1.0mm thick laminate sheet of approved shade and quality on both sides of the door shutter including cost of hardware fittings e.g. mortice locks, brass hinges, hydraulic door closer, S.S. door handles etc. of approved make and quality.</p>				
A	<p>Partly glazed door having 8mm thk. float glass 3ft. from finished floor level upto 6'-6"</p> <p>Average size of shutter (D1) : 3' 0"x 7'-0" for B.M.'s Room &amp; Passage door</p>	3	No.		
B.	<p>Solid Flush Doors with vision glazed panel(1'x1')</p> <p>Average size of shutter (D1) : 3' 6"x 7'-0"</p>	2	No.		
C	<p>Average size of shutter (D2) : 2' 6"x 4'-0"(swing door)</p>	3	No.		
9	<p>PIN-UP NOTICE BOARD</p> <p>Providing, fitting in position pin-up board made of soft cork board finished with the fabric as approved, matching with the colour scheme of the banking hall with a R.W. moulding all around the edges.</p>	10	Sqft.		
10	<p>WRITING LEDGE CUM CHEQUE DROP BOX</p> <p>Providing &amp; fixing in position writing ledge of size: 3'(l) x 1'(w) fabricated out of 19mm thk BWP blockboard, 1mm laminate finished and 12mm</p>	1	NO.		

	<p>&amp; 10mm bevelled, machine polished glass as indicated fixed to the pillar. Writing ledge will be having glass divider made out of 10mm thk glass for keeping deposit slips. White beach / white cedar flipping with natural polish is to be provided as directed.</p> <p>Below the shelf after a 6" gap is place a cheque drop box of size :2'x 2'x 6" with 1" wide slit for inserting cheques made of 19mm thk BWP blockboard, 1mm laminate finished. (At the branch and ATM 1no. each)</p> <p>Item is to be completed in all respects as per design, direction / approval of the Architect.</p>				
11	<p><b>PANELLING ON THE PILLAR WITH LAMINATE FINISH</b></p> <p>Wall Panelling / column encasing ( upto False ceiling height ) works as per Branch Ambience Standardised manual of the Bank conforming to the following specifications :</p> <p>Shall be made up of 2"x1" salwood framework with 12mm thk ply back up.</p> <p>The framing shall be fixed at intervals of 2'0" c/c horizontally and vertically.</p> <p>Shall be made up of 19mm thk plywood as per site conditions.</p> <p>The framing shall be fixed with 6mm thick ply to form 4mm grooves finished with 1mm thick approved color laminate of approved make at every 1ft interval. The skirting shall be finished with 3" wide 1.00mm approved bi color laminate of approved make.</p> <p>Quoted rates shall include all necessary materials, accessories and labour and also allow provisions for electrical/telephone/computer wiring conduits &amp; switch boxes etc. complete with necessary jacking /thickening of panels to accommodate conduits/ switch boxes. (Materials for wiring conduits and</p>	125.0	SQFT		
12	<p><b>WINDOW SCREEN</b></p> <p>Providing, fitting in position 100mm Vertical blinds made of best quality PVC coated polyester fabric of approved make &amp; shade &amp; to be tailored to the size of the window.</p>	130	SQft		
13	<p><b>GYPSUM BOARD FALSE CEILING (INCLUDING DROP)</b></p> <p>Providing and fixing in position dropped ceiling in two levels including vertical surfaces in between two level of ceiling surface with 12.5mm thick tapered edge gypsum board conforming to IS 2095 including providing and fixing of framework made of special sections power pressed from MS Sheet and galvanised in accordance with Zinc coating 600 as per IS 277 and costing of angle cleats of size 25mm wide x 16mm thick with flanges of 22mm and 37mm at 1200mm center to center one flange fixed to the ceiling with dash fastner 12.5mm dia with flanges of 22mm and 37mm at 1200mm center to center one flange fixed to the ceiling with dash fastner 12.5mm dia x 40mm long with 6mm dia bolts to the angle hangers of 25x25x5 mm of required length and other end of angle hanger being fixed with nut and bolts to G.I. Channels 45mm x 15mm x 0.9mm running at the rate of 12mm centre to centre to which the ceiling section 0.5mm thick bottom wedge of 08mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm center to centre shall be fixed in a direction perpen - dicular to G.I. Channel with connecting clips made out of 2.64 mm dia x 230mm long G.I. Wire at every junction including fixing the gypsum board with ceiling section and perimeter channel.</p>	200	Sqft.		



	<p>The perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm center to center with 25mm long drive all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the gypsum board with recommended filter, paper tapes, finisher and two coats of primer suitable for gypsum board as per manufactures specification and also include the cost of making openings for light fittings grills, diffusers, cutouts made with frame of perimeter channels of the Engineer-In-Charge &amp; including the cost of Plastic Emulsion paint.</p> <p>Rates to include cost of making openings for ceiling mounted electrical fittings/air-conditioning accessories and also making of openings of size 2'x2' with door for electrical servicing as per instructions.</p>			
14	<p><b>FALSE CEILING (Armstrong)</b></p> <p>Providing &amp; fixing in position false ceiling in Armstrong Make 600 x600 mm x 15/16 mm Dune Microlook tile with Regular Black reveal framework as specified by Armstrong Co. with suspenders wherever required.</p> <p>Making necessary framework for A.C ducting, if any and Necessary cutouts for diffusers and light fittings, taping and finishing to proper line &amp; level, including making grooves and trap doors for A.C unit in 18mm thk M.R. Grade Plywood with Stainless Steel hinges &amp; locks with moulding 1" x 1" for edges.</p>	1,060	SQFT	
15	<p>Repair &amp; replacement of existing broken Ceramic flooring tiles due to dismantling of the existing counters and partitions and making good all damages</p>	300	Sqft	
16	<p><b>PLASTIC EMULSION PAINT WORK</b></p> <p>Providing and applying minimum two coats of acrylic emulsion paint of approved shade &amp; make on a base coat of necessary primer including necessary scrapping of old surface &amp; new surface preparation in the walls under false ceiling.</p>	4500	SQFT	
17	<p><b>SYNTHETIC ENAMEL PAINT ON STEEL WINDOWS/WOODWORK/ROLLING SHUTTER</b></p> <p>Providing and painting on wooden, steel or plastered surfaces with two coats of Synthetic Enamel paint of approved shade &amp; brand over a coat of primer of approved quality after sand papering the old/new surface to give an even uniform shade.</p>	1200	SQFT	
19	<p><b>ALUMINIUM HEAVY DUTY FRONT GLAZED DOOR CUM FIXED GLAZING</b></p> <p>Providing and fixing Main Entrance door cum fixed glazing made of fully glazed &amp; heavy duty aluminium sections (14 Gauge) frame at the main entrance as shown in the drwng. Glazing shall consist of approved make heavy duty 6" x 2" sections for the top &amp; bottom rails and 2" x 2" sections for the vertical styles. 10mm thk. approved make clear float glass shall be provided and fixed in the above framing. Rate shall include necessary etching film / LOGO, and any necessary hardware items. (Heavy Duty 6" &amp; 2" thick frames(14 Gauge) - approved make). The aluminium shall be made Anodised Sections.</p>	45	SQFT	
20	<p><b>SHIFTING OF OLD FULL HEIGHT CABINETS &amp; ALMIRAHs FROM THE EXISTING POSITIONS TO NEW POSITIONS WITHIN THE PREMISES AND PLACING THEM IN POSITION AS DIRECTED.</b></p>	1	JOB	
21	<p><b>DISMANTLING OF EXISTING PARTITIONS ,PANELLING &amp; RUNNING COUNTER AND REMOVAL OF THEM AS PER LOCAL MUNICIPALITY NORMS</b></p>	1	JOB	
TOTAL				