

BOQ - FURNISHING WORKS AT "REGIONAL OFFICE" CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
1.0	Partitions				
a.	P1-(Ht. 8'-6") (Chief Manager Partition)	1000.00	Sq.Ft.		
	Frame Work- Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically.				
	Plywood- 6.0mm thick BWR Grade IS303:1998				
	Laminate-1.0 mm thick over Plywood (Approved Colour Scheme)				
	(The necessary additional frame/opening in frame work for Electrical Conduits, Electric Modular Box, AC Grills, AC Duct etc. provide as per site requirements & aluminium member of partition shall be fixed rigidly to the floor, columns and beams). All exposed edges of Plywood shall be fixed with 1/8" C.P. Teak Lipping with natural/white colour polish. The door is also inclusive, made with 32mm board (flush door) along with necessary fittings like SS finish 100mm hinges, fittings. The glass shall be 6mm th.clear float glass to be fixed at 3' height, complete with itching as per design .The full height partition includes the Glass wool layer for sound proof cabin . The measurement purpose the partition will be up to ceiling height but measurement will be only for visible area .				
	Door Size/ Design/ Type - As per drawing/instruction of Bank/Architect including Door Closure / Door Lock / Mortise Lock / Night Latch of Godrej or equivalent make.				
b.	P5-(Low Ht. 4'-6") (Solid Partition)	1650.00	Sq.Ft.		
	(Side partition for SWO, Flap Door & Other counters)				
	As per other Specification partition P1 / Low ht. partition shall be 3'-6" high wooden and 1'-0" high 10 mm glass work on top. Item shall also include 3" high skirting				
c.	P6-(Low Ht. 4'-6") (Solid Wicket Gate) with inner side locking arrangements	50.00	Sq.Ft.		
	Ply Wood-19.0mm thick BWR Grade commercial board IS303:1998 for frame work.				
	Laminate- Specification as per partition P1				
d.	AL. PARTITION :- Providing and fixing powder coated aluminium partitions comprising approximately 1.75" X 1.75" size aluminium sections as per shade approved by bank . The thickness of the aluminium section should not be less than 1.5 mm. The partition shall have 10 mm thk clear glass. The rate should be inclusive of all fittings like neoprin rubber beading, springs etc. complete. Height of lower glass panel to be 7' and rest to be in upper panel.	30.00	Sq.Ft.		
e.	GLASS DOOR : Providing and fixing full Glass door with 12 mm thick toughened glass fixed on 85 to 100 mm top and bottom power coated (as approved) aluminium panels. The item shall have heavy duty floor spring (80 Kg.) of approved make (Godrej code no. 8293),SS D- type 25 mm dia - 300 long door handles (Product code no. 8699 of Godrej), locking arrangement etc. complete with other necessary hardwares required for proper functioning of the door.	80.00	Sq.Ft.		

BOQ - FURNISHING WORKS AT "REGIONAL OFFICE" CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
g	MORTICE LOCK :: P/F of 7" mortice lock with handle set of godrej make. It shall have 6brass lever, suitable for reight or left handed door shutter, inside or outside opening. The keyless latch shall be opened from either side of the door by turning th handle, itshall work as a latch from inside at the turn of a button and as a lock operable with a key from outside. The item should be complete in all respect including fixing in place to the satisfaction of the Bank.(Fusion rossette-2-c of godrege make code 7729) including lock body (code 8448) and 2 c -70mm cyleinder (code 8452)	15.00	Nos		
h	HYDRAULIC DOOR CLOSERS :: P/F of hydraulic door closer godrej make, it shall incorporate, body manufactured from aluminium extruded alloy machined to extreme accuracy, rack and pinion made of machined alloy steel duly heat - treated, adjustable closing speed, suitable for right hand and left hand opening door, suitable for door / frame mounting, suitable for door weight up to 60 kgs, suitable for 180/100 degree door opening. All complete in all respect to the satisfaction of the Bank, item is inclusive of fixing of the door closures.	15.00	Nos		
i	S/F door stopper	18.00	Nos		
2.0	Wooden Tables/Counters				
a.	T1- DGM Table	1.00	No.		
	(including side unit & 12 mm thick glass on top of table)				
	Size- 8'-0" X 3'-5" X 2'-6"				
	Side Storage- 3'-6" X 2'-6" X 1'-6"				
	Ply Wood- 19.0mm thick BWR Grade board IS303 for frame work				
	Supports- 2" X 2" & 2" X 1.5" CP Teak Wood and beading Patti				
	Drawer- 1'-6" wide two drawers and one shutter below the drawers at left side of the table				
	Laminate- 1.0mm thick approved colour				
	Key Board Tray- 19.0mm thick BWR Grade commercial board IS303 for frame work with 1mm laminate the unit shall have guides, sliding units etc.				
	CPU Metal Stand, Twin Telescopic Drawer Fittings, Brass Powder Coated Wire Manager				
	Foot Rest- 12.0mm thick BWR Grade Ply tapered box finish with polish				
	Handle-Brush finish stainless steel, Brass Ball Catches				
	All exposed surfaces to be finished with 1mm thick laminate of approved make & shade and all exposed edges of table top & verticals to have T.W. lipping of appropriate/approved size & shape. All visible wood should be polished with melamine polish. All inner surfaces painted with enamel paint with two and more coast after applying the primer coat. The board of 19mm thick to be used should be termite resistant. The item shall also include 10 mm glass on table top.				
b.	T2- AGM Table	1.00	No.		
	Size- 7'-0" X 2'-6" X 2'-6"				
	Other specifications as per Table T1				
	The item shall also include 10 mm glass on table top.				
c.	T3- CM Table	3.00	No.		
	Size- 6'-5" X 2'-6" X 2'-6"				
	Other specifications as per Table T1				
	The item shall also include 10 mm glass on table top.				
d.	T4- Officer Table	40.00	No.		
	Size- 5'-0" X 2'-6" X 2'-6"				

BOQ - FURNISHING WORKS AT "REGIONAL OFFICE" CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
	Other specifications as per Table T1 but cubical type officer's table as per Design				
e.	Supply and fixing of Conference table made out of 19mm BWP board and finished with 1.0 mm approved laminate Other specifications as per Table T1 but 2'-0" wide provisions for microphone and its wiring etc. complete	72.00	Rft.		
d.	T3- Centar Table	2.00	No.		
	Size- 4'-0" X 3'-0"				
	Other specifications as per Table T1				
3.0	Storage Unit				
a.	S1-Storage (Low Height - 2'-6"/4'-0")	735.00	Sq.Ft.		
	Ply Wood- 19.0mm thick BWR Grade IS303 for sides, top, shelf & door and 6.0mm IS 303 for Backside				
	Shelf- 19.0mm thick BWR Grade IS303 ply				
	Depth- 1'6"				
	Handle- Brush finish stainless steel				
	Lock- As approved				
	All visible teak/ cedar wood should be polished with spirit polish. All inner surfaces painted with enamel paint with two and more coats after applying the primer coat. The board of 19mm thick to be used should be termite resistant.				
b.	S2-Storage (Meter/ Electrical panel box) with air louvers	50.00	Sq.Ft.		
	Size- Length & Width as per site and Depth- 1'10" to 2'0"				
	Other specification as per Low Height Storage S1				
4.0	False Ceiling Works (Gypsum)	3100.00	Sq.Ft.		
	Providing & fixing with necessary scaffolding frame in 22 gauge GI channel /angle, placed at appropriate grid, fixed to RCC slab, beam, wall etc. with fasteners /screws finished with 12.0mm Gypsum sheets joints covered with POP slurry/tape. Rates shall include painting (One Coat of putty, one coat of primer coat and two coats of acrylic paint). Rates shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills, vertical drop up to 1'6" etc. item includes finishing with painting base work and finishing in plastic paint of white colour. (Note - : No extra payment shall be given for design)				
5.0	False Ceiling Works (Armstrong)	2900.00	Sq.Ft.		
	Providing & Fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15.0mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drg. Rate shall be inclusive of providing the total system with installation etc. Contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations. Rate shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills etc.(Note - : No extra payment shall be given for design)				

BOQ - FURNISHING WORKS AT "REGIONAL OFFICE" CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
6.0	Miscellaneous Works				
a.	Panelling on Wall & Column With Aluminium Frames	2650.00	Sq.Ft.		
	Providing and fixing panelling on wall. Both ways horizontally and vertically on the wall / with Aluminium Sections of 2"x1" as directed by Bank / Architect. This framing would be covered by 6mm thk. Ply and overit finished with 1mm thick laminate all complete.				
	Plywood -6.0mm thick BWR Grade IS303:1998				
	Laminate -1.0 mm thick (Approved Colour Scheme)				
e.	Suggestion Box	2.00	Nos		
	providing & fixing Acrylic Make with shutter, lock and white mat film finish, complete as per instruction of Bank's Engineer/Architect.				
f.	Pin-up Board (Size- 4'x3' - 2nos.)	24.00	Sq.Ft.		
	Providing and fixing in position pin-up board (as per design). It shall have 12.0mm thick soft board (Make - Cellotex or equivalent) laminated with carpet cloth (Make – Unitex, Type – Utsav) as/shade approved by the Architect. It shall have backing with 12.0mm thick marine plywood. The fixing shall include for expansion bolts, cleats, clamps, bolts, nuts, screws, rivets and other anodized accessories, all complete up to the satisfaction of the Architect. All the exposed edges of soft board shall be provided with teakwood beading of section 50mm x 19mm with rebate of 30mm x 6mm. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of Bank Engineer/Architect.				
h.	Vertical blinds				
	Providing and fixing of vertical blinds made out of 100mm wide (Scotch - Guarded) fabric louvers (as per shade approved by the Architect) including Head rail, control unit carries, Tilter, Traverse cord, Tilt rod bottom Machanism, Installation Bracket etc. all Complete.	460.00	Sq.Ft.		
i.	Supply & Placing of 7- seater corner type soffa in waiting area of ground floor made out of wooden frame, spring, canvas etc in sit & back, 100mm foam in sheet & 75mm in back of 40 density and soffa cloth as approved by bank or architect(cloth should not less than 400/ metre). The item shall also include polishing etc complete.	7.00	Seat		
j.	Supply & placing of 3-seater's soffa in D.G. M., A.G. M. Cabins & waiting area of first floor made out of wooden frame, spring, canvas etc in sit & back, 100mm foam in sheet & 75mm in back of 40 density and soffa cloth as approved by bank or architect(cloth should not less than 500/ metre). The item shall also include polishing etc complete.	3.00	Nos		
h.	Supply & fixing of pin-up board of size (3'-0"X 1'-6") on front partition of cubical tables.	38.00	No.		
7	Dismentling of Old furnishing work.	1.00	Job		

BOQ - FURNISHING WORKS AT "REGIONAL OFFICE" CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
BOQ - FURNISHING WORKS AT RAH CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
1.0	Partitions				
a.	P1-(Ht. 8'-6") (Chief Manager Partition)	440.00	Sq.Ft.		
	Frame Work- Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically.				
	Plywood- 6.0mm thick BWR Grade IS303:1998				
	Laminate- 1.0 mm thick over Plywood (Approved Colour Scheme)				
	(The necessary additional frame/opening in frame work for Electrical Conduits, Electric Modular Box, AC Grills, AC Duct etc. provide as per site requirements & aluminium member of partition shall be fixed rigidly to the floor, columns and beams). All exposed edges of Plywood shall be fixed with 1/8" C.P. Teak Lipping with natural/white colour polish. The door is also inclusive, made with 32mm board (flush door) along with necessary fittings like SS finish 100mm hinges, fittings. The glass shall be 6mm th.clear float glass to be fixed at 3' height, complete with itching as per design ..The full height partition includes the Glass wool layer for sound proof cabin . The measurement purpose the partition will be up to ceiling height but measurement will be only for visible area .				
	Door Size/ Design/ Type - As per drawing/instruction of Bank/Architect including Door Closure / Door Lock / Mortise Lock / Night Latch of Godrej or equivalent make.				
b.	P5-(Low Ht. 4'-6") (Solid Partition)	500.00	Sq.Ft.		
	(Side partition for SWO, Flap Door & Other counters)				
	As per other Specification partition P1 / Low ht. partition shall be 3'-6" high wooden and 1'-0" high 10 mm glass work on top. Item shall also include 3" high skirting				
c.	P6-(Low Ht. 4'-6") (Solid Wicket Gate) with inner side locking arrangements	30.00	Sq.Ft.		
	Ply Wood- 19.0mm thick BWR Grade commercial board IS303:1998 for frame work.				
	Laminate- Specification as per partition P1				
e.	GLASS DOOR : Providing and fixing full Glass door with 12 mm thick toughened glass fixed on 85 to 100 mm top and bottom power coated (as approved) aluminium panels. The item shall have heavy duty floor spring (80 Kg.) of approved make (Godrej code no. 8293),SS D- type 25 mm dia - 300 long door handles (Product code no. 8699 of Godrej), locking arrangement etc. complete with other necessary hardwares required for proper functioning of the door.	30.00	Sq.Ft.		
g	MORTICE LOCK :: P/F of 7" mortice lock with handle set of godrej make. It shall have 6brass lever, suitable for reight or left handed door shutter, inside or outside opening. The keyless latch shall be opened from either side of the door by turning th handle, itshall work as a latch from inside at the turn of a button and as a lock operable with a key from outside. The item should be complete in all respect including fixing in place to the satisfaction of the Bank.(Fusion rosette-2-c of godrege make code 7729) including lock body (code 8448) and 2 c -70mm cyleinder (code 8452)	3.00	Nos		

BOQ - FURNISHING WORKS AT "REGIONAL OFFICE" CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
h	HYDRAULIC DOOR CLOSERS :: P/F of hydraulic door closer godrej make, it shall incorporate, body manufactured from aluminium extruded alloy machined to extreme accuracy, rack and pinion made of machined alloy steel duly heat - treated, adjustable closing speed, suitable for right hand and left hand opening door, suitable for door / frame mounting, suitable for door weight up to 60 kgs, suitable for 180/100 degree door opening. All complete in all respect to the satisfaction of the Bank, item is inclusive of fixing of the door closures.	3.00	Nos		
i	S/F door stopper	4.00	Nos		
2.0	Wooden Tables/Counters				
a.	T1- CM Table	2.00	No.		
	(including side unit & 12 mm thick glass on top of table)				
	Size- 5'-0" X 3'-0" X 2'-6"				
	Side Storage- 3'-6" X 2'-6" X 1'-6"				
	Ply Wood- 19.0mm thick BWR Grade board IS303 for frame work				
	Supports- 2" X 2" & 2" X 1.5" CP Teak Wood and beading Patti				
	Drawer- 1'-6" wide two drawers and one shutter below the drawers at left side of the table				
	Laminate- 1.0mm thick approved colour				
	Key Board Tray- 19.0mm thick BWR Grade commercial board IS303 for frame work with 1mm laminate the unit shall have guides, sliding units etc.				
	CPU Metal Stand, Twin Telescopic Drawer Fittings, Brass Powder Coated Wire Manager				
	Foot Rest- 12.0mm thick BWR Grade Ply tapered box finish with polish				
	Handle-Brush finish stainless steel, Brass Ball Catches				
	All exposed surfaces to be finished with 1mm thick laminate of approved make & shade and all exposed edges of table top & verticals to have T.W. lipping of appropriate/approved size & shape. All visible wood should be polished with melamine polish. All inner surfaces painted with enamel paint with two and more coat after applying the primer coat. The board of 19mm thick to be used should be termite resistant. The item shall also include 10 mm glass on table top.				
d.	T4- Officer Table	10.00	No.		
	Size- 5'-0" X 2'-6" X 2'-6"				
	Other specifications as per Table T1 but cubical type officer's table as per Design				
3.0	Storage Unit				
a.	S1-Storage (Low Height - 2'-6"/4'-0")	190.00	Sq.Ft.		
	Ply Wood- 19.0mm thick BWR Grade IS303 for sides, top, shelf & door and 6.0mm IS 303 for Backside				
	Shelf- 19.0mm thick BWR Grade IS303 ply				
	Depth- 1'6"				
	Handle- Brush finish stainless steel				
	Lock- As approved				
	All visible teak/ cedar wood should be polished with spirit polish. All inner surfaces painted with enamel paint with two and more coats after applying the primer coat. The board of 19mm thick to be used should be termite resistant.				

BOQ - FURNISHING WORKS AT "REGIONAL OFFICE" CANARA BANK AGRA					
S.NO	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
4.0	False Ceiling Works (Gypsum) Providing & fixing with necessary scaffolding frame in 22 gauge GI channel /angle, placed at appropriate grid, fixed to RCC slab, beam, wall etc. with fasteners /screws finished with 12.0mm Gypsum sheets joints covered with POP slurry/tape. Rates shall include painting (One Coat of putty, one coat of primer coat and two coats of acrylic paint). Rates shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills, vertical drop up to 1'6" etc. item includes finishing with painting base work and finishing in plastic paint of white colour. (Note - : No extra payment shall be given for design)	410.00	Sq.Ft.		
5.0	False Ceiling Works (Armstrong) Providing & Fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15.0mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drg. Rate shall be inclusive of providing the total system with installation etc. Contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations. Rate shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills etc.(Note - : No extra payment shall be given for design)	500.00	Sq.Ft.		
6.0	Miscellaneous Works				
a.	Panelling on Wall & Column With Aluminium Frames Providing and fixing panelling on wall. Both ways horizontally and vertically on the wall / with Aluminium Sections of 2"x1" as directed by Bank / Architect. This framing would be covered by 6mm thk. Ply and overit finished with 1mm thick laminate all complete. Plywood -6.0mm thick BWR Grade IS303:1998 Laminate -1.0 mm thick (Approved Colour Scheme)	200.00	Sq.Ft.		
e.	Suggestion Box providing & fixing Acrylic Make with shutter, lock and white mat film finish, complete as per instruction of Bank's Engineer/Architect.	2.00	Nos		
f.	Pin-up Board (Size- 4'x3' - 2nos.) Providing and fixing in position pin-up board (as per design). It shall have 12.0mm thick soft board (Make - Cellotex or equivalent) laminated with carpet cloth (Make – Unitex, Type – Utsav) as/shade approved by the Architect. It shall have backing with 12.0mm thick marine plywood. The fixing shall include for expansion bolts, cleats, clamps, bolts, nuts, screws, rivets and other anodized accessories, all complete up to the satisfaction of the Architect. All the exposed edges of soft board shall be provided with teakwood beading of section 50mm x 19mm with rebate of 30mm x 6mm. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of Bank Engineer/Architect.	24.00	Sq.Ft.		
h.	Supply & fixing of pin-up board of size (3'-0"X 1'-6") on front partition of cubical tables.	10.00	No.		
7	Dismantling of old furnishing work.	1.00	Job		
TOTAL (excl. GST) (Rs.)					
G. TOTAL (Including RO and RAH) Including GST					