

ANNEXURE - 13

‘MASKED PRICE BID’ FORMAT TO BE SUBMITTED ALONG WITH TECHNICAL BID

Sl No	Item Description	Tentative Quantity In Sqft/ Nos	Rate Per Sqft/ Nos In Rs.
1	<p>Replacement of fascia with Flex and Vinyl: Providing and fixing only fascia with flex and vinyl as per the specifications in the existing board structure after removing the old flex.</p>		
2	<p>Replacement of fascia with printed flex: Providing and fixing only fascia with printing on flex as per the specifications in the existing board structure after removing the old flex.</p>		
3	<p>Replacement of fascia with Biodegradable material: Providing and fixing only front fascia with Biodegradable Cotton Black back coated fabric Frontlit with Ultraviolet printing as per the specifications. The materials to be fixed/pasted in the existing flex board structure.</p>		
4	<p>Providing of New ACP Board with vinyl sticker: Providing and fixing of MS framework using 40mmx40mmx18G MS square tube section all round horizontal & vertical members at every 4' c/c with necessary brackets to fix to the building. Covering the frame work with 3mm thick ACP (Aluminium composite panel) with vinyl sticker as detailed in the technical specifications.</p>		
5	<p>Providing of New Backlit Signage Board: Providing and fixing back lit signage as per specifications mentioned in the bid including internal electrical fittings/wiring and external fasteners/anchoring as detailed in the technical specifications.</p>		

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

6	<p>Supplying and fixing LED flood lights of 30 Watt of Philips/ Wipro/ Crompton/ Bajaj makes for frontlit board with minimum 20"-30" length MS bracing of 25mmx25mmx18G square tubes coated with primer and finished with 2 coats of enamel paint.</p> <p>The qualities of lights shall vary as per board size.</p>		
	Total Amount (Sl No: 1 to 6)		

Notes:

- **The Lowest bidder will be finalised based on the total amount quoted for Sl: 01 to 06 based on the tentative quantities provided and also follows other terms & conditions as per 'Determination L1 bidder and award of work'.**
- Quantity given is approximate in sq ft and the Rate quoted should be in ` Per Sq ft in figures and words
- Bidder must take care in filling price information in the Price Offer, to ensure that there are no typographical or arithmetic errors. All blanks fields must be filled up correctly.

Name and Signature of Bidder with address and seal

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank
Across India In Region Wise under Rate Contract

PRICE BIDS IN SEPARATE ENVELOPE

ANNEXURE 14 (A)

PRICE BID OF NORTHERN REGION

Sl No	Item Description	Floor wise	Tentative Quantity In Sqft/ Nos	Rate Per Sqft/ Nos In Rs.
1	Replacement of fascia with Flex and Vinyl: Providing and fixing only fascia with flex and vinyl in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 02	Ground Floor	93600	
		First Floor	31200	
2	Replacement of fascia with printed flex: Providing and fixing only fascia with printing on flex s in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 04.	Ground Floor	15600	
		First Floor	5200	
3	Replacement of fascia with Biodegradable material: Providing and fixing only front fascia with Biodegradable Cotton Black back coated fabric Frontlit with Ultraviolet printing. The materials to be fixed/pasted in the existing flex board structure as per technical specification Sl no: 03.	Ground Floor	46800	
		First Floor	15600	
4	Providing of New ACP Board with vinyl sticker: Providing and fixing of MS framework using 40mmx40mmx18G MS square tube section all round horizontal & vertical members at	Ground Floor	15600	

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank
Across India In Region Wise under Rate Contract

	every 4' c/c with necessary brackets to fix to the building. Covering the frame work with 3mm thick ACP (Aluminium composite panel) with vinyl sticker as detailed in the technical specifications Sl No: 05.	First Floor	5200	
5	Providing of New Backlit Signage Board: Providing and fixing back lit signage board including internal electrical fittings/ wiring and external fasteners/anchoring as detailed in the technical specifications Sl No: 01, 1(A), 2 & 6.	Ground Floor	15600	
		First Floor	5200	
6	Supplying and fixing LED flood lights of 30 Watt of Philips/ Wipro/ Crompton/ Bajaj makes for frontlit board with minimum 20"-30" length MS bracing of 25mmx25mmx18G square tubes coated with primer and finished with 2 coats of enamel paint. The qualities of lights shall vary as per board size.		1700 Nos	
	Total Amount (Sl No: 1 to 6)			

Notes:

- **The Lowest bidder will be finalised based on the total amount quoted for Sl: 01 to 06 based on the tentative quantities provided and also follows other terms & conditions as per 'Determination L1 bidder and award of work'.**
- Quantity given is approximate in sq ft and the Rate quoted should be in ` Per Sq ft in figures and words
- Bidder must take care in filling price information in the Price Offer, to ensure that there are no typographical or arithmetic errors. All blanks fields must be filled up correctly.

Name and Signature of Bidder with address and seal

ANNEXURE 14 (B)

PRICE BID OF EASTERN REGION

Sl No	Item Description	Floor wise	Tentative Quantity In Sqft/ Nos	Rate Per Sqft/ Nos In Rs.
1	Replacement of fascia with Flex and Vinyl: Providing and fixing only fascia with flex and vinyl in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 02.	Ground Floor	56000	
		First Floor	18700	
2	Replacement of fascia with printed flex: Providing and fixing only fascia with printing on flex s in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 04.	Ground Floor	9300	
		First Floor	3100	
3	Replacement of fascia with Biodegradable material: Providing and fixing only front fascia with Biodegradable Cotton Black back coated fabric Frontlit with Ultraviolet printing. The materials to be fixed/pasted in the existing flex board structure as per technical specification Sl no: 03.	Ground Floor	28000	
		First Floor	9300	
4	Providing of New ACP Board with vinyl sticker: Providing and fixing of MS framework using 40mmx40mmx18G MS square tube section all round horizontal & vertical members at	Ground Floor	9300	

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank
Across India In Region Wise under Rate Contract

	every 4' c/c with necessary brackets to fix to the building. Covering the frame work with 3mm thick ACP (Aluminium composite panel) with vinyl sticker as detailed in the technical specifications Sl No: 05.	First Floor	3100	
5	Providing of New Backlit Signage Board: Providing and fixing back lit signage board including internal electrical fittings/ wiring and external fasteners/anchoring as detailed in the technical specifications Sl No: 01, 1(A), 2 & 6.	Ground Floor	9300	
		First Floor	3100	
6	Supplying and fixing LED flood lights of 30 Watt of Philips/ Wipro/ Crompton/ Bajaj makes for frontlit board with minimum 20"-30" length MS bracing of 25mmx25mmx18G square tubes coated with primer and finished with 2 coats of enamel paint. The qualities of lights shall vary as per board size.		1000 Nos	
	Total Amount (Sl No: 1 to 6)			

Notes:

- **The Lowest bidder will be finalised based on the total amount quoted for Sl: 01 to 06 based on the tentative quantities provided and also follows other terms & conditions as per 'Determination L1 bidder and award of work'.**
- Quantity given is approximate in sq ft and the Rate quoted should be in ` Per Sq ft in figures and words
- Bidder must take care in filling price information in the Price Offer, to ensure that there are no typographical or arithmetic errors. All blanks fields must be filled up correctly.

Name and Signature of Bidder with address and seal

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

ANNEXURE 14 (C)
PRICE BID OF WESTERN REGION

Sl No	Item Description	Floor wise	Tentative Quantity In Sqft/ Nos	Rate Per Sqft/ Nos In Rs.
1	Replacement of fascia with Flex and Vinyl: Providing and fixing only fascia with flex and vinyl in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 02.	Ground Floor	60000	
		First Floor	20000	
2	Replacement of fascia with printed flex: Providing and fixing only fascia with printing on flex s in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 04.	Ground Floor	10000	
		First Floor	3300	
3	Replacement of fascia with Biodegradable material: Providing and fixing only front fascia with Biodegradable Cotton Black back coated fabric Frontlit with Ultraviolet printing. The materials to be fixed/pasted in the existing flex board structure as per technical specification Sl no: 03.	Ground Floor	30000	
		First Floor	10000	
4	Providing of New ACP Board with vinyl sticker: Providing and fixing of MS framework using 40mmx40mmx18G MS square tube section all round horizontal & vertical members at every 4' c/c with necessary	Ground Floor	10000	

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

	brackets to fix to the building. Covering the frame work with 3mm thick ACP (Aluminium composite panel) with vinyl sticker as detailed in the technical specifications Sl No: 05.	First Floor	3300	
5	Providing of New Backlit Signage Board: Providing and fixing back lit signage board including internal electrical fittings/ wiring and external fasteners/anchoring as detailed in the technical specifications Sl No: 01, 1(A), 2 & 6.	Ground Floor	10000	
		First Floor	3300	
6	Supplying and fixing LED flood lights of 30 Watt of Philips/ Wipro/ Crompton/ Bajaj makes for frontlit board with minimum 20"-30" length MS bracing of 25mmx25mmx18G square tubes coated with primer and finished with 2 coats of enamel paint. The qualities of lights shall vary as per board size.		1100 Nos	
	Total Amount (Sl No: 1 to 6)			

Notes:

- **The Lowest bidder will be finalised based on the total amount quoted for Sl: 01 to 06 based on the tentative quantities provided and also follows other terms & conditions as per 'Determination L1 bidder and award of work'.**
- Quantity given is approximate in sq ft and the Rate quoted should be in ` Per Sq ft in figures and words
- Bidder must take care in filling price information in the Price Offer, to ensure that there are no typographical or arithmetic errors. All blanks fields must be filled up correctly.

Name and Signature of Bidder with address and seal

ANNEXURE 14 (D)
PRICE BID OF SOUTHERN - I REGION (KARNATAKA)

Sl No	Item Description	Floor wise	Tentative Quantity In Sqft/ Nos	Rate Per Sqft/ Nos In Rs.
1	Replacement of fascia with Flex and Vinyl: Providing and fixing only fascia with flex and vinyl in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 02.	Ground Floor	45400	
		First Floor	15100	
3	Replacement of fascia with printed flex: Providing and fixing only fascia with printing on flex s in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 04.	Ground Floor	22700	
		First Floor	7600	
2	Replacement of fascia with Biodegradable material: Providing and fixing only front fascia with Biodegradable Cotton Black back coated fabric Frontlit with Ultraviolet printing. The materials to be fixed/pasted in the existing flex board structure as per technical specification Sl no: 03.	Ground Floor	37800	
		First Floor	12600	
4	Providing of New ACP Board with vinyl sticker: Providing and fixing of MS framework using 40mmx40mmx18G MS square tube section all round horizontal & vertical members at every 4' c/c with necessary brackets to fix to the	Ground Floor	22700	

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

	building. Covering the frame work with 3mm thick ACP (Aluminium composite panel) with vinyl sticker as detailed in the technical specifications Sl No: 05.	First Floor	7600	
5	Providing of New Backlit Signage Board: Providing and fixing back lit signage board including internal electrical fittings/ wiring and external fasteners/anchoring as detailed in the technical specifications Sl No: 01, 1(A), 2 & 6.	Ground Floor	22700	
		First Floor	7600	
6	Supplying and fixing LED flood lights of 30 Watt of Philips/ Wipro/ Crompton/ Bajaj makes for frontlit board with minimum 20"-30" length MS bracing of 25mmx25mmx18G square tubes coated with primer and finished with 2 coats of enamel paint. The qualities of lights shall vary as per board size.		2400 Nos	
	Total Amount (Sl No: 1 to 6)			

Notes:

- **The Lowest bidder will be finalised based on the total amount quoted for Sl: 01 to 06 based on the tentative quantities provided and also follows other terms & conditions as per 'Determination L1 bidder and award of work'.**
- Quantity given is approximate in sq ft and the Rate quoted should be in ` Per Sq ft in figures and words
- Bidder must take care in filling price information in the Price Offer, to ensure that there are no typographical or arithmetic errors. All blanks fields must be filled up correctly.

Name and Signature of Bidder with address and seal

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

ANNEXURE 14 (E)
PRICE BID OF SOUTHERN - II REGION (ANDHRA PRADESH & TELANGANA)

Sl No	Item Description	Floor wise	Tentative Quantity In Sqft/ Nos	Rate Per Sqft/ Nos In Rs.
1	Replacement of fascia with Flex and Vinyl: Providing and fixing only fascia with flex and vinyl in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 02.	Ground Floor	45500	
		First Floor	15200	
3	Replacement of fascia with printed flex: Providing and fixing only fascia with printing on flex s in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 04.	Ground Floor	7600	
		First Floor	2500	
2	Replacement of fascia with Biodegradable material: Providing and fixing only front fascia with Biodegradable Cotton Black back coated fabric Frontlit with Ultraviolet printing. The materials to be fixed/pasted in the existing flex board structure as per technical specification Sl no: 03.	Ground Floor	22800	
		First Floor	7600	
4	Providing of New ACP Board with vinyl sticker: Providing and fixing of MS framework using 40mmx40mmx18G MS square tube section all round horizontal & vertical members at every 4' c/c with necessary	Ground Floor	7600	

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

	brackets to fix to the building. Covering the frame work with 3mm thick ACP (Aluminium composite panel) with vinyl sticker as detailed in the technical specifications Sl No: 05.	First Floor	2500	
5	Providing of New Backlit Signage Board: Providing and fixing back lit signage board including internal electrical fittings/ wiring and external fasteners/anchoring as detailed in the technical specifications Sl No: 01, 1(A), 2 & 6.	Ground Floor	7600	
		First Floor	2500	
6	Supplying and fixing LED flood lights of 30 Watt of Philips/ Wipro/ Crompton/ Bajaj makes for frontlit board with minimum 20"-30" length MS bracing of 25mmx25mmx18G square tubes coated with primer and finished with 2 coats of enamel paint. The qualities of lights shall vary as per board size.		800 Nos	
	Total Amount (Sl No: 1 to 6)			

Notes:

- **The Lowest bidder will be finalised based on the total amount quoted for Sl: 01 to 06 based on the tentative quantities provided and also follows other terms & conditions as per 'Determination L1 bidder and award of work'.**
- Quantity given is approximate in sq ft and the Rate quoted should be in ` Per Sq ft in figures and words
- Bidder must take care in filling price information in the Price Offer, to ensure that there are no typographical or arithmetic errors. All blanks fields must be filled up correctly.

Name and Signature of Bidder with address and seal

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

ANNEXURE 14 (F)
PRICE BID OF SOUTHERN - III REGION
(KERALA & TAMIL NADU AND UTS OF LAKSHADWEEP, PONDICHERRY AND ANDAMAN & NICOBAR)

Sl No	Item Description	Floor wise	Tentative Quantity In Sqft/ Nos	Rate Per Sqft/ Nos In Rs.
1	Replacement of fascia with Flex and Vinyl: Providing and fixing only fascia with flex and vinyl in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 02.	Ground Floor	70500	
		First Floor	23500	
3	Replacement of fascia with printed flex: Providing and fixing only fascia with printing on flex s in the existing board structure after removing the old flex as per technical specification Sl no: 01 & 04.	Ground Floor	11700	
		First Floor	3900	
2	Replacement of fascia with Biodegradable material: Providing and fixing only front fascia with Biodegradable Cotton Black back coated fabric Frontlit with Ultraviolet printing. The materials to be fixed/pasted in the existing flex board structure as per technical specification Sl no: 03.	Ground Floor	35200	
		First Floor	11700	
4	Providing of New ACP Board with vinyl sticker: Providing and fixing of MS framework using 40mmx40mmx18G MS square tube section all round horizontal & vertical members at every 4' c/c with necessary	Ground Floor	11700	

Tender Document for Providing External Sign Boards at Various Branches, ATMs and Offices Of Canara Bank Across India In Region Wise under Rate Contract

	brackets to fix to the building. Covering the frame work with 3mm thick ACP (Aluminium composite panel) with vinyl sticker as detailed in the technical specifications Sl No: 05.	First Floor	3900	
5	Providing of New Backlit Signage Board: Providing and fixing back lit signage board including internal electrical fittings/ wiring and external fasteners/anchoring as detailed in the technical specifications Sl No: 01, 1(A), 2 & 6.	Ground Floor	11700	
		First Floor	3900	
6	Supplying and fixing LED flood lights of 30 Watt of Philips/ Wipro/ Crompton/ Bajaj makes for frontlit board with minimum 20"-30" length MS bracing of 25mmx25mmx18G square tubes coated with primer and finished with 2 coats of enamel paint. The qualities of lights shall vary as per board size.		1200 Nos	
	Total Amount (Sl No: 1 to 6)			

Notes:

- The Lowest bidder will be finalised based on the total amount quoted for Sl: 01 to 06 based on the tentative quantities provided and also follows other terms & conditions as per 'Determination L1 bidder and award of work'.
- Quantity given is approximate in sq ft and the Rate quoted should be in ` Per Sq ft in figures and words
- Bidder must take care in filling price information in the Price Offer, to ensure that there are no typographical or arithmetic errors. All blanks fields must be filled up correctly.

Name and Signature of Bidder with address and seal